

Florida National Cemetery
Statement of Work for Golf Carts

Location: Florida National Cemetery
6502 SW 102nd Ave.
Bushnell, Florida 33513

Introduction:

Florida National Cemetery is in need of golf carts to support cemetery operations, events and assist customers. The vehicle is used to transport customers and visitors. At times, this equipment will be used on rough terrains. Golf carts have been leased on the past via service contracts. The price for this serve have increased to the point that is no longer fiscally beneficial to continue this practice.

Operator's manuals and mechanic's / maintenance manuals shall be provided for each vehicle.

6 Seater/gas - Features & Specifications:

- Color – Vendor shall provide color options prior to award
- Impact resistant Foldable windshield
- Frame: Welded tubular steel with DuraShield™ powder coating
- Dimensions 143.5" (L) x 48.5" (W) x 76.5" (H)
- Ground Clearance: 7.0in (18 cm) +
- Power Source: 4-cycle, 24.5 cu in (401 cc) low-emission
- Horsepower (kW): 13.5 hp (10 kW)
- Batteries (qty/type): one 12V Battery, maintenance free
- Air Cleaner: Replaceable dry cartridge
- Oil Filter: Spin-on
- Cooling System: Air-cooled
- Fuel Capacity: 5.8 gallons (22.0 L)
- All weather Seating -foldable seating w/ cargo deck-: 6-person
- Dry Weight: 970 lb (445 kg)
- Curb Weight: 1020 lb (465 kg)
- Speed (level ground): 16 mph ± 0.5 mph (25.7 kph ± 0.8 kph)
- Front Tires: Speed Racer 18 x 10.5-10 mounted on alloy wheel
- Rear Tires: Speed Racer 18 x 10.5-10 mounted on alloy wheel
- Street Legal – Includes Headlights, Taillights, Brake Lights, Turn Signals, and Side Mirrors

4 Seater/gas (Lifted) - Features & Specifications:

- Vendor Shall provide color options prior to award
- Lifted Golf Cart - Ground Clearance: 7.0in (18 cm) +
- Impact resistant Foldable windshield

Florida National Cemetery
Statement of Work for Golf Carts

- Engine: 13.5 hp (10.1 kW) Exceeds SAE J1940 Standard, 4 cycle, 24.5 ci (401 cc) single cylinder, air-cooled by Kawasaki
- Valve Train: Overhead valve
- Fuel System: Fixed float bowl with remote pulse fuel pump
- Lubrication: Pressurized oil system, spin-on oil filter
- Ignition: Electronic spark/magneto
- Balancer: Internal counter rotating balance shaft
- Air Cleaner: Replaceable dry cartridge
- Electrical: Starter/Generator, solid-state regulator, 12 Volt maintenance free battery (425 CCA, 60 minute reserve)
- Drive Train: Automatic, continuously variable transmission (CVT)
- Brakes: Dual rear wheel mechanical self-adjusting drum brakes. Automatic single point park brake release with self-compensating system
- Transaxle: Differential with helical gears, ground speed governor, forward/reverse
- All weather Seating -rear flip seat w/ cargo deck
- Capacity: Seating for 4 persons.
- Street Legal – Includes Headlights, Taillights, Brake Lights, Turn Signals, and Side Mirrors

4 Seater/electric - Features & Specifications:

- Color – Vendor shall provide color options prior to award
- Impact resistant Foldable windshield
- All weather Seating -rear flip seat w/ cargo deck 36 Volt Charger!
- Headlights/taillights
- 5 Panel Mirror
- State Of Charge Meter
- 20.5x8.0x10 Low Profile Tires
- 10" Medusa Rims
- St350 Steering Wheel
- 12volt Power Supply Outlet
- Street Legal – Includes Headlights, Taillights, Brake Lights, Turn Signals, and Side Mirrors