

VA Northern California Health Care System

2000 Concord Avenue
Chico, CA 95928

Modular Wall Panels

VA Northern California Health Care System

2000 Concord Avenue
Chico, CA 95928

U1020

Project: Chico VA Clinic

Total Quantity: 1

- ☒ Finish Sample Required if Checked ☒ Manufacturer Certified Installation Required if Checked
☐ BMET Training Required if Checked ☐ End User Training Required if Checked

Item Name: Wall, Panel, Demountable, With Glazing

Please Note: Picture is for reference only to illustrate the general design concept:

Salient Characteristics:

- Basis of Design: Environamics, Symbio
- U-Shape design
- Approximate Dimensions (+/-2"):
 - Width: 10'-6" - 11'-00"
 - Inside Depth: 2'-2" to 2'-4"
 - Height: 5'-8" *closest size to workstation panels specified at 5'-8"
- Panel Thickness: 2-3"
- Will have modular base cabinets at 36"H between side panels
- Provide power and data at 2 locations, equal spacing
 - 4 power and 4 data on each side
- Interchangeable panel type with standardized units which can be rearranged in any desired combination within a given wall space
- Can be extended in any direction without removing adjacent units (non-progressive).
- U-Shape design consisting of (2) end panels around 2'-3" deep
- Mounted over finished floor, carpet.
- Leveling guides
- Concealed fasteners
- Install shall not damage surrounding surface
- Double sided tape, Velcro, or other non-mechanical attachments are not acceptable

