

VAMC MONTROSE, NY

"MENTAL HEALTH AWE CORRECTIONS FOR BLDG.4 at
FDR"

PROJECT NO. 620-17-204

SECTION 09 06 00
SCHEDULE FOR FINISHES

SECTION 09 06 00-SCHEDULE FOR FINISHES

VAMC: Hudson Valley Healthcare System - Montrose FDR Campus
Location: Montrose, NY
Project no. and Name: 620-17-204 "Mental Health AWE Corrections for
Bldg. 4 at FDR"
Submission Date:

SECTION 09 06 00
SCHEDULE FOR FINISHES

PART I - GENERAL

1.1 DESCRIPTION

This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

1.2 MANUFACTURERS

Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer for finish requirements.

1.3 SUBMITALS

Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES—provide quadruplicate samples for color approval of materials and finishes specified in this section.

1.4 APPLICABLE PUBLICATIONS

- A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.
- B. MASTER PAINTING INSTITUTE: (MPI)
2001.....Architectural Painting Specification Manual

PART 2 EXECUTION

2.1 FINISH SCHEDULE SYMBOLS

<u>Symbol</u>	<u>Definition</u>
P	paint
ACT	Acoustical Ceiling Tile System
CFT	Ceramic Floor Tile
CBT	Ceramic base Tile
CWT	Ceramic Wall Tile

2.2 ROOM FINISH SCHEDULE

- A. Match adjoining or existing similar surfaces colors, textures or patterns where disturbed or damaged by alterations or new work when not scheduled.
- B. Provide finishes as specified in Room Finish Schedule below.

“MENTAL HEALTH AWE CORRECTIONS FOR BLDG.4 at FDR”

PROJECT NO. 620-17-204

ROOM NO. AND NAME	FLOOR AREA (SF)	PERIMETER OF WALL (LF)	CEILING HEIGHT (FT)	CEILING AREA (SF)	FLOOR	BASE	WALLS	CEILING	REMARKS
103 CONFERENCE ROOM		70	8'-6"	75			P	ACT	P: PRIME (1 COAT) AND PAINT (2 COATS) ALL WALLS IN ENTIRE ROOM AFTER NEW PARTITIONS ARE CONSTRUCTED. PAINT COLOR AND FINISH TO MATCH EXISTING. ACT: INSTALL NEW ACCOUSTICAL CEILING TILE SYSTEM (75 SF) TO EXTEND EXISTING CEILING SYSTEM TO NEW WALL. COLOR, FINISH, AND CONSTRUCTION OF NEW CEILING GRID AND TILE TO MATCH EXISTING.
103A CLOSET		18	8'-3"	18			P	P	P: TAPE, PATCH, SAND, PRIME (1 COAT), PAINT (2 COATS). WALL PAINT COLOR AND FINISH TO MATCH EXISTING. CEILING PAINT SHALL BE SHERWIN WILLIAMS PROMAR 200 FLAT INTERIOR LATEX PAINT.
105 TOILET	45	24	8'-6"	45	CFT	CBT	CWT	P	CFT: INSTALL 2" X 2" CERAMIC FLOOR TILE. CBT: INSTALL 2" X 2" CERAMIC COVE TILE. CWT: INSTALL 4" X 4" CERAMIC WALL TILE. CERAMIC FLOOR, COVE, AND WALL TILE SHALL BE DAL TILE WHITE COLOR, MATTE FINISH. P: PRIME (1 COAT) AND PAINT (2 COATS). CEILING PAINT SHALL BE SHERWIN WILLIAMS PROMAR 200 FLAT INTERIOR LATEX PAINT.
106 NURSE COMM CENTER		28	8'-6"	45			P	P	P: TAPE, PATCH, SAND, PRIME (1 COAT), PAINT (2 COATS). WALL PAINT COLOR AND FINISH TO MATCH EXISTING. CEILING PAINT SHALL BE SHERWIN WILLIAMS PROMAR 200 FLAT INTERIOR LATEX PAINT.
141 DAY ROOM				4200				P	P: PRIME (1 COAT) AND PAINT (2 COATS) ENTIRE CEILING (NEW AND EXISTING) IN DAY ROOM (4200 SF). CEILING PAINT SHALL BE SHERWIN WILLIAMS PROMAR 200 FLAT INTERIOR LATEX PAINT.
C1-10 NURSES STATION								P	P: PRIME (1 COAT) AND PAINT (2 COATS) ENTIRE CEILING (NEW AND EXISTING) IN NURSES STATION C1-10. CEILING PAINT SHALL BE SHERWIN WILLIAMS PROMAR 200 FLAT INTERIOR LATEX PAINT.
144 BEDROOM		52	8'-3"	175			P	P	P: PRIME (1 COAT) AND PAINT (2 COATS) ALL WALLS AND CEILING. WALL PAINT COLOR AND FINISH TO MATCH EXISTING. CEILING PAINT SHALL BE SHERWIN WILLIAMS PROMAR 200 FLAT INTERIOR LATEX PAINT.
144A WOMEN'S BATHROOM	55	38	8'-3"	55	CFT	CBT	CWT	P	CFT: INSTALL 2" X 2" CERAMIC FLOOR TILE. CBT: INSTALL 2" X 2" CERAMIC COVE TILE. CWT: INSTALL 4" X 4" CERAMIC WALL TILE. CERAMIC FLOOR, COVE, AND WALL TILE SHALL BE DAL TILE WHITE COLOR, MATTE FINISH. GWB: INSTALL GYPSUM WALL BOARD (USG WATER RESISTANT GREEN BOARD ON ALL WALLS AND USG FIRECODE X FOR CEILING). P: PRIME (1 COAT) AND PAINT (2 COATS) CEILING. CEILING PAINT SHALL BE SHERWIN WILLIAMS PROMAR 200 FLAT INTERIOR LATEX PAINT.
145 WOMEN'S LOUNGE		71	8'-3"	240			P	P	P: PRIME (1 COAT) AND PAINT (2 COATS) ALL WALLS AND CEILING. WALL PAINT COLOR AND FINISH TO MATCH EXISTING. CEILING PAINT SHALL BE SHERWIN WILLIAMS PROMAR 200 FLAT INTERIOR LATEX PAINT.
146B VESTIBULE		24	8'-3"	36			P	P	P: PRIME (1 COAT) AND PAINT (2 COATS) ALL WALLS AND CEILING. WALL PAINT COLOR AND FINISH TO MATCH EXISTING. CEILING PAINT SHALL BE SHERWIN WILLIAMS PROMAR 200 FLAT INTERIOR LATEX PAINT.
146C CLOSET		14	8'-3"	12			P	P	P: PRIME (1 COAT) AND PAINT (2 COATS) ALL WALLS AND CEILING. WALL PAINT COLOR AND FINISH TO MATCH EXISTING. CEILING PAINT SHALL BE SHERWIN WILLIAMS PROMAR 200 FLAT INTERIOR LATEX PAINT.
CORRIDOR				4200				P	P: PRIME (1 COAT) AND PAINT (2 COATS) ALL SHEETROCK CEILINGS (NEW AND EXISTING) IN CORRIDORS (4200 SF). CEILING PAINT SHALL BE SHERWIN WILLIAMS PROMAR 200 FLAT INTERIOR LATEX PAINT.
AREAS WHERE SPRINKLER HEADS ARE BEING REPLACED IN EXISTING SHEETROCK CEILING TO REMAIN				2500				P	P: PRIME (1 COAT) AND PAINT (2 COATS) 5' X 5' PATCH AT EACH LOCATION (100) WHERE EXISTING SHEETROCK CEILING IS REPAIRED. CEILING PAINT SHALL BE SHERWIN WILLIAMS. COLOR AND FINISH SHALL MATCH EXISTING CEILING PAINT.
<p>NOTE 1: ALL NEW METAL FRAMES FOR DOORS AND WINDOWS SHALL BE PRIMED AND PAINTED WITH SHERWIN WILLIAMS DTM PAINT WITH SEMI-GLOSS FINISH. ALL NEW ACCESS DOORS AND FRAMES SHALL BE PRIMED AND PAINTED WITH SHERWIN WILLIAMS DTM ACRYLIC PAINT. COLOR AND FINISH OF DTM PAINT FOR ACCESS DOOR AND FRAME IN CEILINGS SHALL MATCH COLOR AND PAINT OF NEW PAINT TO BE APPLIED TO CEILINGS BY CONTRACTOR. COLOR AND FINISH FOR ACCESS DOORS AND FRAMES IN WALLS SHALL MATCH COLOR AND FINISH OF NEW PAINT OR CERAMIC TILES TO BE APPLIED TO WALLS BY CONTRACTOR.</p> <p>NOTE 2: ALL AREA NUMBERS ARE ESTIMATED FOR BIDDING PURPOSES. CONTRACTOR SHALL VERIFY ACTUAL CONDITIONS WHEN ORDERING MATERIAL.</p>									

-- E N D --