

1. Contractor shall provide the necessary personnel and equipment to meet or exceed required service. Contractor shall have the following responsibilities:

~~Provide licensed and trained personnel to perform the project in the State of Florida.~~

Provide all supervision, labor and materials to complete all requirements described in this PWS.

Contractors shall be certified by the InterNational Electrical Testing Association (NETA) or equivalent certifying organization as certified technicians, with each having completed the Occupational Safety & Health Administration (OSHA) approved 10-hour Construction Outreach Training or General Industry Outreach Training.

Contractors shall have technical training and evident track records of working experience in Maintenance and Testing of electrical power distribution systems and related components in healthcare, industrial, educational, or commercial facilities for a minimum of five (5) years. Electrical components on which Contractors have experience shall include, but not be limited to, switchboards & switchgear (low and medium voltage), low voltage controls, oil filled disconnects, medium voltage distribution sub-stations, dry & oil filled transformers (medium voltage), switchgear circuit breakers (medium voltage), motor control centers, infrared thermographic inspections, arch flash testing, battery & battery charger inspections, ventilation inspections, external & internal enclosure inspections, calibration & functional checks, dielectric tests of oil, and other electrical appurtenances.

Contractors shall possess and utilize all necessary tools, equipment, and Personal Protective Equipment (PPE) to perform all work safely, effectively, and timely. Tools, equipment, and PPE shall comply with OSHA Standard 29 CFR 1910, (Subpart I), and NFPA 70E. Prior to initiating work, the Contractor shall provide documentation demonstrating that all instruments, test equipment, tools, and PPE possess current calibration and safety inspections. Dated calibration and safety inspection labels shall be visible on all equipment as applicable

Arrange and pay for all proper disposal of waste and debris.

Maintain project schedule agreed upon in the purchase order documents.

Provide all OSHA site safety for each employee during work.

Contractor employees shall have back ground checks completed.

2. Contractor's Minimum Requirement

The contractor shall follow Joint Commission and NFPA format for all reports

The contractor shall provide a dedicated Account Manager to supervise all delivery of services per scope.

Contractors shall comply with and have ready access to the latest versions of the references listed in section I.

The contractor shall be escorted by a VA employee at all times during Maintenance and Testing at all facilities.

E. DELIVERABLES

The Contractor shall perform the services necessary to complete the tasks in accordance with the procedures described in a timely and professional manner, consistent with industry standards, at the location, place and time that the VA has set aside, and all in accordance with the PWS.

Contractor shall provide a copy of the inspection document used (field report) on the day of each performed inspection. A completed final copy of all inspections per campus shall be provided to the COR within seven (7) days after the completion of inspections and shall include a complete inventory of tested devices and equipment. Each complete final inspection shall be delivered to the COR and shall be delivered in two formats: 1 each Hard Copy and 1 each Electronic Copy. The Hard Copy shall be