

Project Number 839-M&R18-21

Paint and Lighting Renovations

at the

Winchester National Cemetery

TECHNICAL SPECIFICATION SECTIONS AND DRAWINGS - TABLE OF CONTENTS

SPECIFICATION SECTIONS:

01 33 23	Shop Drawings, Product Data, and Samples
09 93 00	Paint for Exterior Metals
26 05 11	Requirements For Electrical Installations
26 56 00	Exterior Lighting

SECTION 01 33 23
SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES

- 1-1. Refer to Articles titled SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION (FAR 52.236-21) and, SPECIAL NOTES (VAAR 852.236-91), in GENERAL CONDITIONS.
- 1-2. For the purposes of this contract, samples including laboratory samples to be tested, test reports, certificates, and manufacturers' literature and data shall also be subject to the previously referenced requirements. The following text refers to all items collectively as SUBMITTALS.
- 1-3. Submit for approval, all of the items specifically mentioned under the separate sections of the specification, with information sufficient to evidence full compliance with contract requirements. Materials, fabricated articles and the like to be installed in permanent work shall equal those of approved submittals. Submit to the COR, Project Engineer, and carbon copy the Contracting Officer on all submittals. After an item has been approved, no change in brand or make will be permitted unless:
 - A. Satisfactory written evidence is presented to, and approved by Contracting Officer, that manufacturer cannot make scheduled delivery of approved item or;
 - B. Item delivered has been rejected and substitution of a suitable item is an urgent necessity or;
 - C. Other conditions become apparent which indicates approval of such substitute item to be in best interest of the Government.
- 1-4. Forward submittals in sufficient time to permit proper consideration and approval action by Government. Time submission to assure adequate lead time for procurement of contract - required items. Delays attributable to untimely and rejected submittals including any laboratory samples to be tested will not serve as a basis for extending contract time for completion.
- 1-5. Submittals shall be reviewed for compliance with contract requirements by Architect-Engineer (for work items designated as "Design Build Elements", hired by contractor), and action thereon will be taken by COR and Project Engineer on behalf of the Contracting Officer. For

items which are not "Design Build Elements", the COR and Project Engineer will jointly review for approval.

- 1-6. Upon receipt of submittals, the COR and Project Engineer will assign a file number thereto. Contractor, in any subsequent correspondence, shall refer to this file and identification number to expedite replies relative to previously approved or disapproved submittals.
- 1-7. The Government reserves the right to require additional submittals, whether or not particularly mentioned in this contract. If additional submittals beyond those required by the contract are furnished pursuant to request therefor by Contracting Officer, adjustment in contract price and time will be made in accordance with Articles titled CHANGES (FAR 52.243-4) and CHANGES - SUPPLEMENT (VAAR 852.236-88) of the GENERAL CONDITIONS.
- 1-8. Schedules called for in specifications and shown on shop drawings shall be submitted for use and information of Department of Veterans Affairs and Architect-Engineer. However, the Contractor shall assume responsibility for coordinating and verifying schedules. The Contracting Officer assumes no responsibility for checking schedules or layout drawings for exact sizes, exact numbers and detailed positioning of items.
- 1-9. Submittals must be submitted by Contractor only and shipped prepaid. Contracting Officer assumes no responsibility for checking quantities or exact numbers included in such submittals. Electronic submittals will be permitted for product data, but submissions of samples, drawings and other items will require hard copy.
 - A. Submit samples in single units unless otherwise specified. Submit shop drawings, schedules, manufacturers' literature and data, and certificates in quadruplicate, except where a greater number is specified.
 - B. Submittals will receive consideration only when covered by a transmittal letter signed by Contractor. Letter shall be sent via first class mail and shall contain the list of items, name of Cemetery, name of Contractor, contract number, applicable specification paragraph numbers, applicable drawing numbers (and other information required for exact identification of location for each item), manufacturer and brand, ASTM or Federal Specification Number (if any) and such

additional information as may be required by specifications for particular item being furnished. In addition, catalogs shall be marked to indicate specific items submitted for approval.

1. A copy of letter must be enclosed with items, and any items received without identification letter will be considered "unclaimed goods" and held for a limited time only.
2. Each sample, certificate, manufacturers' literature and data shall be labeled to indicate the name and location of the Cemetery, name of Contractor, manufacturer, brand, contract number and ASTM or Federal Specification Number as applicable and location(s) on project.
3. Required certificates shall be signed by an authorized representative of manufacturer or supplier of material, and by Contractor.

C. In addition to complying with the applicable requirements specified in preceding Article 1.9, samples which are required to have Laboratory Tests (those preceded by symbol "LT" under the separate sections of the specification shall be tested, at the expense of Contractor, in a commercial laboratory approved by Contracting Officer.

1. Laboratory shall furnish Contracting Officer with a certificate stating that it is fully equipped and qualified to perform intended work, is fully acquainted with specification requirements and intended use of materials and is an independent establishment in no way connected with organization of Contractor or with manufacturer or supplier of materials to be tested.
2. Certificates shall also set forth a list of comparable projects upon which laboratory has performed similar functions during past five years.
3. Samples and laboratory tests shall be sent directly to approved commercial testing laboratory.
4. Contractor shall send a copy of transmittal letter to both COR and to Architect-Engineer simultaneously with submission of material to a commercial testing laboratory.
- 4b. Contractor shall forward a copy of transmittal letter to COR simultaneously with submission to a commercial testing laboratory.
5. Laboratory test reports shall be sent directly to COR for appropriate action.

6. Laboratory reports shall list contract specification test requirements and a comparative list of the laboratory test results. When tests show that the material meets specification requirements, the laboratory shall so certify on test report.
 7. Laboratory test reports shall also include a recommendation for approval or disapproval of tested item.
- D. If submittal samples have been disapproved, resubmit new samples as soon as possible after notification of disapproval. Such new samples shall be marked "Resubmitted Sample" in addition to containing other previously specified information required on label and in transmittal letter.
- E. Approved samples will be kept on file by the COR at the site until completion of contract, at which time such samples will be delivered to Contractor as Contractor's property. Where noted in technical sections of specifications, approved samples in good condition may be used in their proper locations in contract work. At completion of contract, samples that are not approved will be returned to Contractor only upon request and at Contractor's expense. Such request should be made prior to completion of the contract. Disapproved samples that are not requested for return by Contractor will be discarded after completion of contract.
- F. Submittal drawings (shop, erection or setting drawings) and schedules, required for work of various trades, shall be checked before submission by technically qualified employees of Contractor for accuracy, completeness and compliance with contract requirements. These drawings and schedules shall be stamped and signed by Contractor certifying to such check.
1. For each drawing required, submit one legible photographic paper or vellum reproducible.
 2. Reproducible shall be full size.
 3. Each drawing shall have marked thereon, proper descriptive title, including Cemetery location, project number, manufacturer's number, reference to contract drawing number, detail Section Number, and Specification Section Number.
 4. A space 120 mm by 125 mm (4-3/4 by 5 inches) shall be reserved on each drawing to accommodate approval or disapproval stamp.
 5. Submit drawings, ROLLED WITHIN A MAILING TUBE, fully protected for shipment.

6. One reproducible print of approved or disapproved shop drawings will be forwarded to Contractor.
7. When work is directly related and involves more than one trade, shop drawings shall be submitted to Architect-Engineer under one cover.
- 1-10. Samples, shop drawings, test reports, certificates and manufacturers' literature and data, shall be submitted for approval to the contractor's hired Architect-Engineering firm (also discussed in these specifications as Professional Design firm).
- 1-11. Samples for approval shall be sent to COR. Coordinate address for shipment with the COR, or deliver in person.

- - - E N D - - -

**SECTION 09 93 00
PAINTING FOR EXTERIOR METALS**

PART 1-GENERAL

1.1 DESCRIPTION

- A. Section specifies field painting for existing flagpoles, gates, and other metal items, and related appurtenances such as their bases.

1.2 RELATED WORK

- A. NA

1.3 SUSTAINABILITY REQUIREMENTS

- A. Materials in this section may contribute towards contract compliance with sustainability requirements.
- B. Biobased Material: For products designated by the USDA's BioPreferred® program, provide products that meet or exceed USDA recommendations for biobased content, subject to the products compliance with performance requirements in this Section. For more information regarding the product categories covered by the BioPreferred® program, visit <http://www.biopreferred.gov>.

1.4 REGULATORY REQUIREMENTS FOR RECYCLED CONTENT

- A. Products and Materials with Post-Consumer Content and Recovered Materials Content:
 - 1. Contractor is obligated by contract to satisfy Federal mandates for procurement of products and materials meeting recommendations for post-consumer content and recovered materials content; the list of designated product categories with recommendations has been compiled by the EPA - refer to <http://www.epa.gov/wastes/conserve/tools/cpg/products/>.
 - 2. Materials or products specified by this section may be obligated to satisfy this Federal mandate and Comprehensive Procurement Guidelines program.
 - 3. The EPA website also provides tools such as a Product Supplier Directory search engine and product resource guides.

1.5 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's Literature and Data:
 - 1. Before work is started, or sample panels are prepared, submit manufacturer's literature, the current Master Painters Institute (MPI) "Approved Product List" indicating brand label, product name

and product code as of the date of contract award, will be used to determine compliance with the submittal requirements of this specification. The Contractor may choose to use subsequent MPI "Approved Product List", however, only one list may be used for the entire contract and each coating system is to be from a single manufacturer. All coats on a particular substrate must be from a single manufacturer. No variation from the MPI "Approved Product List" where applicable is acceptable.

C. Samples:

1. After painters' materials have been approved and before work is started submit samples showing each type of finish and color specified.
2. Samples to show color: Composition board, 150 by 150 (6 inch by 6 inch).
3. Panel to show transparent finishes: Wood of same species and grain pattern as wood approved for use, 100 by 250 by 3 mm (4 inch by 10 inch face by 1/4 inch) thick minimum, and where both flat and edge grain will be exposed, 250 mm (10 inches) long by sufficient size, 50 by 50 mm (2 by 2 inch) minimum or actual wood member to show complete finish.

D. Manufacturers' Certificates indicating compliance with specified requirements:

1. Manufacturer's paint substituted for Federal Specification paints meets or exceeds performance of paint specified.
2. High temperature aluminum paint.
3. Epoxy coating.

E. Manufacturer's letter of recommendation:

1. Provide a letter addressed to the National Cemetery Administration from the manufacturer of the paint/coating, detailing their understanding of the substrate to be painted, preparations required before painting, the application, and the national shrine aesthetically-pleasing appearance expected of the finished product. This letter shall be signed by a "Paint Specialist" or other approved equal or greater qualifications.

1.6 DELIVERY AND STORAGE

A. Deliver materials to site in manufacturer's sealed container marked to show following:

1. Name of manufacturer.

2. Product type.
 3. Batch number.
 4. Instructions for use.
 5. Safety precautions.
- B. In addition to manufacturer's label, provide a label legibly printed as following:
1. Federal Specification Number, where applicable, and name of material.
 2. Surface upon which material is to be applied.
 3. If paint or other coating, state coat types; prime, body or finish.
- C. Maintain space for storage, and handling of painting materials and equipment in a neat and orderly condition to prevent spontaneous combustion from occurring or igniting adjacent items.
- D. Store materials at site at least 24 hours before using, at a temperature between 18 and 30 degrees C (65 and 85 degrees F).

1.7 APPLICABLE PUBLICATIONS

- A. Publications listed below form a part of this specification to extent referenced. Publications are referenced in text by the basic designation only. Comply with applicable provisions and recommendations of the following, except as otherwise shown or specified.
- B. American Conference of Governmental Industrial Hygienists (ACGIH):
- | | |
|---------------------|---|
| ACGIH TLV-BKLT-2009 | Threshold Limit Values (TLV) for Chemical Substances and Physical Agents and Biological Exposure Indices (BEIs) |
| ACGIH TLV-DOC-2009 | Documentation of Threshold Limit Values and Biological Exposure Indices, (Seventh Edition) |
- C. Master Painters Institute (MPI): Submitted product data shall indicate compatibility with the corresponding MPI standard.
- D. Steel Structures Painting Council (SSPC):
- | | |
|--------------|---------------------|
| SSPC SP 1-04 | Solvent Cleaning |
| SSPC SP 2-04 | Hand Tool Cleaning |
| SSPC SP 3-04 | Power Tool Cleaning |

PART 2 - PRODUCTS

2.1 MATERIALS

- A.

2.2 PAINT PROPERTIES

- A. Use ready-mixed (including colors), except two component epoxies, polyurethanes, polyesters, paints having metallic powders packaged separately and paints requiring specified additives.
- B. Where no requirements are given in the referenced specifications for primers, use primers with pigment and vehicle, compatible with substrate and finish coats specified.

2.3 REGULATORY REQUIREMENTS

- A. Paint materials must conform to the restrictions of the local Environmental and Toxic Control jurisdiction or the requirements of this section, whichever is most stringent.
 - 1. Lead-Based Paint:
 - a. Lead based paint is not permitted to be used.
 - 2. Asbestos: Materials must not contain asbestos.
 - 3. Chromate, Cadmium, Mercury, and Silica: Materials must not contain zinc-chromate, strontium-chromate, Cadmium, mercury or mercury compounds or free crystalline silica.
 - 4. Human Carcinogens: Materials must not contain any of the ACGIH-BKLT and ACGHI-DOC confirmed or suspected human carcinogens.
 - 5. Use high performance acrylic paints in place of alkyd paints, where possible.
 - 6. VOC content for solvent-based paints must not exceed specified performance requirement; aromatic hydro carbons contained in solvent-based paints must not exceed one percent by weight.

PART 3 - EXECUTION

3.1 JOB CONDITIONS

- A. Safety: Observe required safety regulations and manufacturer's warning and instructions for storage, handling and application of painting materials.
 - 1. Take necessary precautions to protect personnel and property from hazards due to falls, injuries, toxic fumes, fire, explosion, or other harm.
 - 2. Deposit soiled cleaning rags and waste materials in metal containers approved for that purpose. Dispose of such items off the site at end of each day's work.
- B. Atmospheric and Surface Conditions:
 - 1. Do not apply coating when air or substrate conditions are:
 - a. Less than 3 degrees C (5 degrees F) above dew point.

- b. Below 10 degrees C (50 degrees F) or over 35 degrees C (95 degrees F), unless specifically pre-approved by the Contracting Officer and the product manufacturer.
- 2. Do not exceed application conditions recommended by the manufacturer.
- 3. Maintain interior temperatures until paint dries hard.
- 4. Do no exterior painting when it is windy and dusty.
- 5. Do not paint in direct sunlight or on surfaces that the sun will soon warm.
- 6. Apply only on clean, dry and frost free surfaces except as follows:
 - a. Apply water thinned acrylic and cementitious paints to damp (not wet) surfaces where allowed by manufacturer's printed instructions.
 - b. Dampened with a fine mist of water on hot dry days concrete and masonry surfaces to which water thinned acrylic and cementitious paints are applied to prevent excessive suction and to cool surface.
- 7. Varnishing:
 - a. Apply in clean areas and in still air.
 - b. Before varnishing vacuum and dust area.
 - c. Immediately before varnishing wipe down surfaces with a tack rag.

3.2 SURFACE PREPARATION

- A. Method of surface preparation is optional, provided results of finish painting produce solid even color and texture specified with no overlays.
- B. General:
 - 1. Remove prefinished items not to be painted such as lighting fixtures, escutcheon plates, hardware, trim, and similar items for reinstallation after paint is dried.
 - 2. Remove items for reinstallation and complete painting of such items and adjacent areas when item or adjacent surface is not accessible or finish is different.
 - 3. See other sections of specifications for specified surface conditions and prime coat.
 - 4. Clean surfaces for painting with materials and methods compatible with substrate and specified finish. Remove any residue remaining from cleaning agents used. Do not use solvents, acid, or steam on concrete and masonry.

C. Ferrous Metals:

1. Remove oil, grease, soil, drawing and cutting compounds, flux and other detrimental foreign matter in accordance with SSPC-SP 1 (Solvent Cleaning).
2. Remove loose mill scale, rust, and paint, by hand or power tool cleaning, as defined in SSPC-SP 2 (Hand Tool Cleaning) and SSPC-SP 3 (Power Tool Cleaning). Exception: where high temperature aluminum paint is used, prepare surface in accordance with paint manufacturer's instructions.
3. Fill dents, holes and similar voids and depressions in flat exposed surfaces of hollow steel doors and frames, access panels, roll-up steel doors and similar items specified to have semi-gloss or gloss finish with TT-F-322D (Filler, Two-Component Type, For Dents, Small Holes and Blow-Holes). Finish flush with adjacent surfaces.
 - a. This includes flat head countersunk screws used for permanent anchors.
 - b. Do not fill screws of item intended for removal such as glazing beads.
4. Spot prime abraded and damaged areas in shop prime coat which expose bare metal with same type of paint used for prime coat. Feather edge of spot prime to produce smooth finish coat.
5. Spot prime abraded and damaged areas which expose bare metal of factory finished items with paint as recommended by manufacturer of item.

D. Zinc-Coated (Galvanized) Metal, Aluminum, Copper and Copper Alloys Surfaces Specified Painted:

1. Clean surfaces to remove grease, oil and other deterrents to paint adhesion in accordance with SSPC-SP 1 (Solvent Cleaning).
2. Spot coat abraded and damaged areas of zinc-coating which expose base metal on hot-dip zinc-coated items with Organic Zinc Rich Coating. Prime or spot prime with the submitted/approved primer.

E. Masonry, Concrete, Cement Board, Cement Plaster and Stucco:

1. Clean and remove dust, dirt, oil, grease efflorescence, form release agents, laitance, and other deterrents to paint adhesion.
2. Use emulsion type cleaning agents to remove oil, grease, paint and similar products. Use of solvents, acid, or steam is not permitted.
3. Remove loose mortar in masonry work.

4. Replace mortar and fill open joints, holes, cracks and depressions with new mortar.
5. Neutralize Concrete floors to be painted by washing with a solution of 1.4 Kg (3 pounds) of zinc sulfate crystals to 3.8 L (1 gallon) of water, allow to dry three days and brush thoroughly free of crystals.
6. Repair broken and spalled concrete edges with concrete patching compound to match adjacent surfaces as specified in CONCRETE Sections. Remove projections to level of adjacent surface by grinding or similar methods.

3.3 PAINT PREPARATION

- A. Thoroughly mix painting materials to ensure uniformity of color, complete dispersion of pigment and uniform composition.
- B. Do not thin unless necessary for application and when finish paint is used for body and prime coats. Use materials and quantities for thinning as specified in manufacturer's printed instructions.
- C. Remove paint skins, then strain paint through commercial paint strainer to remove lumps and other particles.
- D. Mix two component and two part paint and those requiring additives in such a manner as to uniformly blend as specified in manufacturer's printed instructions unless specified otherwise.
- E. For tinting required to produce exact shades specified, use color pigment recommended by the paint manufacturer.

3.4 APPLICATION

- A. Limited touch up in the field will be permitted by NCA. Start of surface preparation or painting will be construed as acceptance of the surface as satisfactory for the application of materials.
- B. Unless otherwise specified, apply paint in three coats; prime, body, and finish. When two coats applied to prime coat are the same, first coat applied over primer is body coat and second coat is finish coat.
- C. Apply each coat evenly and cover substrate completely.
- D. Allow not less than 48 hours between application of succeeding coats, except as allowed by manufacturer's printed instructions, and approved by RE/COR.
- E. Finish surfaces to show solid even color, free from runs, lumps, brush marks, laps, holidays, or other defects.
- F. Apply by brush or roller, except as otherwise specified. No spray painting will be permitted at the project location.

- H. Do not paint in closed position operable items such as access doors and panels, window sashes, overhead doors, and similar items except overhead roll-up doors and shutters.

3.5 PRIME PAINTING

- A. After surface preparation, prime surfaces before application of body and finish coats, except as otherwise specified.
- B. Spot prime and apply body coat to damaged and abraded painted surfaces before applying succeeding coats.
- C. Additional field applied prime coats over shop or factory applied prime coats are not required except for exterior exposed steel. Apply an additional prime coat.
- D. Prime rebates for face glazing of steel.
- F. Steel/Aluminum/Galvanized:
 - 1. Use an epoxy-based primer.
 - a. Paint shall be a high solids, high build, fast drying polyamide epoxy designed to protect steel in industrial exposures.
 - b. Low VOC.
 - c. Must pass ASTM D4587, QUV-A 12,000 hours for Accelerated Weathering-QUV test.
 - d. Corrosion Weathering: Must achieve a minimum rating of 10 per ASTM D714 for blistering, and a minimum rating of 9 per ASTM D610 for rusting. Tested per ASTM D5894, 36 cycles, 12,000 hours.
 - e. Humidity Resistance: No blistering, cracking or rusting when tested per ASTM D4585 for 6,000 hours.
- G. Concrete and Masonry Units:
 - 1. Use an epoxy block filler.
 - a. Paint shall be a high performance, exterior, low VOC, epoxy block filler.
 - b. Humidity Resistance: Must pass ASTM D2247 100F test for 1,000 hours with no blistering or loss of adhesion.
 - c. Adhesion: Must pass ASTM D3359, Method B with minimum results per 5B of 100% retention.

3.6 EXTERIOR FINISHES

- A. Apply following finish coats where specified.
- B. Steel and Ferrous Metal, Galvanized, Aluminum, and Concrete/Masonry:
 - 1. Two coats of high performance acrylic polyurethane coating.
 - a. Shall be specifically designed to provide long term UV protection for high visibility structures.

- b. Corrosion Weathering: Must achieve a minimum rating of 10 per ASTM D714 for blistering, and a minimum rating of 10 per ASTM D610 for rusting. Tested per ASTM D5894, minimum 30 cycles, 12,000 hours.
- c. Salt Water and Fresh Water Resistances: Both Pass ASTM D870, 30 days.
- d. Thermal Cycling: Must achieve minimum rating of Excellent tested per ASTM 2246, 10 cycles.

3.8 REFINISHING EXISTING PAINTED SURFACES

- A. Clean, patch and repair existing surfaces as specified under surface preparation.
- B. Remove and reinstall items as specified under surface preparation.
- C. Remove existing finishes or apply separation coats to prevent non-compatible coatings from having contact.
- D. Patched or Replaced Areas in Surfaces and Components: Apply spot prime and body coats as specified for new work to repaired areas or replaced components.
- E. Except where scheduled for complete painting apply finish coat over plane surface to nearest break in plane, such as corner, reveal, or frame.
- F. In existing rooms and areas where alterations occur, clean existing stained and natural finished wood retouch abraded surfaces and then give entire surface one coat of or Polyurethane, Moisture Cured, Clear Gloss or Polyurethane, Moisture Cured, Clear Flat (PV) or.
- G. Refinish areas as specified for new work to match adjoining work unless specified or scheduled otherwise.
- H. Coat knots and pitch streaks showing through old finish with Knot Sealer before refinishing.
- I. Sand or dull glossy surfaces prior to painting.
- J. Sand existing coatings to a feather edge so that transition between new and existing finish will not show in finished work.
- K. Perform any surface preparation recommended by submitted/approved product installation literature as required by manufacturer.

3.9 PAINT COLOR

- A. Color and gloss of finish coats is by COR. Finish color to match existing, with the understanding that often the existing color is faded from years of weathering.

B. For additional requirements regarding color see Articles, REFINISHING EXISTING PAINTED SURFACE and MECHANICAL AND ELECTRICAL FIELD PAINTING SCHEDULE.

C. Coat Colors:

1. Color of priming coat: Lighter than body coat.
2. Color of body coat: Lighter than finish coat.
3. Color prime and body coats to not show through the finish coat and to mask surface imperfections or contrasts.

3.10 PROTECTION CLEAN UP, AND TOUCH-UP

- A. Protect work from paint droppings and spattering by use of masking, drop cloths, removal of items or by other approved methods.
- B. Upon completion, clean paint from hardware, glass and other surfaces and items not required to be painted of paint drops or smears.
- C. Before final inspection, touch-up or refinished in a manner to produce solid even color and finish texture, free from defects in work which was damaged or discolored.

- - - E N D - - -

SECTION 26 05 11
REQUIREMENTS FOR ELECTRICAL INSTALLATIONS

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, applies to all sections of Division 26.
- B. Furnish and install electrical wiring, systems, equipment and accessories in accordance with the specifications and drawings. Capacities and ratings of motors, transformers, cable, switchboards, switchgear, panelboards, and other items and arrangements for the specified items are shown on drawings.
- C. Electrical service entrance equipment (arrangements for temporary and permanent connections to the power company's system) shall conform to the power company's requirements. Coordinate fuses, circuit breakers and relays with the power company's system, and obtain power company approval for sizes and settings of these devices.
- D. Wiring ampacities specified or shown on the drawings are based on copper conductors, with the conduit and raceways accordingly sized. Aluminum conductors are prohibited.

1.2 MINIMUM REQUIREMENTS

- A. References to the National Electrical Code (NEC), Underwriters Laboratories, Inc. (UL) and National Fire Protection Association (NFPA) are minimum installation requirement standards. Contractor shall follow the latest versions of the codes listed herein, based on the date of the signed contract.
- B. Drawings and other specification sections shall govern in those instances where requirements are greater than those specified in the above standards.

1.3 TEST STANDARDS

- A. All materials and equipment shall be listed, labeled or certified by a nationally recognized testing laboratory to meet Underwriters Laboratories, Inc., standards where test standards have been established. Equipment and materials which are not covered by UL Standards will be accepted provided equipment and material is listed, labeled, certified or otherwise determined to meet safety requirements of a nationally recognized testing laboratory. Equipment of a class which no nationally recognized testing laboratory accepts, certifies, lists, labels, or determines to be safe, will be considered if inspected or tested in accordance with national industrial standards, such as

NEMA, or ANSI. Evidence of compliance shall include certified test reports and definitive shop drawings.

B. Definitions:

1. Listed; equipment or device of a kind mentioned which:
 - a. Is published by a nationally recognized laboratory which makes periodic inspection of production of such equipment.
 - b. States that such equipment meets nationally recognized standards or has been tested and found safe for use in a specified manner.
2. Labeled; equipment or device is when:
 - a. It embodies a valid label, symbol, or other identifying mark of a nationally recognized testing laboratory such as Underwriters Laboratories, Inc.
 - b. The laboratory makes periodic inspections of the production of such equipment.
 - c. The labeling indicates compliance with nationally recognized standards or tests to determine safe use in a specified manner.
3. Certified; equipment or product is which:
 - a. Has been tested and found by a nationally recognized testing laboratory to meet nationally recognized standards or to be safe for use in a specified manner.
 - b. Production of equipment or product is periodically inspected by a nationally recognized testing laboratory.
 - c. Bears a label, tag, or other record of certification.
4. Nationally recognized testing laboratory; laboratory which is approved, in accordance with OSHA regulations, by the Secretary of Labor.

1.4 QUALIFICATIONS (PRODUCTS AND SERVICES)

- A. Manufacturers Qualifications: The manufacturer shall regularly and presently produce, as one of the manufacturer's principal products, the equipment and material specified for this project, and shall have manufactured the item for at least three years.
- B. Product Qualification:
 1. Manufacturer's product shall have been in satisfactory operation, on three installations of similar size and type as this project, for approximately three years.
 2. The Government reserves the right to require the Contractor to submit a list of installations where the products have been in operation before approval.
- C. Service Qualifications: There shall be a permanent service organization maintained or trained by the manufacturer which will render satisfactory service to this installation within four hours of receipt of

notification that service is needed. Submit name and address of service organizations.

1.5 MANUFACTURED PRODUCTS

- A. Materials and equipment furnished shall be of current production by manufacturers regularly engaged in the manufacture of such items, for which replacement parts shall be available.
- B. When more than one unit of the same class of equipment is required, such units shall be the product of a single manufacturer.
- C. Equipment Assemblies and Components:
 - 1. Components of an assembled unit need not be products of the same manufacturer.
 - 2. Manufacturers of equipment assemblies, which include components made by others, shall assume complete responsibility for the final assembled unit.
 - 3. Components shall be compatible with each other and with the total assembly for the intended service.
 - 4. Constituent parts which are similar shall be the product of a single manufacturer.
- D. Factory wiring shall be identified on the equipment being furnished and on all wiring diagrams.
- E. When Factory Testing Is Specified:
 - 1. The Government shall have the option of witnessing factory tests. The contractor shall notify the VA through the COTR/Resident Engineer a minimum of 15 working days prior to the manufacturers making the factory tests.
 - 2. Four copies of certified test reports containing all test data shall be furnished to the Resident Engineer prior to final inspection and not more than 90 days after completion of the tests.
 - 3. When equipment fails to meet factory test and re-inspection is required, the contractor shall be liable for all additional expenses, including expenses of the Government.

1.6 EQUIPMENT REQUIREMENTS

- A. Where variations from the contract requirements are requested in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES, the connecting work and related components shall include, but not be limited to additions or changes to branch circuits, circuit protective devices, conduits, wire, feeders, controls, panels and installation methods.

1.7 EQUIPMENT PROTECTION

- A. Equipment and materials shall be protected during shipment and storage against physical damage, dirt, moisture, cold and rain:

1. During installation, enclosures, equipment, controls, controllers, circuit protective devices, and other like items, shall be protected against entry of foreign matter; and be vacuum cleaned both inside and outside before testing and operating and repainting if required.
2. Damaged equipment shall be, as determined by the COTR/Resident Engineer, placed in first class operating condition or be returned to the source of supply for repair or replacement.
3. Painted surfaces shall be protected with factory installed removable heavy kraft paper, sheet vinyl or equal.
4. Damaged paint on equipment and materials shall be refinished with the same quality of paint and workmanship as used by the manufacturer so repaired areas are not obvious.

1.8 WORK PERFORMANCE

- A. All electrical work must comply with the requirements of NFPA 70 (NEC), NFPA 70B, NFPA 70E, OSHA Part 1910 subpart J, OSHA Part 1910 subpart S and OSHA Part 1910 subpart K in addition to other references required by contract.
- B. Job site safety and worker safety is the responsibility of the contractor.
- C. Electrical work shall be accomplished with all affected circuits or equipment de-energized. When an electrical outage cannot be accomplished in this manner for the required work, the following requirements are mandatory:
 1. Electricians must use full protective equipment (i.e., certified and tested insulating material to cover exposed energized electrical components, certified and tested insulated tools, etc.) while working on energized systems in accordance with NFPA 70E.
 2. Electricians must wear personal protective equipment while working on energized systems in accordance with NFPA 70E.
 3. Before initiating any work, a job specific work plan must be developed by the contractor with a peer review conducted and documented by the COTR/Resident Engineer. The work plan must include procedures to be used on and near the live electrical equipment, barriers to be installed, safety equipment to be used and exit pathways.
- D. For work on existing stations, arrange, phase and perform work to assure electrical service for other buildings at all times.
- E. New work shall be installed and connected to existing work neatly and carefully. Disturbed or damaged work shall be replaced or repaired to its prior conditions.

- F. Coordinate location of equipment and conduit with other trades to minimize interferences.

1.9 EQUIPMENT INSTALLATION AND REQUIREMENTS

- A. Equipment location shall be as close as practical to locations shown on the drawings.
- B. Working spaces shall not be less than specified in the NEC for all voltages specified.
- C. Inaccessible Equipment:
 - 1. Where the Government determines that the Contractor has installed equipment not conveniently accessible for operation and maintenance, the equipment shall be removed and reinstalled as directed at no additional cost to the Government.
 - 2. "Conveniently accessible" is defined as being capable of being reached without the use of ladders, or without climbing or crawling under or over obstacles such as, but not limited to, motors, pumps, belt guards, transformers, piping, ductwork, conduit and raceways.

1.10 EQUIPMENT IDENTIFICATION

- A. In addition to the requirements of the NEC, install an identification sign which clearly indicates information required for use and maintenance of items such as panelboards, cabinets, motor controllers (starters), safety switches, separately enclosed circuit breakers, individual breakers and controllers in switchboards, switchgear, control devices and other significant equipment.
- B. Nameplates shall be laminated black phenolic resin with a white core with engraved lettering, a minimum of 6 mm (1/4 inch) high. Secure nameplates with screws. Nameplates that are furnished by manufacturer as a standard catalog item, or where other method of identification is herein specified, are exceptions.

1.11 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. The Government's approval shall be obtained for all equipment and material before delivery to the job site. Delivery, storage or installation of equipment or material which has not had prior approval will not be permitted at the job site.
- C. All submittals shall include adequate descriptive literature, catalog cuts, shop drawings and other data necessary for the Government to ascertain that the proposed equipment and materials comply with specification requirements. Catalog cuts submitted for approval shall be legible and clearly identify equipment being submitted.

D. Submittals for individual systems and equipment assemblies which consist of more than one item or component shall be made for the system or assembly as a whole. Partial submittals will not be considered for approval.

1. Mark the submittals, "SUBMITTED UNDER SECTION_____".
2. Submittals shall be marked to show specification reference including the section and paragraph numbers.
3. Submit each section separately.

E. The submittals shall include the following:

1. Information that confirms compliance with contract requirements. Include the manufacturer's name, model or catalog numbers, catalog information, technical data sheets, shop drawings, pictures, nameplate data and test reports as required.
2. Submittals are required for all equipment anchors and supports. Submittals shall include weights, dimensions, center of gravity, standard connections, manufacturer's recommendations and behavior problems (e.g., vibration, thermal expansion,) associated with equipment or piping so that the proposed installation can be properly reviewed.
3. Elementary and interconnection wiring diagrams for communication and signal systems, control system and equipment assemblies. All terminal points and wiring shall be identified on wiring diagrams.
4. Parts list which shall include those replacement parts recommended by the equipment manufacturer, quantity of parts, current price and availability of each part.

F. Manuals: Submit per specifications.

1. Maintenance and Operation Manuals: Submit as required for systems and equipment specified in the technical sections. Furnish four copies, bound in hardback binders, (manufacturer's standard binders) or an approved equivalent. Furnish one complete manual as specified in the technical section but in no case later than prior to performance of systems or equipment test, and furnish the remaining manuals prior to contract completion.
2. Inscribe the following identification on the cover: the words "MAINTENANCE AND OPERATION MANUAL," the name and location of the system, equipment, building, name of Contractor, and contract number. Include in the manual the names, addresses, and telephone numbers of each subcontractor installing the system or equipment and the local representatives for the system or equipment.
3. Provide a "Table of Contents" and assemble the manual to conform to the table of contents, with tab sheets placed before instructions

covering the subject. The instructions shall be legible and easily read, with large sheets of drawings folded in.

4. The manuals shall include:

- a. Internal and interconnecting wiring and control diagrams with data to explain detailed operation and control of the equipment.
- b. A control sequence describing start-up, operation, and shutdown.
- c. Description of the function of each principal item of equipment.
- d. Installation and maintenance instructions.
- e. Safety precautions.
- f. Diagrams and illustrations.
- g. Testing methods.
- h. Performance data.
- i. Lubrication schedule including type, grade, temperature range, and frequency.
- j. Pictorial "exploded" parts list with part numbers. Emphasis shall be placed on the use of special tools and instruments. The list shall indicate sources of supply, recommended spare parts, and name of servicing organization.
- k. Appendix; list qualified permanent servicing organizations for support of the equipment, including addresses and certified qualifications.

G. Approvals will be based on complete submission of manuals together with shop drawings.

H. After approval and prior to installation, furnish the COTR/Resident Engineer with one sample of each of the following:

1. A 300 mm (12 inch) length of each type and size of wire and cable along with the tag from the coils of reels from which the samples were taken.
2. Each type of conduit coupling, bushing and termination fitting.
3. Conduit hangers, clamps and supports.
4. Duct sealing compound.
5. Each type of receptacle, toggle switch, outlet box, manual motor starter, device plate, engraved nameplate, wire and cable splicing and terminating material and single pole molded case circuit breaker.
6. Each type of light fixture specified in Section 26 51 00, INTERIOR LIGHTING or shown on the drawings.

1.12 SINGULAR NUMBER

A. Where any device or part of equipment is referred to in these specifications in the singular number (e.g., "the switch"), this reference shall be deemed to apply to as many such devices as are required to complete the installation as shown on the drawings.

1.13 PCB EQUIPMENT

- A. This project requires the removal, transport and disposal of electrical equipment containing Polychlorinated Biphenyl (PCB) in accordance with the Federal Toxic Substances Control Act (TSCA).
- B. The equipment for removal is shown on the drawings.
- C. The selective demolition shall be in accordance with specifications.

1.14 TRAINING

- A. Training shall be provided in accordance with specifications.
- B. Training shall be provided for the particular equipment or system as required in each associated specification.
- C. A training schedule shall be developed and submitted by the contractor and approved by the COTR/Resident Engineer at least 30 days prior to the planned training.

- - - E N D - - -

**SECTION 26 56 00
EXTERIOR LIGHTING**

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This section specifies the furnishing, installation, and connection of exterior luminaries, controls, poles and supports.

1.2 RELATED WORK

- A. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: General electrical requirements and items that are common to more than one section of Division 26.
- B. Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS: Conduits, fittings, and boxes for raceway systems.
- C. Section 26 05 21, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES (600 VOLTS AND BELOW): Low voltage power and lighting wiring.
- D. Section 26 05 41, UNDERGROUND ELECTRICAL CONSTRUCTION: Underground handholes and conduits.
- E. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS: Requirements for personnel safety and to provide a low impedance path for possible ground fault currents.

1.3 SUBMITTALS

- A. Submit in accordance with Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.
- B. Shop Drawings:
 - 1. Sufficient information, clearly presented, shall be included to determine compliance with drawings and specifications.
 - 2. Include electrical ratings, dimensions, mounting, details, materials, required clearances, terminations, wiring and connection diagrams, photometric data, ballasts, poles, luminaries, lamps and controls.
- C. Manuals: Two weeks prior to final inspection, submit four copies of operating and maintenance manuals to the RESIDENT ENGINEER/COTR. Include technical data sheets, wiring and connection diagrams, and information for ordering replacement parts.
- D. Certifications: Two weeks prior to final inspection, submit four copies of the following to the Resident Engineer/COTR:
 - 1. Certification that the materials are in accordance with the drawings and specifications.

2. Certification, by the Contractor, that the complete installation has been properly installed and tested.

1.4 APPLICABLE PUBLICATIONS

Publications listed below (including amendments, addenda, revisions, supplements and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by the basic designation only.

A. Aluminum Association Inc. (AA):

AAH35.1-2006Alloy and Temper Designation Systems for
Aluminum

B. American Association of State Highway and Transportation Officials
(AASHTO):

LTS-4-2006.....Structural Supports for Highway Signs,
Luminaries and Traffic Signals

C. American Concrete Institute (ACI):

318-2008Building Code Requirements for Structural
Concrete

D. American National Standards Institute (ANSI):

IEEE C57.12-2006.....General Requirements For Liquid-Immersed
Distribution, Power, and Regulating
Transformers

E. American Society for Testing and Materials (ASTM):

A123/A123M-2009Zinc (Hot-Dip Galvanized) Coatings on Iron and
Steel Products

A153/A153M-2009.....Zinc Coating (Hot-Dip) on Iron and Steel
Hardware - AASHTO No.: M232

B108-03a-2008Aluminum-Alloy Permanent Mold Castings

D3487-2008.....Mineral Insulating Oil Used in Electrical
Apparatus

AC 150/5345-43E-1995....Specification for Obstruction Lighting
Equipment

G. Illuminating Engineering Society of North America (IESNA)

HB-9-2000.....Lighting Handbook

RP-8-2000 (R-2005).....Roadway Lighting

H. National Electrical Manufacturers Association (NEMA):

C81.61-2005Electrical Lamp Bases

- ICS 2-2008Industrial Control and Systems Controllers,
Contactors and Overload Relays Rated 600 Volts
- ICS 6-2006Industrial Control and Systems Enclosures
- I. National Fire Protection Association (NFPA):
 - 70-2008National Electrical Code (NEC)
- J. Underwriters Laboratories, Inc. (UL):
 - 496-2008Edison-Base Lamp holders
 - 773-1995.....Plug-in, Locking Type Photo controls, for Use
with Area Lighting
 - 773A-2006Non-industrial Photoelectric Switches for
Lighting Control
 - 1598-2008Luminaries

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Store in accordance with manufacturer's instructions.

PART 2 - PRODUCTS

2.1 MATERIALS AND EQUIPMENT

- A. Materials and equipment shall be in accordance with NEC, UL, ANSI, and as shown on the drawings and specified.

2.4 LUMINAIRES

- A. UL 1598 and NEMA C136.17. Luminaries shall be weatherproof, heavy duty, outdoor types designed for efficient light utilization, adequate dissipation of lamp and ballast heat and safe cleaning and relamping.
- B. IESNA HB-9 and RP-8 light distribution pattern types shall be as shown on the drawings.
- C. Incorporate ballasts in the luminaire housing except where otherwise shown on the drawings.
- D. Lenses shall be frame-mounted heat-resistant, borosilicate glass, prismatic refractors. Attach the frame to the luminaire housing by hinges or chain. Use heat and aging resistant resilient gaskets to seal and cushion lenses and refractors in luminary doors.
- F. Pre-wire internal components to terminal strips at the factory.
- G. Bracket mounted luminaries shall have leveling provisions and clamp type adjustable slip-fitters with locking screws.
- H. Materials shall be rustproof. Latches and fittings shall be non-ferrous metal.
- I. IESNA Cutoff Category: semi cutoff.

2.5 LAMPS

- A. Install the proper lamps in every luminaire installed and every luminaire relocated or reinstalled.
- B. Lamps to be general-service, outdoor lighting types.
- C. LED as shown on the drawings and specifications.
- D. Mercury vapor, high pressure sodium, and any other high intensity discharge lamps shall not be used.

2.6 HIGH INTENSITY DISCHARGE BALLASTS

- A. For low voltage systems, the ballasts shall be the high efficiency, high power factor, copper-wound constant wattage type and shall meet the requirements of UL 1029 and NEMA C82.4.
 - 1. Ballasts shall operate the discharge lamp of the type, wattage, and voltage shown on the drawings.
 - 2. Ballasts shall have individual overcurrent protection (inline fuse holder) as recommended by the ballast manufacturer.
 - 3. Ballasts shall be capable of providing reliable starting of the lamps at minus 30 degrees C.
 - 4. Open-circuit operation shall not reduce the average life.
- B. For series systems, the ballasts shall be the high efficiency, high power factor, copper wound constant current type.
 - 1. Provide each ballast with a film type lamp failure protector to prevent excessive secondary voltage.
 - 2. Provide ballasts to operate the discharge lamp of the type, wattage, and voltage shown on the drawings.
 - 3. Ballasts shall be capable of providing reliable starting of the lamps at minus 30 degrees C.
- C. Locate protective devices for ballasts to be accessible if the devices are not integral with ballasts.
- D. Each ballast shall operate not more than one lamp except where otherwise shown on the drawings.

2.7 LIGHTING CONTACTORS

NEMA ICS 2, electrically held contactors. Rate contactors as indicated. Provide in NEMA 4 enclosure conforming to NEMA ICS 6. Contactors shall have silver alloy double-break contacts and coil clearing contacts for mechanically held contactor] and shall require no arcing contacts. Provide contactors with hand-off-automatic selector switch.

2.8 CONTROLS

- A. Each Lighting System:

1. Shall be controlled the following method:
 - a. A photocell to act as the pilot device. The photocell shall be the type which fails safe to the closed position meeting UL 773 or 773A.
2. Mount and connect photocells.
3. Photocells shall have the following features:
 - a. Quick-response, cadmium-sulfide type.
 - b. A 15 to 30 second, built-in time delay to prevent response to momentary lightning flashes, car headlights or cloud movements.
 - c. Energizes the system when the north sky light decreases to approximately 1.5 foot candles, and maintains the system energized until the north sky light increases to approximately 3 to 5 foot candles.

2.9 EXISTING LIGHTING SYSTEMS

- A. For modifications or additions to existing lighting systems, the new components shall be compatible with the existing systems.
- B. New poles and luminaries shall have approximately the same configurations and dimensions as the existing poles and luminaries except where otherwise shown on the drawings.

2.10 AUXILIARY EQUIPMENT

- A. Parallel-Type Systems: Shall be supplied power as shown on the drawings.
- B. Series Type Systems:
 1. Provide components specifically for constant-current series type lighting systems.
 2. Constant-Current Transformers:
 - a. Self-cooled by natural convection, liquid-immersed, fully automatic, outdoor type.
 - b. Liquid shall be oil conforming to ASTM D3487, except where otherwise shown.
 - c. Temperature rises shall not exceed the following ANSI C57.12. test values for the respective insulation systems:
 - 1) Standard, 55 degrees C by resistance and 65 degrees C hottest spot.
 - 2) Thermally upgraded, 65 degrees C by resistance and 80 degrees C hottest spot.
 - d. Core Coil Assemblies:

- 1) Braced to withstand the stresses caused by the maximum current available under all conditions and rough handling during shipment.
- 2) Cores, silicon steel.
- 3) Coils, continuous windings without splices except for taps.
- e. Bring primary and secondary leads out through wet-process, porcelain bushings, pressure-tight. Terminals shall be suitable for the specific cables being connected to them.
- f. Shall have capacitors for power factor improvement. The value of power factor under the percent of full load rating shall be as shown on the drawings.
- g. Shall regulate the secondary current within one percent over the entire load rating range while the primary voltage remains within five percent of the rated voltage.
- h. Operation of the transformers shall not be adversely affected while the transformers are mounted five degrees off of perpendicular.
- i. Provide tanks and covers of steel to meet NEMA and ANSI requirements; which are cleaned, phosphatized and painted at the factory with primer and the manufacturer's standard extremely durable finish.
- j. Sound levels shall not exceed 45 db.
- k. Standard ANSI features and accessories including a pressure relief device, ground pad, lifting provisions and diagrammatic nameplate.
- l. Dimensions and configurations shall conform to the spaces designated for installations.
- m. Install the transformers so they will have adequate air circulation for heat removal.
- 3. Controllers:
 - a. Oil-immersed, rated-load-interrupter, outdoor type with heavy duty, silver-alloy contacts.
 - b. Oil, ASTM D3487.
 - c. Operate at 120 volts, 60 Hz.
 - d. Have an auxiliary hand lever for manual operation during emergencies.
 - e. The depth below the oil surface of the contacts shall be not less than the depth of the switch mechanism.

- f. Bring leads out through wet-process, porcelain bushings, pressure-tight. Terminals shall be suitable for the specific cables being connected to them.
 - g. Provide steel tanks and covers, thoroughly cleaned, phosphatized, and painted at the factory with primer and the manufacturer's standard durable finish.
 - h. Dimensions and configurations shall conform to the spaces designed for installations.
- 4. Provide protective relays to de-energize the control circuits for the controllers and thereby de-energize the series lighting load circuits when open circuit faults occur in the series lighting load circuits.
 - 5. Transformer, equipment enclosure, lightning arresters, primary and secondary protection shall be provided.
 - 6. Disconnecting Devices: Watertight, submersible types suitable for the cables being installed and for use in outdoor lighting systems.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install lighting in accordance with the NEC, as shown on the drawings, and in accordance with manufacturer's recommendations.
- B. Photocell Switch Aiming: Aim switch according to manufacturer's recommendations. Mount switch on or beside each luminaire when switch is provided in cast weatherproof aluminum housing with swivel arm.

3.2 GROUNDING

- A. Ground noncurrent-carrying parts of equipment including metal poles, luminaries, mounting arms, brackets, and metallic enclosures as specified in Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS. Where copper grounding a conductor is connected to a metal other than copper, provide specially treated or lined connectors suitable and listed for this purpose.

- - - E N D - - -