
SECURITY REQUIREMENTS - FACILITY SECURITY LEVEL II

THESE PARAGRAPHS CONTAIN ADDITIONAL SECURITY REQUIREMENTS, AND, UNLESS INDICATED OTHERWISE, ARE TO BE PRICED AS PART OF THE BUILDING SPECIFIC AMORTIZED CAPITAL (BSAC). WHERE THEY ARE IN CONFLICT WITH ANY OTHER REQUIREMENTS ON THIS LEASE, THE STRICTEST SHALL APPLY.

DEFINITIONS:

CRITICAL AREAS - The areas that house systems that if damaged or compromised could have significant adverse consequences for the facility, operation of the facility, or mission of the agency or its occupants and visitors. These areas may also be referred to as "limited access areas," "restricted areas," or "exclusionary zones." Critical areas do not necessarily have to be within Government-controlled space (e.g., generators, air handlers, electrical feeds which could be located outside Government-controlled space).

SENSITIVE AREAS – Sensitive areas include vaults, SCIFs, evidence rooms, war rooms, and sensitive documents areas. Sensitive areas are primarily housed within Government-controlled space.

FACILITY ENTRANCES, LOBBY, COMMON AREAS, NON-PUBLIC, AND UTILITY AREAS

FACILITY ENTRANCES AND LOBBY

EMPLOYEE ACCESS CONTROL AT ENTRANCES (SHELL)

The Lessor shall provide key or electronic access control for the entrance to this building. All Government employees, under this lease, shall be allowed access to the leased space (including after-hours access).

COMMON AREAS, NON-PUBLIC, AND UTILITY AREAS

PUBLIC RESTROOM ACCESS (SHELL)

The Government reserves the right to control access to public restrooms located within the Space.

SECURING CRITICAL AREAS (SHELL)

The Lessor shall secure areas designated as Critical Areas to restrict access:

A. Keyed locks, keycards, or similar security measures shall strictly control access to mechanical areas. Additional controls for access to keys, keycards, and key codes shall be strictly maintained. The Lessor shall develop and maintain accurate HVAC diagrams and HVAC system labeling within mechanical areas.

B. Roofs with HVAC systems shall also be secured. Fencing or other barriers may be required to restrict access from adjacent roofs based on a Government Building Security Assessment. Roof access shall be strictly controlled through keyed locks, keycards, or similar measures. Fire and life safety egress shall be carefully reviewed when restricting roof access.

INITIALS: _____ LESSOR _____ GOV'T

Security Requirements (Level II) (REV 4/25/17),

RLP# _____

SECURITY REQUIREMENTS - FACILITY SECURITY LEVEL II

C. At a minimum, Lessor shall secure building common areas including sprinkler rooms, electrical closets, telecommunications rooms.

VISITOR ACCESS CONTROL (SHELL)

Entrances are open to the public during business hours. After hours, visitor entrances are secured, and have a means to verify the identity of persons requesting access prior to allowing entry into the Space.

INTERIOR (GOVERNMENT SPACE)

DESIGNATED ENTRANCES (SHELL)

The Government shall have a designated main entrance.

IDENTITY VERIFICATION (SHELL)

The Government reserves the right to verify the identity of persons requesting access to the Space prior to allowing entry.

FORMAL KEY CONTROL PROGRAM (SHELL)

The Government reserves the right to implement a formal key control program. The Lessor shall have a means of allowing the electronic disabling of lost or stolen access media, if electronic media is used.

SITES AND EXTERIOR OF THE BUILDING

SIGNAGE

POSTING OF SIGNAGE IDENTIFYING THE SPACE AS GOVERNMENTAL (SHELL)

The Lessor shall not post sign(s) or otherwise identify the facility and parking areas as a Government, or specific Government tenant, occupied facility, including during construction, without written Government approval.

POSTING OF REGULATORY SIGNAGE (SHELL)

The Government may post or request the Lessor to post regulatory, statutory, sensitive areas and site specific signage.

LANDSCAPING

LANDSCAPING REQUIREMENTS (SHELL)

Lessor shall maintain landscaping (trees, bushes, hedges, land contour, etc,) around the facility. Landscaping shall be neatly trimmed in order to minimize the opportunity for concealment of individuals and packages/containers. Landscaping shall not obstruct the views of security guards and CCTV cameras, or interfere with lighting or IDS equipment.

CRIME PREVENTION THROUGH ENVIRONMENTAL DESIGN (SHELL)

The Lessor shall separate from public access, restricted areas as designated by the Government, through the application of Crime Prevention Through Environmental Design (CPTED) principles by using trees, hedges, berms, or a combination of these or similar features, and by fences, walls, gates and other barriers, where feasible and acceptable to the Government.

INITIALS: _____ LESSOR _____ GOV'T

Security Requirements (Level II) (REV 4/25/17),

RLP# _____

SECURITY REQUIREMENTS - FACILITY SECURITY LEVEL II

HAZMAT STORAGE

If there is HAZMAT storage, Lessor shall locate it in a restricted area or storage container away from loading docks, entrances, and uncontrolled parking.

PLACEMENT OF RECEPTACLES, CONTAINERS, AND MAILBOXES

Trash receptacles, containers, mailboxes, vending machines, or other fixtures and/or features that could conceal packages, brief cases, or other portable containers shall be located 10 feet away from building.

SECURITY SYSTEMS

CLOSED CIRCUIT TELEVISION SYSTEM (CCTV)

LESSOR PROVIDED DESIGN, INSTALLATION, AND MAINTENANCE

The lessor shall design, install, and maintain a Closed Circuit Television (CCTV) system as described in this section. The CCTV system will support the entry control system (at entrances and exits to the space), with time lapse video recording, that will allow Government employees to view and communicate remotely with visitors before allowing access to the Space. As determined by the Government the CCTV system shall provide unobstructed coverage of designated pedestrian entrances and exits. Technical review of the proposed system shall be coordinated with the Government security representative, at the direction of the Contracting Officer, prior to installation. CCTV system testing and acceptance shall be conducted by the Government prior to occupancy. The CCTV system shall comply with the Architectural Barriers Act, section F230.0. The Government will centrally monitor the CCTV system. Government specifications are available from the Lease Contracting Officer. CCTV system components which fail or require maintenance or which fail during testing should be serviced in accordance with the Security System Maintenance Criteria listed below.

Security System Maintenance Criteria: The Lessor, in consultation and coordination with a security provider, either internal or external, as determined by the Lease Contracting Officer, and the Government security representative, shall implement a preventive maintenance program for all security systems the Lessor has installed. Any critical component that becomes inoperable must be replaced or repaired by the Lessor within 5 business days. Critical components are those required to provide security (IDS, CCTV, access control, etc.) for a perimeter access point or critical area. "Replacement" may include implementing other temporary measures in instances where the replacement or repair is not achievable within the specified time frame (e.g. a temporary barrier to replace an inoperable pop-up vehicle barrier, etc.). Failure by the Lessor to provide sufficient replacement measures within the timeframe identified above may result in the Government's providing guard service, the cost of which must be reimbursed by the Lessor.

GOVERNMENT PROVIDED PRODUCT, INSTALLATION, AND MAINTENANCE

The Government shall provide and install an entry control system, with time lapse video recording, that will allow Government employees to view and communicate remotely with visitors before allowing access. This Closed Circuit Television (CCTV) system shall provide the Government with unobstructed coverage, as determined by the Government, of designated pedestrian entrances and exits. The Lessor shall permit twenty-four hour CCTV coverage and recording, provided and operated by the Government. The Government will centrally monitor the CCTV surveillance. Government specifications are available from the Contracting Officer. The Lessor shall post necessary regulatory, statutory, and/or site specific signage, as determined by the Government.

INITIALS: _____ LESSOR _____ GOV'T

Security Requirements (Level II) (REV 4/25/17),

RLP# _____

SECURITY REQUIREMENTS - FACILITY SECURITY LEVEL II

The Lessor, at the notice to proceed stage of the procurement, shall advise the Government of the appropriate time to install the equipment during the construction of the Space. The Lessor shall facilitate the installation by allowing access to electrical panels and other areas of the building as necessary.

INTRUSION DETECTION SYSTEM (IDS)

LESSOR PROVIDED DESIGN, INSTALLATION, AND MAINTENANCE

The Lessor shall design, install, and maintain an Intrusion Detection System (IDS) as described in this section. The Government requires an IDS, which will cover perimeter entry and exit doors, and operable ground-floor windows. Basic Security-in-Depth IDS components include: magnetic door switch(s), alarm system keypad, passive infrared sensor(s) (PIR), an alarm panel (to designated monitoring center) and appropriate communication method i.e. telephone and/or Internet connection, glass-break detector, magnetic window switches or shock sensors. Technical review of the proposed system shall be coordinated with the Government security representative, at the direction of the Lease Contracting Officer, prior to installation. System testing and acceptance shall be conducted by the Government prior to occupancy.

Basic Security-in-Depth IDS shall be connected to and monitored at a central station operated by the Department of Homeland Security Megacenter. Emergency notification lists shall be coordinated with the monitoring station to include all applicable Government and lessor points of contact. Monitoring shall be designed to facilitate a real-time detection of an incident, and to coordinate an active response to an incident. The Lessor must complete the Megacenter Alarm Requirements (MAR) application process specified by the Government to meet the monitoring requirements for a functional IDS. Components which fail or require maintenance or which fail during testing shall be serviced in accordance with the Security System Maintenance Criteria listed below..

Security System Maintenance Criteria: The Lessor, in consultation and coordination with a security provider, either internal or external, as determined by the Lease Contracting Officer, and the Government security representative, shall implement a preventive maintenance program for all security systems the Lessor has installed. Any critical component that becomes inoperable must be replaced or repaired by the Lessor within 5 business days. Critical components are those required to provide security (IDS, CCTV, access control, etc.) for a perimeter access point or critical area. "Replacement" may include implementing other temporary measures in instances where the replacement or repair is not achievable within the specified time frame (e.g. a temporary barrier to replace an inoperable pop-up vehicle barrier, etc.). Failure by the Lessor to provide sufficient replacement measures within the timeframe identified above may result in the Government's providing guard service, the cost of which must be reimbursed by the Lessor.

GOVERNMENT PROVIDED SCOPE AND PRODUCT, INSTALLATION, AND MAINTENANCE

The Lessor shall permit installation of a perimeter Intrusion Detection System (IDS) to be operated by the Government. The Government shall provide and install an IDS on perimeter entry and exit doors, and operable ground-floor windows. Basic Security-in-Depth IDS— include: magnetic door switch(s), alarm system keypad, passive infrared sensor(s) (PIR), an alarm panel (to designated monitoring center) and appropriate communication method i.e. telephone and/or Internet connection, glass-break detector, magnetic window switches or shock sensors.

Basic Security-in-Depth IDS shall be connected and monitored at a central station. Emergency notification lists shall be coordinated with the monitoring station to include all applicable Government and

INITIALS: _____ LESSOR _____ GOV'T

Security Requirements (Level II) (REV 4/25/17),

RLP# _____

SECURITY REQUIREMENTS - FACILITY SECURITY LEVEL II

Lessor points of contact. Monitoring shall be designed to facilitate a real-time detection of an incident, and to coordinate an active response to an incident.

The Lessor, at the notice to proceed stage of the procurement, shall advise the Government of the appropriate time to install the equipment during the construction of the Space. The Lessor shall facilitate the installation by allowing access to electrical panels and other areas of the building, as necessary.

DURESS ALARM

LESSOR PROVIDED DESIGN, INSTALLATION, AND MAINTENANCE

The Lessor shall design, install, and maintain a duress alarm system as described. Technical review shall be coordinated with the Government security representative, at the direction of the Contracting Officer, prior to installation. System testing and acceptance shall be conducted by the Government prior to occupancy. This system shall comply with the Architectural Barriers Act, section F230.0.

The Lessor in consultation and coordination with the security provider and Government shall conduct security system performance testing annually. Testing must be based on established, consistent agency-specific protocols, documented and furnished to the Contracting Officer. Components which fail or require maintenance or which fail during testing should be serviced in accordance with the Security System Maintenance Criteria listed below.

Security System Maintenance Criteria: The Lessor in consultation and coordination with a security provider, either internal or external, as determined by the Lease Contracting Officer, and the Government security representative shall implement a preventive maintenance program for all security systems they have installed. Any critical component that becomes inoperable must be replaced or repaired within 5 business days. Critical components are those required to provide security (IDS, CCTV, access control, etc.) for a perimeter access point or critical area. "Replacement" may include implementing other temporary measures in instances where the replacement or repair is not achievable within the specified time frame (e.g. a temporary barrier to replace an inoperable pop-up vehicle barrier, etc.). Failure by the Lessor to provide sufficient replacement measures within the timeframe identified above may result in the Government's providing guard service, the cost of which must be reimbursed by the Lessor.

GOVERNMENT PROVIDED SCOPE, PRODUCT, INSTALLATION, AND MAINTENANCE

The Lessor shall permit installation of a duress alarm system to be provided and operated by the Government. The Government, in coordination with a security provider, either internal or external, as determined by the Contracting Officer, shall document and implement duress procedures for emergency situations.

The Lessor, at the notice to proceed stage of the procurement, shall advise the Government of the appropriate time to install the equipment during the construction of the Space and shall facilitate the installation, including access to electrical panels and other areas of the building, as necessary.

INITIALS: _____ LESSOR _____ GOV'T

Security Requirements (Level II) (REV 4/25/17),

RLP# _____

SECURITY REQUIREMENTS - FACILITY SECURITY LEVEL II

STRUCTURE

WINDOWS

No countermeasures are required for baseline standard.

OPERATIONS AND ADMINISTRATION

LESSOR TO WORK WITH FACILITY SECURITY COMMITTEE (FSC) (SHELL)

The Lessor shall cooperate and work with the buildings Facility Security Committee (FSC) throughout the term of the lease.

ACCESS TO BUILDING INFORMATION (SHELL)

Building Information—including mechanical, electrical, vertical transport, fire and life safety, security system plans and schematics, computer automation systems, and emergency operations procedures—shall be strictly controlled. Such information shall be released to authorized personnel only, approved by the Government, by the development of an access list and controlled copy numbering. The Contracting Officer may direct that the names and locations of -Government tenants not be disclosed in any publicly accessed document or record. If that is the case, the Government may request that such information not be posted in the building directory.

Lessor shall have emergency plans and associated documents readily available in the event of an emergency.

INITIALS: _____ LESSOR _____ GOV'T

Security Requirements (Level II) (REV 4/25/17),

RLP# _____

SECURITY REQUIREMENTS - FACILITY SECURITY LEVEL II

SECURITY UNIT PRICE LIST (FSL II)				
REQUEST FOR LEASE PROPOSAL #				
DATE:				
	Project Name:			
	*To be filled out with initial offer			
<p style="color: red; font-size: small;">The following security countermeasures are required by the Request for Proposals package. Using this form, the offeror shall quote unit prices on all security countermeasures identified in the RLP package, and enter the total costs on the GSA Form 1364 as Building Specific Amortized Capital (BSAC). Upon lease award, BSAC pricing shall be fixed and not subject to further negotiation. Refer to "Security Requirements" attachment to the lease for additional details. This form must be submitted with all offers.</p>				
	<i>Lease Security Standards Section</i>	<i>Unit Price</i>	<i>QTY</i>	<i>Total</i>
	FACILITY ENTRANCES			
	<u>FACILITY ENTRANCES AND LOBBY</u>			
	EMPLOYEE ACCESS CONTROL AT ENTRANCES			
	<u>COMMON AREAS, NON-PUBLIC, AND UTILITY AREAS</u>			
	PUBLIC RESTROOM ACCESS			
	SECURING "CRITICAL AREAS"			
	VISITOR ACCESS CONTROL			
	INTERIOR OF SPACE (GOVERNMENT)			
	DESIGNATED ENTRANCES			
	IDENTITY VERIFICATION			
	FORMAL KEY CONTROL PROGRAM			N/A
	SITE AND EXTERIOR OF BUILDING			
	<u>SIGNAGE</u>			
	POSTING OF SIGNAGE IDENTIFYING THE SPACE AS GOVERNMENTAL			
	POSTING OF REGULATORY SIGNAGE			

INITIALS: _____ LESSOR _____ GOV'T

Security Requirements (Level II) (REV 4/25/17),

RLP# _____

SECURITY REQUIREMENTS - FACILITY SECURITY LEVEL II

	Unit Price	QTY	Total
<u>LANDSCAPING AND ENTRANCES</u>			
LANDSCAPING REQUIREMENTS			
CRIME PREVENTION THROUGH ENVIRONMENTAL DESIGN			
HAZMAT STORAGE			
PLACEMENT OF RECEPTACLES, CONTAINERS, AND MAILBOXES			
SECURITY SYSTEMS			
<u>CLOSED CIRCUIT TELEVISION</u>			
LESSOR PROVIDED DESIGN, INSTALLATION, AND MAINTENANCE - LEVEL II			
GOVERNMENT PROVIDED PRODUCT, INSTALLATION, AND MAINTENANCE			
<u>INTRUSION DETECTION SYSTEM</u>			
LESSOR PROVIDED DESIGN, INSTALLATION, AND MAINTENANCE - LEVEL II			
GOVERNMENT PROVIDED PRODUCT, INSTALLATION, AND MAINTENANCE			
<u>DURESS ALARM</u>			
LESSOR PROVIDED DESIGN, INSTALLATION, AND MAINTENANCE - LEVEL II			
GOVERNMENT PROVIDED PRODUCT, INSTALLATION, AND MAINTENANCE			
STRUCTURE			
<u>WINDOWS</u>			
SHATTER-RESISTANT WINDOW PROTECTION			
OPERATIONS AND ADMINISTRATION			
LESSOR TO WORK WITH THE FACILITY SECURITY COMMITTEE (FSC)			
ACCESS TO BUILDING INFORMATION			
TOTAL COSTS			

INITIALS: _____ LESSOR _____ GOV'T

Security Requirements (Level II) (REV 4/25/17),

RLP# _____