



- NOTES:**
- TOP OF FINISHED FLOOR ELEVATION EQUALS 26'-11/4". UNO. TOP OF SLAB AT PROMENADE IS (-0'-7").
 - THE SLAB-ON-GRADE SHALL BE 4" THICK CONCRETE REINFORCED WITH 6x6-W2.9xW2.9 WWR PLACED ON A 4" LAYER OF SAND OVER A VAPOR BARRIER AND 4" DRAINAGE FILL.
 - UPPER LEVEL FRAMED FLOOR CONSTRUCTION IS 3/4" LIGHT WEIGHT CONCRETE SLAB REINFORCED WITH 6x6-W2.9xW2.9 WWR OVER 2" DEEP, 20 GAGE GALVANIZED COMPOSITE STEEL DECK. (5/4" TOTAL THICKNESS)
 - TOP OF STEEL ELEVATION EQUALS (1'-0 1/4") UNLESS NOTED THUS: (-X") FROM FINISHED FLOOR.
 - FOR SIZE AND LOCATIONS OF SLAB OPENINGS, CURBS, DEPRESSIONS, SLOPES, FLOOR DRAINS, ETC. NOT SHOWN ON THIS DRAWING, SEE ARCHITECTURAL, MECHANICAL, ELECTRICAL & PLUMBING DRAWINGS. SEE TYPICAL FLOOR OPENING DETAIL FOR ADDITIONAL FRAMING AND / OR REINFORCING AT OPENINGS.
 - SHOWN THUS ON PLAN:
 - A: (-0'-0") INDICATES TOP OF FOOTING ELEVATION.
 - B: <-0'-0"> INDICATES TOP OF CONCRETE WALL / GRADE BEAM ELEVATION.
 - C: [-0'-0"] INDICATES TOP OF PIER ELEVATION.
 - D: "00" INDICATES NUMBER OF 3/4"x4" LONG HEADED SHEAR STUD CONNECTORS.
 - E: "P" INDICATES A HSS5x5x1/4 POST ABOVE, UNO.
 - F: "LF" INDICATES DIRECTION OF STEEL DECK SPAN.
 - G: "LF" INDICATES LATERAL FRAME.
 - H: "LF" INDICATES FULLY DEVELOPED MOMENT CONNECTION ST THAT END OF MEMBER.
 - TOP OF EXTERIOR FOOTINGS SHALL BE (-2'-0"), UNO. TOP OF INTERIOR FOOTINGS SHALL BE (-8"), UNO. TOP OF PIERS SHALL BE [-8"], UNO.
 - FOR TYPICAL DETAILS SEE SHEETS S401 THROUGH S405, FOR COLUMN & PIER SCHEDULES SEE SHEET S705.
 - REACTION SHOWN INCLUDE BLAST DESIGN LOADS (5/24/2016).

FOOTING SCHEDULE (3KSF)					
MARK	LENGTH	WIDTH	THICKNESS	REINFORCEMENT (BOT UNO)	REMARKS
F30	3'-0"	3'-0"	12"	4#5 EW BOT	
F40	4'-0"	4'-0"	12"	4#5 EW BOT	
F46	4'-6"	4'-6"	12"	4#5 EW BOT	
F50	5'-0"	5'-0"	12"	7#4 EW BOT	
F60	6'-0"	6'-0"	14"	7#5 EW BOT	
F66	6'-6"	6'-6"	16"	8#5 EW BOT	
F70	7'-0"	7'-0"	17"	6#6 EW-B & 6#4 EW-T	
F80	8'-0"	8'-0"	19"	6#7 EW BOT	
F108/99	10'-8"	10'-9"	24"	11#7 EW BOT	
F149/100	14'-9"	10'-0"	34"	13#9 EW BOT	

UPPER LEVEL MALL FRAMING PLAN - B
1/8" = 1'-0"

FINAL CONSTRUCTION DOCUMENTS
FULLY SPRINKLERED

CONSULTANTS: BURDETTE KOEHLER MURPHY & ASSOCIATES, INC. MECHANICAL / ELECTRICAL CONSULTING ENGINEERING 1416 CLARKVIEW ROAD, SUITE 500 BALTIMORE, MARYLAND 21209 410.323.0600 - FAX 410.377.2543 CENTURY ENGINEERING, INC. CIVIL & STRUCTURAL ENGINEERING 15716 GILROY ROAD HUNT VALLEY, MARYLAND 21031 443.589.2400 - FAX 443.589.2401		KOFFEL ASSOCIATES, INC. FIRE PROTECTION ENGINEERING 8815 CENTRE PARK DR., SUITE 200 COLUMBIA, MARYLAND 21045 410.790.2246 - FAX 410.790.2888		ROBERT L. SEYMOUR ASSOCIATES AUTOMATIC TRANSPORT CONSULTANT 182 THOMAS JOHNSON DR., SUITE 200 FREDERICK, MARYLAND 21702 301.662.8112 - FAX 301.662.8117		I.D.E.A.S., INC. PLANT/PROCESS CONSULTANT 8085 CHORDON RD. KIRTLAND, OHIO 44094 440.296.1880 - FAX 440.296.1881	
BUILDING COST CONSULTANTS COST ESTIMATING 12817 - 30TH AVENUE PLATTSMOUTH, NEBRASKA 68048 402.298.8290 - FAX 402.298.8290		JOHN MILNER ASSOCIATES, INC. CULTURAL RESOURCES CONSULTANT 533 NORTH CHURCH ST. WEST CHESTER, PENNSYLVANIA 19380 610.436.9000 - FAX 610.436.8468		ARCHITECT/ENGINEERS: ARCHITECTURE PLANNING ENGINEERING POLT DESIGN GROUP 2215 Conowingo Rd, Suite 101 Bel Air, Maryland 21015-1436 410.803.2141 fax 410.836.6611 www.polt-design.com		Drawing Title UPPER LEVEL MALL FRAMING PLAN - B Approved: Project Director	
Project Title REPLACEMENT COMMUNITY LIVING CENTER		Project Number 512-173		Building Number 370		Office of Construction and Facilities Management	
Location PERRY POINT VA MEDICAL CENTER		Drawing Number SF106		Date 06/08/18		Checked CEI	
Revisions 1 ADDENDUM - BID RFI 10/5/18		Department of Veterans Affairs		Drawn CEI			