



PARTIAL 4TH FLOOR DEMOLITION PLAN

SCALE: 1/4" = 1'-0"



- 28 TEMPORARY DUST PARTITION AS SHOWN. PARTITION TO BE STUD AND GYPSUM BOARD TO DECK. SEAL AS REQUIRED TO PREVENT SPREAD OF CONSTRUCTION DUST. REPAIR ALL WALLS, FLOORS, AND CEILINGS AFTER REMOVAL TO MATCH EXISTING FINISHES.
- 29 CUT OPENING IN EXISTING 2-HR FIRE-RATED MASONRY SHAFT WALL FOR NEW 2'-6" W. X 7'-0" H. H.M. DOOR AND FRAME. INSTALL STEEL ANGLE W/ WELDED PLATE LINTEL IF REQUIRED FOR SUPPORT OF WALL ABOVE.



**AMERICAN
STRUCTUREPOINT
INC.**

7260 SHADELAND STATION
INDIANAPOLIS, IN 46256-3957
TEL 317.547.5580 FAX 317.543.0270
www.structurepoint.com

**NEW OPENING FOR FIRE-RATED CHASE DOOR
ADDENDUM NO. 1**

RICHARD L. ROUDEBUSH VAMC
1481 W. 10TH STREET, INDIANAPOLIS, IN 46202

RENOVATE FOR CLINICAL IMPROVEMENTS
3RD FLR. C-WING WEST AND 4TH FLR. C-WING EAST
BUILDING 1
VA PROJECT NO. 583-CSI-01

DATE: 08/20/2012
SCALE: 1/4"=1'-0"
DRAWN: FMF
CHECKED: FMF
PROJ. #2010.00629.0002

AD-102-A