

Cooling Tower Replacement

Department of Veterans Affairs Project No. 595-11-135

Miller-Remick LLC Project No. 0499-0011

Lebanon VA Medical Center  
Acquisitions (Building 99)  
1700 South Lincoln Avenue  
Lebanon, PA

**ADDENDUM No. 1**

**August 31, 2012**

Notes on Phasing of Construction:

A requirement of this project is that the existing campus chilled water distribution system may not be interrupted. The intent is that the new cooling towers and all associated components of new construction, as indicated in the contract documents, be installed, tested, and operational prior to the tie-in to the existing condenser water system. Once the tie-in to the existing condenser water system has occurred, the existing cooling towers can be demolished. To achieve this requirement, any valves, fittings, and/or associated piping required, but not specifically shown on the contract drawings, are the responsibility of the contractor's means and methods. The project specifications contain requirements regarding working with existing components and interruption of utilities; for the purposes of this project, chilled water (supply and return), and condenser water (supply and return), shall be considered utilities.