

Approved By: Date:

VA Northern California Health Care System

1601 Concord Avenue

Chico, CA 95928



VA Northern California
HEALTH CARE SYSTEM

DRAFT

VA Northern California Health Care System
Initial Outfitting, Transition & Activation

Statement of Work

Physical Therapy Equipment

VA Northern California Health Care System

1601 Concord Avenue

Chico, CA 95928

1 Introduction

Veteran Affairs Northern California Health Care System (VANCHCS) has a requirement to purchase Physical Therapy Equipment with an authorized vendor to supply and deliver the item(s) identified in Table 1 below. This requirement is in support of a brand name or equal requirement. See attachments for salient characteristics. This requirement is in support of the activation of Chico VA Clinic. Item(s) are to be delivered to the location specified in section 2.4.1.

Table 1 – Package Items Summary

Item Number	Item Description	Quantity
M8100	Bath, Warming, Splint – Whitehall Manufacturing SP-1501-SLD; Brand Name or Equivalent	1
M8105	Bath, Paraffin, Hand/Foot – Whitehall Manufacturing PB-104 Brand Name or Equivalent	1
M8111	Fluidotherapy Unit, Single Extremity – DJO Global, for Chattanooga Products FLU110D ; Brand Name or Equivalent	1
M8115	Conditioner, Cold Treatment Pack – Game Ready; Brand Name or Equivalent	1
M8174	Ultrasound/Neuromuscular Stimulation Combo Unit – Dynatronics D709; Brand Name or Equivalent	2
T0975	Table, Hand Therapy – AliMed ; Brand Name or Equivalent	1
U1016	Bench, Positioning, Bariatric – Medicus Health 7052M1, Brand Name or Equivalent	1

2 General Conditions 2.1 Site Address

2.1.1 The address of the VANCHCS Chico VA Clinic is provided below. Further information on delivery is located in section 2.4.

Chico VA Clinic
1601 Concord Avenue Chico,
CA 95928

2.2 Delivery Schedule

Items shall be delivered no earlier than the estimated delivery start date and no later than the delivery end date listed in Table 2 below.

Table 2 – Anticipated Building Outfitting Schedule

VA Northern California Health Care System

1601 Concord Avenue

Chico, CA 95928

Building Name	Building # & Letter	Acronym	Est. Delivery Start Date	Est. Delivery End Date
Go Energistics Warehouse		Whse.	12/10/2018	1/10/2018

2.3 Schedule and Order Management

2.3.1 The above delivery schedule is based upon the current construction schedule. The vendor shall not increase prices for a change in delivery date for up to 30+ days due to construction delays.

2.3.2 The awardees actual delivery dates will be confirmed by VA upon award. The Government's Beneficial Use/Acceptance date of the ANCHCS Chico VA Clinic is February 13 2019. Due to construction timelines and possible delays, the completion date of VANCHCS Chico VA Clinic may change.

2.3.3 Post-award, the vendor will coordinate delivery prior to beginning any work (See Section 2.4).

2.4 Delivery and Receiving

2.4.1 Delivery and receipt of the proposed items is anticipated to be directed to the location identified below. Confirmation of delivery location will be provided post-award.

VANCHCS Chico VA Clinic (*Direct Delivery to address detailed in paragraph 2.1.1*)

IOT&A Contractor-Provided Warehouse Local to the

VANCHCS Go Energistics Warehouse: Attn: GoE-VA Project, 13290 Contractor Dr., Chico, CA 95928

2.4.2 Delivery shall be freight on board (FOB) – Destination.

2.4.3 The vendor is required to define the need for a staging area to accommodate item delivery, if needed. Post-award, this information will be confirmed with the vendor.

2.4.4 The delivery of items identified in this document shall take place during normal business hours which are defined as: 0800 to 1630 (i.e.: 8:00am to 4:30pm Pacific Standard Time), Monday through Friday, and excluding Federal Holidays.

2.4.5 Delivery trucks will not be permitted to remain at the loading dock. Trucks shall be unloaded, moved from the dock, and then brought back to the dock if required to haul out any waste, tools, or excess materials.

2.4.6 Labeling of delivered items shall include the VA facilities contract number and VA purchase order number for identification and reference upon receipt of product.

2.5 Use of Warehouse

2.5.1 The vendor shall communicate through the VA POC any required coordination requirements.

VA Northern California Health Care System

1601 Concord Avenue

Chico, CA 95928

2.6 Clean Up and Disposal

2.6.1 There are no dumpsters available for vendor use.

2.6.2 The removal of waste and/or excess material shall be conducted through the loading dock area. Delivery trucks and/or other vendor vehicles will not be permitted to remain at the loading dock. Vehicles will need to be brought back to the dock if required to remove any waste, tools, or excess materials.

2.7 Deliverables

2.7.1 The vendor shall provide CAD drawings (including shop drawings) and specifications for site prep for their product as required.

2.7.2 The vendor shall provide Finish Sample(s) where indicated. Contact name and location TBD.

DRAFT

VA Northern California Health Care System

1601 Concord Avenue

Chico, CA 95928

VA Northern California Health Care System

M8100

Project: Chico VA Clinic

Total Quantity: 1

Finish Sample Required if Checked Manufacturer Certified Installation Required if Checked

BMET Training Required if Checked End User Training Required if Checked

Item Name: Bath, Warming, Splint : Brand Name or Equivalent

Salient Characteristics:

- A warming bath for softening splinting sheets of thermoplastic material
- Used in physical therapy treatment
- Table top mounted unit
- Ball valve drain on lower side of the unit for draining water
- Unit constructed out of steel
- Accommodates sheets up to 19" x 11" • Slider lid rather than flip up lid
- Adjustable thermostat.
- Temperature range from 150 to 190 degrees Fahrenheit
- Approximate Dimensions (+/- 2"): 29" wide x 21" deep x 7" high
- Electrical: 120V cord and plug

VA Northern California Health Care System

1601 Concord Avenue

Chico, CA 95928

VA Northern California Health Care System

M8105

Project: Chico VA Clinic

Total Quantity: 1

Finish Sample Required if Checked Manufacturer Certified Installation Required if Checked

BMET Training Required if Checked End User Training Required if Checked

Item Name: Bath, Paraffin, Hand/Foot : Brand Name or Equivalent :

Salient Characteristics:

- Paraffin bath for heat treatment of injuries
- Unit features a chrome plated, corrosion resistant, double walled Monel metal tank to prevent loss of heat, thermostatic control, drain, timer, thermometer and stand with casters
- Unit can hold approximately 22 lbs. of paraffin.
- Hardwood molding around the outside of the unit
- Heated drain
- Sterilizing high heat setting
- Treatment tank Approximate Dimensions (+/- 2"):
14" l x 7"w x 10"h
- Electrical: 120V cord and plug

VA Northern California Health Care System

1601 Concord Avenue

Chico, CA 95928

VA Northern California Health Care System

M8111

Project: Chico VA Clinic

Total Quantity: 1

Finish Sample Required if Checked Manufacturer Certified Installation Required if Checked

BMET Training Required if Checked End User Training Required if Checked

Item Name: Fluidotherapy Unit, Single Extremity: Brand Name or Equivalent

Salient Characteristics:

- Surface Bench grinder used in the creation and modification of orthotics and prosthetics
- 2 speeds with suction filter bag and hose
- Grinder shall mount to the bench
- Self-contained polishing and grinding system with dust containment/collector
- Includes 4in. x 3in. sanding drum, fine abrasive sleeve and dust collection assembly
- Approximate Dimensions (+/- 2"): 27" wide x 16" deep x 10" high
- Electrical 120V cord and plug

VA Northern California Health Care System

1601 Concord Avenue

Chico, CA 95928

VA Northern California Health Care System

M8115

Project: Chico VA Clinic

Total Quantity: 1

Finish Sample Required if Checked Manufacturer Certified Installation Required if Checked

BMET Training Required if Checked End User Training Required if Checked

Item Name: Conditioner, Cold Treatment Pack : Brand Name or Equivalent

Salient Characteristics:

- Portable control unit which provides compression and adjustable cold therapies to extremities to reduce swelling
- Unit provides active cryotherapy, compression therapy, circumferential coverage and fast deep cooling
- Unit consists of control unit which generates cold and pressure via control compressor
- Pressure, temperature and time can be adjusted via control unit
- Unit has compartment for ice cubes to help provide cold to the unit
- Also comes with carrying handle
- Unit includes:
 - Control unit compressor
 - Carry bag
 - Rechargeable battery pack • Unit to include:
 - Knee wrap
 - Ankle wrap
 - Straight
 - Flexed elbow wrap
 - Shoulder wrap
 - Wrist wrap
 - Hand wrap
 - Back wrap
 - Approximate Dimensions (+/- 2"): 8" wide x 16" deep x 8" high

VA Northern California Health Care System

1601 Concord Avenue

Chico, CA 95928

VA Northern California Health Care System

M8174

Project: Chico VA Clinic

Total Quantity: 2

- Finish Sample Required if Checked Manufacturer Certified Installation Required if Checked
- BMET Training Required if Checked End User Training Required if Checked

Item Name: Ultrasound/Neuromuscular Stimulation Combo

Unit : Brand Name or Equivalent

Salient Characteristics:

- Ultrasound unit in combination with a neuromuscular stimulator; unit can deliver both types of treatments simultaneously or individually
- The ultrasound unit operates at one or more frequencies
- The electrotherapy portion of the instrument can operate at set voltages or continuously variable across a range
- Ultrasound features multi-frequencies of 1, 2, and 3 MHz, and duty cycles of 10%, 20%, 50%, and continuous
- 5-Channel electrotherapy has one High Voltage channel
- 7 treatment modes
- Microcurrent conductance indicator
- Easy to read keypad with digital displays electrode conductance meter
- Dual treatment wands
- Accessories
- Mobile Stand
- Soundhead
- Approximate Dimensions (+/- 2"): 15" wide x 13" deep x 5" high
- Electrical: 120V cord and plug

VA Northern California Health Care System

1601 Concord Avenue

Chico, CA 95928

VA Northern California Health Care System

T0975

Project: Chico VA Clinic

Total Quantity: 1

Finish Sample Required if Checked Manufacturer Certified Installation Required if Checked

BMET Training Required if Checked End User Training Required if Checked

Item Name: Table, Hand Therapy : Brand Name or Equivalent

Salient Characteristics:

- A table for use with hand therapy treatment
- The table will be height adjustable with an easy to operate crank hydraulic lift system
- Table will have a laminated top and telescoping legs
- Table Approximate Dimensions (+/- 2"): 16" w x 33"long
- Adjustable legs to accommodate wheel chairs
- Manual height adjustable from 23"-33"
- Surface finish laminate, able to withstand cleaning with 10% bleach solution

VA Northern California Health Care System

1601 Concord Avenue

Chico, CA 95928

VA Northern California Health Care System

U1016

Project: Chico VA Clinic

Total Quantity: 1

- Finish Sample Required if Checked Manufacturer Certified Installation Required if Checked
 BMET Training Required if Checked End User Training Required if Checked

Item Name: Bench, Positioning, Bariatric : Brand Name or Equivalent

Salient Characteristics:

- Basis of Design: Medicus Health 7052M1: Brand Name or Equivalent
- The single steel frame seating bench offers a comfortable and convenient way to provide extra seating for bariatric patients
- With a 1,000 lb. weight capacity.
- Approximate Dimensions (+/- 2"):
- Width: 24"
- Depth: 21"
- Height: 21"
- Finish: Silver
- Vinyl: Copenhagen
- The single steel frame seating bench offers comfortable seating for one
- Medium density foam for seating comfort
- Heavy duty vinyl is long lasting and easy to clean
- Four leg levelers to ensure the bench sits flat on uneven surfaces
- Weight Capacity: 1,000 lbs.
- TB117-2013
- Fabrics and finishes must be approved by VA Interior Designer prior to purchase