

ATTACHMENTS

EXHIBIT 1

CAPTION 1: BLDG 40 - Crawlspace

3/4-in Drip trap for main line



1	BLDG 40 - Crawlspace			
	ITEM	QTY	UNIT	SPEC
	3/4-in Main line Drip Trap	1	EA	Steel trap body (welded connections)
	3/4-in Welded Gate Valves	2	EA	Suitable hardened corrosion resistant allow
	3/4-in Steam Pipe	10	LF	

2	BLDG 40 - 1600			
	ITEM	QTY	UNIT	SPEC
	3-in Steam Pressure Regulator	3	EA	Cast Iron, Flanged with Grade B7 threaded studs, Single Seat, 10-100 psi Pressure Pilot
	3-in Spiral Wound Metal Gasket	6	EA	304SS and Flexible Graphite
	5-in Steam Pressure Regulator	1	EA	Cast Iron, Flanged with Grade B7 threaded studs, Single Seat, 10-100 psi Pressure Pilot
	5-in Gate Valve	1	EA	Cast Steel body grade WCB, flanged with Grade B7 threaded studs
	5-in Spiral Wound Metal Gasket	4	EA	304SS and Flexible Graphite

CAPTION 2: BLDG 40 - 1600

3-in (top) 5-in (bottom) Pressure Regulators



3-in Pressure Regulators



5-in Gate Valve



EXHIBIT 1

CAPTION 3: BLDG 1 - B403 (Tank Room)

6-in Pressure Regulator



5x4 Reducer



Vacuum and Condensate Unit



CAPTION 4: BLDG 1 - 4549

1 1/2-in Pressure regulator (left) 1-in Pressure Regulator (right)



3 BLDG 1 - B403 (Tank Room)			
ITEM	QTY	UNIT	SPEC
6-in Steam Pressure Regulator	1	EA	Cast Iron, Flanged, Single Seat with 3-20 psi Pressure Pilot
Gaskets for 4-in x 5-in Reducer (Steam Pipe)	2	EA	Flanged (8 bolts); 304SS and Flexible Graphite
Vacuum and Condensate unit with independent air and water pumps	2	EA	Type BVC; 19 to 52 CFM with 80 Gallon Condensate; Inlet: 4-in NPT; Overflow: 2-in NPT; Vent: 3-in NPT; Gauge Glass Fittings: 10-in apart; Receiver Drain: 1/2-in NPT; Vacuum Drain: 3/4-in NPT; Condensate Pump: 5HP, Volts: 208-230/460, Amps 12-11.8/5.9, 3450 RPM, Frame 184JM

4 BLDG 1 - 4549			
ITEM	QTY	UNIT	SPEC
1-in Steam Pressure Regulator	1	EA	Cast Iron, Single Seat, 20-150 psi Pressure Pilot
1 1/2-in Steam Pressure Regulator	1	EA	Cast Iron, Flanged, Single Seat, 3-20 psi Pressure Pilot

EXHIBIT 1

CAPTION 5: BLDG 1 - Roof (AC21)
 BLDG 1 - Roof (AC21)



5	BLDG 1 - Roof (AC21)			
	ITEM	QTY	UNIT	SPEC
	2-in 45-Bend	1	EA	Forged Steel, threaded, schedule 80
	2-in Steam pipe and Exterior insulation	20	LF	

CAPTION 6: BLDG 11B - B340
 3-in Pressure Regulators



6	BLDG 11B - B340			
	ITEM	QTY	UNIT	SPEC
	3-in Steam Pressure Regulator	2	EA	Cast Iron, Single Seat with 5-50 psi Pressure Pilot

7	Asbestos Abatement	160	FT	
---	--------------------	-----	----	--