



1. INTERIOR DIMENSIONS GIVEN ARE FROM FINISH TO FINISH OR TO CENTERLINE OF COLUMN UNLESS NOTED OTHERWISE.
2. TOLERANCES FOR BUILT-IN ITEMS, INCLUDING ARCHITECTURAL WINDOWS, CASEWORK AND APPLIANCES, MUST BE FIELD VERIFIED BY THE CONTRACTOR TO ENSURE ADEQUATE CLEARANCES AND PROPER FIT.
3. REFER TO REFLECTED CEILING PLANS FOR CEILING HEIGHTS AND TYPES.
4. REFER TO SPECIFICATIONS FOR FINISHES AND MANUFACTURERS.
5. REFER TO 1/8" SCALE FLOOR PLANS FOR DOOR DESIGNATIONS AND 1/8" SCALE INTERIOR ELEVATIONS FOR WINDOW DESIGNATIONS.
6. REFER TO 4700 SERIES FOR TYPICAL MOUNTING HEIGHTS OF ACCESSORIES AND DEVICES. PROVIDE FIRE RETARDANT WOOD BLOCKING FOR ACCESSORIES AND DEVICES. SEE DETAIL 19A702 FOR GRAB BAR AND CABINETS METAL BLOCKING.
7. ALL DISPENSERS, INCLUDING SHARPS, PAPER TOWEL, SOAP, HAND SANITIZER AND GLOVE DISPENSERS ARE FURNISHED BY THE GOVERNMENT & INSTALLED BY THE CONTRACTOR.
8. REFER TO LIFE SAFETY PLANS FOR LOCATION OF FIRE RATED PARTITIONS.
9. PROVIDE FIBER REINFORCED WATER & MOLD RESISTANT GYPSUM PANELS AT ALL WET WALL LOCATIONS AND WALLS BEHIND AND ADJACENT TO SINKS.
10. CONFIRM ALL CABINET & COUNTER TOP LAYOUTS WITH SHOP DRAWINGS.
11. REFER TO KITCHEN EQUIPMENT DRAWINGS FOR ALL APPLIANCE INFORMATION.

1. **1 HOUR FIRE-RATED BARRIER OR 1 HOUR FIRE RATED SMOKE BARRIER**
5/8" FIRE-RATED GYP-BD. ON BOTH SIDES OF 3 5/8" METAL STUDS @ 16" O.C. FROM FLOOR TO ROOF OR FLOOR DECK ABOVE. PROVIDE FIRE SEALANT AT TOP AND BOTTOM EDGES OF 3 5/8" METAL STUDS. 1" O.C., (AT THASE WALLS, PROVIDE GYP-BD. ON FINISHED SIDE OF STUDS.)
2. **1 HOUR SMOKE PARTITION (NON-RATED)**
CORRIDOR PARTITION, SMOKE SEALED TOP, AT RATED CEILING AND FLOOR. 5/8" GYP-BD. ON BOTH SIDES OF 3 5/8" METAL STUDS, 1" O.C., (AT THASE WALLS, PROVIDE GYP-BD. ON FINISHED SIDE OF STUDS.)
3. **2 HOUR FIRE-RATED BARRIER**
2 LAYERS 5/8" FIRE-RATED GYP-BD. ON BOTH SIDES OF 3 5/8" METAL STUDS @ 16" O.C. SEAL GYP-BD. AT FLOOR AND AT ROOF DECK OR FLOOR STRUCTURE ABOVE. PROVIDE FIRE SAFING AT FLUTES OF FLOOR OR ROOF FLOOR DECK ABOVE PER UL - U419.
4. **1 HOUR FIRE-RATED BARRIER**
NOMINAL 8"X8"X16" CONCRETE MASONRY UNITS TO UNDERSIDE OF RATED STRUCTURE ABOVE PER IBC TABLE 720.1(2). ADD ONE LAYER OF 5/8" GYP-BD. ON ONE SIDE OF 1 5/8" METAL STUD FURRING @ 16" O.C. TO TOP OF WALL WITH FIRE SAFING AT ROOF OR FLOOR DECK ABOVE.
5. **1 HOUR FIRE-RATED BARRIER**
NOMINAL 8"X8"X16" CONCRETE MASONRY UNITS TO UNDERSIDE OF RATED STRUCTURE ABOVE PER IBC TABLE 720.1(2).
6. **1 HOUR FIRE-RATED SHAF WALL**
2 1/2" C-H STUDS AT 24" O.C. COVERED ONE SIDE W/ ONE LAYER, 5/8" TYPE "X" GYPSUM BOARD. OPPOSITE SIDE COVERED W/ 1" GYPSUM PANELS. PER UL NO. U415A.
7. **2 HOUR FIRE-RATED SHAF WALL**
2 1/2" C-H STUDS AT 24" O.C. COVERED ONE SIDE W/ TWO LAYERS 5/8" TYPE "X" GYPSUM BOARD. OPPOSITE SIDE COVERED W/ 1" GYPSUM PANELS. PER UL NO. U415B.
8. **2 HOUR FIRE-RATED BARRIER**
8" CMU FROM FLOOR TO STRUCTURE ABOVE- SEAL TOP OF WALL WITH FIRE SAFING AT ROOF OR FLOOR DECK ABOVE PER UL NO. U995.
9. **TYPICAL PARTITION**
5/8" GYP-BD. ON BOTH SIDES OF 3 5/8" METAL STUDS, @ 16" O.C., GYP-BD. TO STRUCTURE ABOVE.
10. **SAME AS (5) W/ 2" SOUND ATTENUATION BLANKETS**
NOT USED.
11. **CHASE WALL (WIDTH VARIES)**
5/8" GYP-BD. ON ONE SIDE OF BOTTOM EDGES OF 3 5/8" METAL STUDS, @ 16" O.C. PROVIDE GYP-BD. ON EACH FINISH SIDE OF CHASE, GYP-BD TO FIRE-RATED CEILING OR ROOF ASSEMBLY ABOVE.
12. **SAME AS (7) W/ 2" SOUND ATTENUATION BLANKETS IN BOTH LINES STUDS**
13. **5/8" GYP-BD. ON BOTH SIDES OF 6" METAL STUDS**
14. **1 HOUR RATED PARTITION W/ SOUND RATING**
1 1/2" BASE LAYER GYP-BD, 5/8" GYP-BD. ON BOTH SIDES OF 2 1/2" METAL STUDS @ 24" O.C., 1" SOUND INSULATION (STCCS)
15. **LOW WALL PARTITION**
5/8" GYP-BD. ON BOTH SIDES OF 3 5/8" METAL STUDS @ 16" O.C., 1" HEIGHT OF COURTESY TOP.
16. **FOR TOILET RM PARTITIONS FACING A PUBLIC CORRIDOR, 2"**

ITEMS PURCHASED AND INSTALLED BY CONTRACTOR:

- 1. SWING UP GRAB BARS W/ INTEGRATED TOILET PAPER DISPENSER
- 2. SHOWER GRAB BAR
- 3. TOWEL BAR
- 4. SHOWER TRANSFER SEAT
- 5. ROBE HOOK
- 6. RECESSED MEDICINE CABINET - REFER TO SPECIFICATIONS

ITEMS PURCHASED BY GOVERNMENT AND INSTALLED BY CONTRACTOR:

- 1. HAND SANITIZER DISPENSER
- 2. SIDE BY SIDE DOUBLE ROLL BATHROOM DISPENSER (#56794) BY GEORGIA PACIFIC
- 3. PAPER TOWEL HOLDERS
- 4. SPOULTRON FULL-CORET SMOKED SMOKE DISPENSER (CENTER PULL) (#58040) (SIZE: 11.5" x 9.25" x 8.75") FOR ROLLS
- 5. SOAP DISPENSER
- 6. BACTI-FOAM SOAP DISPENSER (#97273188) FOR BACTI-FOAM SOAP (#EL61806-499) BY ECOLAB

ITEMS PURCHASED AND INSTALLED BY GOVERNMENT:

- 1. HAND SANITIZER DISPENSER
- 2. SHARPS CONTAINER
- 3. WASTE BASKET
- 4. GLOVES DISPENSER

Office of
Construction
and Facilities
Management



		CONSULTANTS:				ARCHITECT/ENGINEERS:		Drawing Title ENLARGED PLANS		Project Title RELOCATE DEMENTIA UNIT		Project Number VA PN 613-107		Office of Construction and Facilities Management			
						C.C. HODGSON ARCHITECTURAL GROUP P.C.		Approved: Project Director		Location VAMC MARTINSBURG		Building Number 513				Drawing Number AE-105	
										Date 8/6/2012		Checked Checker		Drawn Author		Department of Veterans Affairs	