

one and one half inches = one foot
one inch = one foot
one half inch = one foot
three quarters inch = one foot
one quarter inch = one foot
one eighth inch = one foot

ELECTRICAL NOTES

WORK DESCRIBED IN THESE NOTES IS TO BE PERFORMED UNDER DIVISION 26 (ELECTRICAL).

- THIS DRAWING LOCATES FINAL ELECTRICAL POINTS OF CONNECTION FOR EACH FOODSERVICE EQUIPMENT ITEM. IT DOES NOT INDICATE UTILITY ROUGH-IN LOCATIONS AND MUST NOT BE USED FOR THAT PURPOSE. LOCATIONS, SIZES, AND HEIGHTS ABOVE THE FLOOR ARE APPROXIMATELY AS THEY WILL OCCUR ON THE EQUIPMENT ITEMS SHOWN. THE DESIGN OF SYSTEMS TO ACCOMMODATE THESE REQUIREMENTS IS TO BE IN ACCORDANCE WITH ALL APPLICABLE CODES AND MEET WITH THE APPROVAL OF ALL GOVERNING AUTHORITIES.
- UTILITIES SHOWN ARE FOR FOODSERVICE EQUIPMENT ITEMS ONLY. THIS DRAWING MUST BE USED IN CONJUNCTION WITH THE ELECTRICAL DRAWINGS FOR OTHER REQUIRED UTILITIES.
- CONCEAL ALL UTILITIES IN WALLS AND STUB-OUT OF WALLS AS REQUIRED FOR CONNECTIONS. DO NOT RUN EXPOSED ON THE FACE OF THE WALL. DO NOT STUB-OUT OF THE FLOOR UNLESS IT IS BELOW FREESTANDING EQUIPMENT.
- EXPOSED CONDUIT ABOVE WORK SURFACES TO BE STAINLESS STEEL. EXPOSED CONDUIT BELOW WORK SURFACES TO BE CHROME PAINTED.
- POWER TO ALL ELECTRICALLY OPERATED EQUIPMENT UNDER HOODS IS TO COME FROM THE PANEL WHERE THE MAIN BREAKER IS INTERWIRED WITH THE FIRE EXTINGUISHING SYSTEM SO THAT POWER SHUT-OFF IS ACHIEVED UPON EITHER MANUAL OR AUTOMATIC OPERATION OF THE FIRE EXTINGUISHING SYSTEM.
- PROVIDE A FLUSH, EMPTY JUNCTION BOX AT EACH REMOTE FIRE CABLE PULL. PROVIDE CONDUIT CONCEALED IN WALL FROM JUNCTION BOX TO A POINT 6"(155mm) ABOVE FINISHED CEILING.
- PROVIDE CONDUIT AND WIRING BETWEEN THE FUEL LINE SOLENOID SHUT-OFF VALVES, SHUNT TRIP BREAKERS, CONTACTORS, REMOTE NOTIFICATION AND FIRE EXTINGUISHING SYSTEMS.
- NOT USED.
- NOT USED.
- NOT USED.
- NOT USED.
- PROVIDE DUPLEX CONVENIENCE OUTLET (120/1Ø, 20A) AT HEIGHT INDICATED.
- COORDINATE THE INTERWIRE OF ALL SPECIFIED TEMPERATURE ALARM SYSTEMS TO BUILDING SYSTEM.
- VENTILATORS SHALL INCLUDE THERMOSTAT(S) INSTALLED IN THE CANOPY TO AUTOMATICALLY START THE EXHAUST FAN(S) WHEN COOKING OCCURS TO MEET IMC 2006 SECTION 507.2.1.1.
- ELECTRICAL PANELS TO BE LOCATED WITHIN LINE OF SIGHT OF EQUIPMENT SERVED BY PANELS AND NOT FURTHER AWAY FROM EQUIPMENT THAN LOCAL CODE REQUIREMENTS ALLOW.

ELECTRICAL ABBREVIATIONS AND SYMBOLS		
SWITCH	SW	Ⓢ
ELECTRICAL CONNECTION	EC	Ⓜ
JUNCTION BOX	JB	Ⓜ
SINGLE RECEPTACLE	SR	Ⓜ
DUPLEX RECEPTACLE	DR	Ⓜ
DATA COMMUNICATIONS	DC	Ⓜ
EMPTY JUNCTION BOX		Ⓜ
AMP	A	Ⓜ
KILOWATT	KW	Ⓜ
HORSEPOWER	HP	Ⓜ
VOLT	V	Ⓜ
PHASE	Ø	Ⓜ
ABOVE FINISHED FLOOR	AFF	Ⓜ
DOWN FROM ABOVE	DFA	Ⓜ

FIRE EXTINGUISHING SYSTEM NOTES		
FA	NOT USED.	
FB	WIRING IN CONDUIT BY ELECTRICAL TRADE TO SHUNT-TRIP BREAKER LOCATED IN POWER PANEL SUPPLYING EQUIPMENT BENEATH VENTILATOR AND/OR BETWEEN RESET RELAY AND CONTACTORS SERVING EQUIPMENT BENEATH VENTILATOR	
FC	WIRING IN CONDUIT BY ELECTRICAL TRADE BETWEEN MICROSWITCH AND BUILDING FIRE ALARM SYSTEM AS REQUIRED	
FD	FLUSH-MOUNT OCTAGONAL J-BOX (8B TYPE) MOUNTED AT 48"(1200mm) TO 54"(1350mm) AFF WITH 1/2" (15mm) EMT TO 6"(150mm) ABOVE CEILING BY ELECTRICAL TRADE FOR REMOTE CABLE PULL (HEIGHT VARIES PER LOCAL CODES)	
FE	NOT USED.	
FF	NOT USED.	

VENTILATOR NOTES		
VA	WIRING IN CONDUIT BY ELECTRICAL TRADE BETWEEN VENTILATOR CONTROL AND MICRO SWITCH IN FIRE SUPPRESSION SYSTEM	
VB	WIRING IN CONDUIT BY ELECTRICAL TRADE BETWEEN VENTILATOR CONTROL (FAN SWITCH, PANEL OR VARIABLE SPEED FAN CONTROL) AND EXHAUST/SUPPLY FAN MAGNETIC STARTER/MOTOR	
VC	NOT USED.	
VD	WIRING IN CONDUIT BY ELECTRICAL TRADE BETWEEN VENTILATOR CONTROL (FAN SWITCH, PANEL OR VARIABLE SPEED FAN CONTROL) AND JB ON TOP OF VENTILATOR FOR DAMPER CONTROL(S), AUTOSTART THERMOSTATS, UV	
VE	WIRING IN CONDUIT BY ELECTRICAL TRADE BETWEEN VENTILATOR CONTROL AND JB ON TOP OF VENTILATOR FOR LIGHTS AND/OR FAN	
VF	NOT USED.	
VG	NOT USED.	
VH	NOT USED.	
VI	NOT USED.	


NOTE:
REFER TO SHEET QF105 FOR
ELECTRICAL UTILITY LOAD
SCHEDULE

NOTE: THIS DRAWING IS FOR INFORMATION ONLY.

GENERAL CONTRACTOR SHALL COORDINATE WITH THE KITCHEN EQUIPMENT SUB-CONTRACTOR AND RELATED MECHANICAL, ELECTRICAL AND PLUMBING SUB-CONTRACTORS TO ESTABLISH FINAL SPOT CONNECTIONS LOCATIONS AND CONFIGURATIONS AS REQUIRED. THIS DRAWING SHALL NOT BE USED TO LOCATE ANY UTILITY CONNECTIONS IN THE FIELD OR TO LOCATE ANY ROUGH-IN, PENETRATION, OR OTHER REQUIREMENTS.

CINI • LITTLE INTERNATIONAL, INC.

BID DOCUMENTS
FULLY SPRINKLERED

Revisions:		Date:	CONSULTANTS:		ARCHITECT/ENGINEERS:		Drawing Title		Project Title		Project Number		Office of Construction and Facilities Management	
			 CINI • LITTLE INTERNATIONAL, INC. 20251 CENTURY BOULEVARD, SUITE 375 GERMANTOWN, MD 20874-1114 USA 301-528-9700 OFFICE 301-528-9711 FAX www.cinilittle.com				Foodservice Equipment Electrical Spot Connection Plan		RELOCATE DEMENTIA UNIT		VA PN 613-107		Department of Veterans Affairs	
							Approved: Project Director		Location VAMC MARTINSBURG		Building Number 513			
									Date 8/6/2012		Checked LKL		Drawn CAD	
											Drawing Number QF103			
											Dwg. of --			