

three inches = one foot  
one and one half inches = one foot  
one inch = one foot  
three quarters inch = one foot  
one half inch = one foot  
one quarter inch = one foot  
one eighth inch = one foot  
one sixteenth inch = one foot

DOOR SCHEDULE										
Project: VA Zablocki Medical Center - Radiation/Oncology Expansion										
PLUNKETT RAYSICH ARCHITECTS, LLP										
Project No.100077-10										
DOOR NO.	ROOM NO.	ROOM NAME	Size (W x H)	Type	DOOR	Finish	Glass	Mat'l	FRAME	Notes
B0239.0	B0239	TEMPORARY BLOCK ROOM	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	2,3
B0400.0	B0400	RECEPTION	3'-0" x 7'-0"	B	STN	PA	MG	STL	PA	
B0400.1	B0400	RECEPTION	5'-0" x 4'-0"	C	STN	PA	MG	STL	PA	
B0403	B0403	PASSAGE	3'-0" x 7'-0"	B	STN	PA	MG	STL	PA	
B0410	B0410	EXAM 1	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0411	B0411	PASSAGE	(2) 3'-8" x 7'-0"	B	STN	PA	MG	STL	PA	
B0413B	B0413B	STORAGE	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0421	B0421	EXAM 5 / ED	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	1 HOUR
B0421A	B0421A	TOILET	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0427.1	B0427A	CLOSET	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0427.2	B0427B	CLOSET	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0428	B0428	BLOCK/DARK ROOM	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0428.1	B0428	BLOCK/DARK ROOM	4'-0" x 7'-0"	A	STN	PA	MG	STL	PA	2,3
B0429	B0429	LEAD RT	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0430	B0430	RTT WORK ROOM	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0431	B0431	PHYSICIST	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0432	B0432	OFFICE	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0433	B0433	OFFICE	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0434	B0434	OFFICE	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0435	B0435	DOSIMETRY	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0435A.0	B0435A	PASSAGE	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
B0435A.1	B0435A	PASSAGE	3'-0" x 7'-0"	A	STN	PA	MG	STL	PA	
NOTES: 1 LIGHT TIGHT 2 YELLOW TEMPORARY CONSTRUCTION DOOR 3 PROVIDE KEY PAD ACCESS										

ROOM FINISH SCHEDULE										
Project: VA Zablocki Medical Center - Radiation/Oncology Expansion										
PLUNKETT RAYSICH ARCHITECTS, LLP										
Project No.100077-10										
Room #	Room Name	Floor	Base	North	East	South	West	Ceiling	Type	Notes
B0400	RECEPTION	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	1
B0401	WAITING ROOM	SV-1/VCT-1	RB-1	PA	PA	PA	PA	PA	AC-1	4
B0402	NURSES	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	1
B0403	PASSAGE	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	
B0410	EXAM 1	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	1
B0411	PASSAGE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC-1	
B0412	EXAM 2	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	
B0413	CT	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	
B0413A	CONTROL	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	1
B0413B	STORAGE	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	
B0414	TOILET	PT-1	PT-2	CT-1,2,3/PA	CT-1,2,3/PA	CT-1,2,3/PA	CT-1,2,3/PA	SUSP	AC-2	2
B0415	LINEAR ACCELERATOR ROOM 1	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	
B0416	CONTROL	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	
B0417	LINEAR ACCELERATOR ROOM 2	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	
B0418	CONTROL	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	
B0421	EXAM 5 / ED	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	
B0421A	TOILET	PT-1	PT-2	CT-1,2,3/PA	CT-1,2,3/PA	CT-1,2,3/PA	CT-1,2,3/PA	SUSP	AC-2	2
B0423	EXAM 4	VCT-1	RB-1	PA	PA	PA	PA	EXTG	EXTG	
B0427	PASSAGE	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	
B0427A	CLOSET	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	5
B0427B	CLOSET	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	5
B0428	BLOCK/DARK ROOM	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	6
B0429	LEAD RT	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	
B0430	RTT WORK ROOM	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	3
B0431	PHYSICIST	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	
B0432	OFFICE	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	
B0433	OFFICE	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	
B0434	OFFICE	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	
B0435	DOSIMETRY	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	
B0435A	PASSAGE	VCT-1	RB-1	PA	PA	PA	PA	SUSP	AC-1	
C0B11	PASSAGE	VCT	RB-1	PA	PA	PA	PA	SUSP	AC-1	
C0B11A	PASSAGE	VCT	RB-1	PA	PA	PA	PA	SUSP	AC-1	

GENERAL NOTES:										
1) PATCH TO MATCH EXISTING FLOOR, WALL, AND CEILING FINISHES AS NECESSARY.										
2) PROVIDE CT-1 WANSOT WITH ACENT TO 4'-0" A.F.F. CAP WANSOT WITH CT-2.										
3) PROVIDE PLAM-X AT CASEWORK. PROVIDE PLAM-X AT COUNTERTOPS.										
4) FLOOR PATTERN TO BE DETERMINED										
5) PROVIDE PLAM-X AT ADJUSTABLE/COAT/SHELVES.										
6) PROVIDE PLAM-X AT CASEWORK. PROVIDE STAINLESS STEEL COUNTERTOPS.										

MATERIALS SCHEDULE				PLUNKETT RAYSICH ARCHITECTS, LLP
Project: VA Zablocki Medical Center - Radiation/Oncology Expansion				Project No. 100077-10
CODE	MATERIAL	NAME & NUMBER	MANUFACTURER	
INTERIOR ARCHITECTURAL WOODWORK - Division 6				
PLAM-1	Plastic Laminate	To be determined	To be determined	
*	PVC Edge Banding	To be determined	To be determined	
TILE - Division 9				
CT-1	Ceramic Tile (Wall)	0135 Almond; Semi-Gloss Glazed Ceramic- 6" x 6" Tile	Daltile	
CT-2	Ceramic Tile (Wall)	0169 Waterfall; Semi-Gloss Glazed Ceramic- 6" x 6" Tile	Daltile	
CT-3	Ceramic Tile (Wall)	0135 Almond; Semi-Gloss Glazed Ceramic- 2" x 6" Bullnose	Daltile	
CT-4	Ceramic Tile (Accent)	0078 Gloss Cappuccino; Semi-Gloss Glazed Ceramic- 1/2" x 6" Liner	American Olean	
PT-1	Porcelain Tile (Floor)	Color Blox, A1101 Sand Box- 6" x 6" Tile	Crossville/Childrest Tile	
PT-2	Porcelain Tile (Floor)	Color Blox, A1104 It's a Boy- 6" x 6" Tile	Crossville/Childrest Tile	
PT-3	Porcelain Tile (Base)	Color Blox, A1104 It's a Boy- 6" x 12" Cove Base	Crossville/Childrest Tile	
*	Transition Strip	To be determined	To be determined	
*	Grout	Keracolor, Color to be selected by Interior Designer from Manufacturer's full color range	Mapei	
ACOUSTICAL CEILING - Division 9				
AC-1	Acoustical Ceiling	#1772 Dune, White, 24" x 24" x 5/8"; Square Lay-In Panel w/ Prelude 15/16" Exposed Tee Grid, White	Armstrong	
AC-2	Acoustical Ceiling	#605 Ceramaguard Unperforated, White, 24" x 24" x 5/8"; Square Edge Lay-In Panel w/ Prelude 15/16" Exposed Tee Grid, White	Armstrong	
RESILIENT FLOORING - Division 9				
RB-1	Resilient Base	45 Sandalwood; Vinyl- 6" high	Johnsonite	
SV-1	Sheet Vinyl Weld Rod	Forestscapes, 73801 Honey Oak; Rollgoods- 6'-0" Wide Provide Manufacturer's Recommended Matching Weld Rod	Teknofloor/Shannon Sales	
VCT-1	Vinyl Composition Tile	Colorpoint, 643 Buttermilk- 12" x 12" Tile	Mannington Commercial	
VCT-2	Vinyl Composition Tile	Solidpoint, 340 Blue Ridge- 12" x 12" Tile	Mannington Commercial	
VCT-3	Vinyl Composition Tile	Solidpoint, 338 Cherrywood- 12" x 12" Tile	Mannington Commercial	
VCT-4	Vinyl Composition Tile	Solidpoint, 337 Toasted Sesame- 12" x 12" Tile	Mannington Commercial	
*	Transition Strip	Profile to be determined; Color to be selected by Interior Designer from Manufacturer's full color line	Johnsonite	
PAINTING / STAINING - Division 9 (Refer to Room Finish Schedule for Finish Designation) PAE, PAF, PAS, PAT or PAX				
PA-1	Paint	HC-45 Shaker Beige; Glass Level 4	Benjamin Moore	
PA-2	Paint	2106-40 Cougar Brown; Glass Level 4	Benjamin Moore	
PA-3	Paint	Color to be determined; Glass Level 4	Benjamin Moore	
STN-1	Stain (On White Birch- Rotary Cut)	Clear		
MISC SPECIALTIES - Division 10				
CC-1	Cubicle Curtain	To be determined	To be determined	
*	Cubicle Curtain Mesh	To be determined	To be determined	
HR-1	Hand Rail	800 Series Handrail, 0114 Haze- 5 1/2" High	InPro Corporation	
CG-1	Corner Guard	150 Series Surface Mount Corner Guards, 0114 Haze- 3" Wing	InPro Corporation	

