

FOOTING SCHEDULE (PROPORTIONED FOR 4,000 PSF)		
FOOTING MARK	SIZE LxWxT	REINF EW BOT UNO
F40	4'-0" x 4'-0" x 12"	(4) #5
F50	5'-0" x 5'-0" x 14"	(5) #5
F66	6'-6" x 6'-6" x 18"	(6) #6
F70	7'-0" x 7'-0" x 19"	(7) #6
F80	8'-0" x 8'-0" x 22"	(9) #6
W30	3'-0" x 1'-0" T x CONT	NONE