

SECTION 105113 - METAL LOCKERS

PART 1 -GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Standard metal lockers.

B. Related Section:

1. Division 6 Sections for "Miscellaneous Rough Carpentry" for wood furring.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product indicated. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of metal locker.

B. Shop Drawings: For metal lockers. Include plans, elevations, sections, details, and attachments to other work.

- 1 Show locker trim and accessories.
- 2 Include locker identification system and numbering sequence.
- 3 Include fillers, base, and sloping tops.

C. Samples for Initial Selection: For units with factory-applied color finishes.

D. Samples for Verification: For metal lockers locker benches, in manufacturer's standard sizes.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For qualified Installer.

B. Warranty: Sample of special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For adjusting, repairing, and replacing locker doors and latching mechanisms to include in maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Full-size units of the following metal locker hardware items equal to 10 percent of amount installed for each type and finish installed, but no fewer than five units:

- ☐ Locks.
- ☐ Identification plates.
- ☐ Hooks.

1.7 QUALITY ASSURANCE

A. Installer Qualifications: Manufacturer's authorized representative who is trained and approved for installation of units required for this Project.

B. Source Limitations: Obtain metal lockers and accessories from single source from single manufacturer.

C. Regulatory Requirements: Where metal lockers are indicated to comply with accessibility requirements, comply with the U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disabilities Act (ADA) and Architectural Barriers Act (ABA) Accessibility Guidelines for Buildings and Facilities" and ICC/ANSIA117.1.

D. Pre-installation Conference: Conduct conference at Project site.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Do not deliver metal lockers until spaces to receive them are clean, dry, and ready for their installation.

B. Deliver master and control keys and combination control charts to Owner by registered mail or overnight package service.

C. Protect lockers from damage during delivery, handling, storage, and installation.

1.9 PROJECT CONDITIONS

A. Field Measurements: Verify actual dimensions of recessed openings by field measurements before fabrication.

1.10 COORDINATION

A. Coordinate sizes and locations for metal lockers.

B. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of work specified in other Sections to ensure that metal lockers can be supported and installed as indicated.

1.11 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of metal lockers that fail in materials or workmanship, excluding finish, within specified warranty period.

1. Failures include, but are not limited to, the following:

- ☐ Structural failures.
- ☐ Faulty operation of latches and other door hardware.

- 2 Damage from deliberate destruction and vandalism is excluded.
- 3 Warranty Period for Knocked-Down Metal Lockers: Two years from date of Substantial Completion.

PART 2 -PRODUCTS

2.1 MATERIALS

- A. Cold-Rolled Steel Sheet: ASTM A 1008/A 1008M, Commercial Steel (CS), Type B, suitable for exposed applications.
- B. Metallic-Coated Steel Sheet: ASTM A 653/A 653M, Commercial Steel (CS), Type B; with A60 (ZF180) zinc-iron, alloy (galvannealed) coating designation.
- C. Stainless-Steel Sheet: ASTM A 666, Type 304.
- D. Steel Tube: ASTM A 500, cold rolled.
- E. Fasteners: Zinc- or nickel-plated steel, slotless-type, exposed bolt heads; with self-locking nuts or lock washers for nuts on moving parts.
- F. Anchors: Material, type, and size required for secure anchorage to each substrate.
- 1 Provide nonferrous-metal or hot-dip galvanized anchors and inserts on inside of walls for corrosion resistance.
 - 2 Provide toothed-steel or lead expansion sleeves for drilled-in-place anchors.

2.2 STANDARD METAL LOCKERS

- A. Products: Subject to compliance with requirements, provide one of the following:
- 1 List Industries Inc.; Classic Line of Superior KD Lockers.
 - 2 Republic Storage Systems Company; Designer Lockers.
- B. Locker Arrangement: Double tier, each tier to be 12"x12"x36".

C. Body: Assembled by riveting or bolting body components together. Fabricate from unperforated steel sheet as follows:

- 1 Tops, Bottoms, and Intermediate Dividers: 0.024-inch (0.61-mm) nominal thickness, with single bend at sides.
- 2 Backs and Sides: 0.024-inch (0.61-mm) nominal thickness, with full-height, double-flanged connections.
- 3 Shelves: 0.024-inch (0.61-mm) nominal thickness, with double bend at front and single bend at sides and back.

D. Frames: Channel formed; fabricated from 0.060-inch (1.52-mm) nominal-thickness steel sheet; lapped and factory welded at corners; with top and bottom main frames factory welded into vertical main frames. Form continuous, integral door strike full height on vertical main frames.

1. Cross Frames between Tiers: Channel formed and fabricated from same material as main frames; welded to vertical main frames.

E. Doors: One piece; fabricated from 0.060-inch (1.52-mm) nominal-thickness steel sheet; formed into channel shape with double bend at vertical edges and with right-angle single bend at horizontal edges.

1. Doors less than 12 inches (305 mm) wide may be fabricated from 0.048-inch (1.21-mm) nominal-thickness steel sheet.
2. Doors for box lockers less than 15 inches (381 mm) wide may be fabricated from 0.048-inch (1.21-mm) nominal-thickness steel sheet.
3. Reinforcement: Manufacturer's standard reinforcing angles, channels, or stiffeners for doors more than 15 inches (381 mm) wide; welded to inner face of doors.
4. Stiffeners: Manufacturer's standard full-height stiffener fabricated from 0.048-inch (1.21-mm) nominal-thickness steel sheet; welded to inner face of doors.
5. Door Style: Vented panel as follows:
 - a. Louvered Vents: No fewer than three louver openings at top and bottom for double-tier lockers.

F. Hinges: Welded to door and attached to door frame with no fewer than two factory-installed rivets per hinge that are completely concealed and tamper resistant when door is closed; fabricated to swing 180degrees[; **self-closing**].

1. Continuous Hinges: Manufacturer's standard, steel, full height.

G. Recessed Door Handle and Latch: Stainless-steel cup with integral door pull, recessed so locking device does not protrude beyond face of door; pry and vandal resistant.

1. Single-Point Latching: Nonmoving latch hook designed to engage bolt of built-in combination or cylinder lock.
 - a. Latch Hook: Equip each door with one latch hook, fabricated from 0.105-inch (2.66-mm) nominal-thickness steel sheet; welded midway up full-height door strike; with resilient silencer.

H. Built-in Combination Locks: Key-controlled, three-number dialing combination locks; capable of at least five combination changes made automatically with a control key.

1. Bolt Operation: automatically locking spring bolt.

I. Equipment: Equip each metal locker with identification plate and the following unless otherwise indicated:

- 1 Double-Tier Units: One double-prong ceiling hook and two single-prong wall hooks attached with at least two fasteners.
- 2 Coat Rods: For each compartment of double-tier metal lockers.

J. Accessories:

1. Continuous Zee Base: Fabricated from manufacturer's standard thickness, but not less than 0.060-inch (1.52-mm) nominal-thickness steel sheet.
 - a. Height: 4 inches (102 mm).
2. Continuous Sloping Tops: Fabricated from manufacturer's standard thickness, but not less than 0.036-inch (0.91-mm) nominal-thickness steel sheet.
 - ☐ Closures: Vertical -end type.
 - ☐ Sloping-top corner fillers, mitered.
3. Filler Panels: Fabricated from manufacturer's standard thickness, but not less than 0.048-inch (1.21-mm) nominal-thickness steel sheet.
4. Boxed End Panels: Fabricated from 0.060-inch (1.52-mm) nominal-thickness steel sheet.
5. Finished End Panels: Fabricated from 0.024-inch (0.61-mm) nominal-thickness steel sheet.
6. Finish: Baked enamel.
7. Color(s): As selected by Architect from manufacturer's full range.

K. Material: Cold-rolled steel sheet.

L. Body: Assembled by welding body components together. Fabricate from unperforated steel sheet with thicknesses as follows:

- 1 Tops, Bottoms, and Sides: 0.060-inch (1.52-mm) nominal thickness.
- 2 Backs: 0.048-inch (1.21-mm) nominal thickness.
- 3 Shelves: 0.060-inch (1.52-mm) nominal thickness, with double bend at front and single bend at sides and back.

M. Frames: Channel formed; fabricated from 0.060-inch (1.52-mm) nominal-thickness steel sheet; lapped and factory welded at corners; with top and bottom main frames factory welded into vertical main frames. Form continuous, integral door strike full height on vertical main frames.

1. Cross Frames between Tiers: Channel formed and fabricated from same material as main frames; welded to vertical main frames.

N. Doors: One piece; fabricated from 0.075-inch (1.90-mm) nominal-thickness steel sheet; formed into channel shape with double bend at vertical edges and with right-angle single bend at horizontal edges.

1. Reinforcement: Manufacturer's standard reinforcing angles, channels, or stiffeners for doors more than 15 inches (381 mm) wide; welded to inner face of doors.

O. Hinges: Welded to door and attached to door frame with no fewer than two factory-installed rivets per hinge that are completely concealed and tamper resistant when door is closed; fabricated to swing 180degrees[; **self-closing**].

P. Material: steel sheet.

2.3 FABRICATION

A. Fabricate metal lockers square, rigid, and without warp and with metal faces flat and free of dents or distortion. Make exposed metal edges safe to touch and free of sharp edges and burrs.

- 1 Form body panels, doors, shelves, and accessories from one-piece steel sheet unless otherwise indicated.
- 2 Provide fasteners, filler plates, supports, clips, and closures as required for complete installation.

B. Fabricate each metal locker with an individual door and frame; individual top, bottom, and back; and common intermediate uprights separating compartments. Factory weld frame members of each metal locker together to form a rigid, one-piece assembly.

C. Knocked-Down Construction: Fabricate metal lockers using nuts, bolts, screws, or rivets for nominal assembly at Project site.

D. Accessible Lockers: Fabricate as follows:

- 1 Locate bottom shelf no lower than 15 inches (381 mm) above the floor.
- 2 Where hooks, coat rods, or additional shelves are provided, locate no higher than 48 inches (1219 mm) above the floor.

E. Hooks: Manufacturer's standard ball-pointed type, aluminum or steel; zinc plated.

F. Identification Plates: Manufacturer's standard, etched, embossed, or stamped aluminum plates, with numbers and letters at least 3/8 inch (9 mm) high. Number lockers in sequence indicated. Attach plates to each locker door, near top, centered, with at least two aluminum rivets.

G. Continuous Base: Formed into channel or zee profile for stiffness, and fabricated in lengths as long as practical to enclose base and base ends of metal lockers; finished to match lockers.

H. Continuous Sloping Tops: Fabricated in lengths as long as practical, without visible fasteners at splice locations; finished to match lockers.

1. Sloping-top corner fillers, mitered.

I. Filler Panels: Fabricated in an unequal leg angle shape; finished to match lockers. Provide slip-joint filler angle formed to receive filler panel.

J. Boxed End Panels: Fabricated with 1-inch-(25-mm-) wide edge dimension, and designed for concealing fasteners and holes at exposed ends of nonrecessed metal lockers; finished to match lockers.

1. Provide one-piece panels for double-row (back-to-back) locker ends.

K. Finished End Panels: Designed for concealing unused penetrations and fasteners, except for perimeter fasteners, at exposed ends of nonrecessed metal lockers; finished to match lockers.

1. Provide one-piece panels for double-row (back-to-back) locker ends.

2.4 STEEL SHEET FINISHES

A. Factory finish steel surfaces and accessories except stainless-steel and chrome-plated surfaces.

B. Baked-Enamel Finish: Immediately after cleaning, pre-treating, and phosphatizing, apply manufacturer's standard thermosetting baked-enamel finish. Comply with paint manufacturer's written instructions for application, baking, and minimum dry film thickness.

PART 3 -EXECUTION

3.1 EXAMINATION

A. Examine walls, floors, and support bases, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. General: Install level, plumb, and true; shim as required, using concealed shims.

1. Anchor locker runs at ends and at intervals recommended by manufacturer, but not more than 36 inches (910 mm) o.c. Using concealed fasteners, install anchors through backup reinforcing plates, channels, or blocking as required to prevent metal distortion.
2. Anchor single rows of metal lockers to walls near top and bottom of lockers.

B. Knocked-Down Metal Lockers: Assemble with standard fasteners, with no exposed fasteners on door faces or face frames.

C. Equipment and Accessories: Fit exposed connections of trim, fillers, and closures accurately together to form tight, hairline joints, with concealed fasteners and splice plates.

1. Attach hooks with at least two fasteners.
2. Attach door locks on doors using security-type fasteners.
3. Identification Plates: Identify metal lockers with identification indicated on Drawings.
 - a. Attach plates to each locker door, near top, centered, with at least two aluminum rivets.
4. Attach filler panels with concealed fasteners. Locate filler panels where indicated on Drawings.
5. Attach sloping-top units to metal lockers, with closures at exposed ends.
6. Attach boxed end panels with concealed fasteners to conceal exposed ends of non-recessed metal lockers.
7. Attach finished end panels with fasteners only at perimeter to conceal exposed ends of non-recessed metal lockers.

3.3 ADJUSTING, CLEANING, AND PROTECTION

A. Clean, lubricate, and adjust hardware. Adjust doors and latches to operate easily without binding. Verify that integral locking devices operate properly.

B. Protect metal lockers from damage, abuse, dust, dirt, stain, or paint. Do not permit use during construction.

C. Touch up marred finishes, or replace metal lockers that cannot be restored to factory-finished appearance. Use only materials and procedures recommended or furnished by locker manufacturer.

END OF SECTION **105113**