

SECTION 09 66 13  
PORTLAND CEMENT TERRAZZO FLOORING

**PART 1 - GENERAL**

**1.1 DESCRIPTION**

This section covers the requirements for patching existing cementitious terrazzo including adhesively bonded monolithic terrazzo.

**1.2 RELATED WORK**

- A. Concrete Sub Floor: Section 03 30 00, CAST-IN-PLACE CONCRETE.
- B. Color and location of each Terrazzo Formula: Match existing.

**1.3 QUALITY ASSURANCE**

- A. Comply with recommendations of National Terrazzo and Mosaic Association, Inc. (NTMA).
- B. Provide certification that materials provided meet or exceed specified NTMA properties.

**1.4 APPLICABLE PUBLICATIONS**

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. American Society for Testing and Materials (ASTM):
  - A185-07.....Steel Welded Wire Reinforcement, Plain, for Concrete
  - C33-11.....Concrete Aggregates
  - C150-09.....Portland Cement
- C. National Terrazzo and Mosaic Association (NTMA):
  - Terrazzo Specifications and Design Guide

**PART 2 - PRODUCTS**

**2.1 PORTLAND CEMENT**

ASTM C150, Type 1, nonstaining, Color as required to match existing aged cement.

**2.2 SAND**

ASTM C33 for fine aggregate.

**2.3 MARBLE GRANULES**

Comply with NTMA requirements. Crushed marble chips not containing any foreign matter. Uniformly graded from 3 mm to 9 mm (1/8 inch to 3/8 inch).

**2.4 COLORANT**

Alkali - resistant and nonfading mineral oxide pigment to match existing.

## **2.5 METAL STRIPS**

- A. Match existing adjacent.

## **2.6 CLEANING SOLUTION**

Use a neutral chemical cleaner, produced by manufacturer of preservative solution that will not change color of or damage terrazzo.

## **2.7 SEALER**

Sealer shall have a pH factor between 7 and 10 and be a penetrating type specially prepared for the terrazzo trade. The sealer shall not discolor or amber the terrazzo and shall produce a slip resistant surface.

## **2.8 TERRAZZO PROPORTIONS**

- A. Underbed: Underbed shall be composed of one part portland cement to 4-1/2 parts sand and sufficient water to provide workability at as low a slump as possible, or as required to match existing adjacent construction.
- B. Terrazzo Topping: Follow NTMA recommendations for mixes.

## **PART 3 - EXECUTION**

### **3.1 INSTALLING METAL STRIPS**

- A. Set strips with close, butt joints, true and square; hold in place with cement mortar, except where specified to be held with adhesive.
- B. Set base divider strips plumb for cast-in-place base. Anchor and space them not over 1500 mm (5 feet) on centers, or to align with floor divider strips. Set them symmetrically at door and other openings and wall breaks and in line with field divider strips of floor.
- C. Use floor divider, T-strips for adhesive bonded monolithic terrazzo floors, located as shown on drawings. Set strips with same adhesive used for bonding terrazzo topping, and shim where necessary to produce a straight and level floor. Tightly butt strips at intersection, and install 24 hours prior to floor installation.

### **3.2 INSTALLING TERRAZZO FLOORS**

- A. Bonded to Concrete Terrazzo: Shall consist of an underbed and terrazzo topping on a rough concrete slab. Finish terrazzo floors a minimum of 44 mm (1-3/4 inches) above rough concrete slab. Surfaces of concrete slabs to receive terrazzo shall be cleaned of plaster, oil, grease, and foreign matter. Saturate slabs with water, remove all excess and then, immediately before placing underbed, slush and broom concrete with neat cement. Underbed shall be a minimum of 32 mm (1-1/8 inches) thick. Wet cement-sand mix to proper consistency and spread evenly over surfaces to receive terrazzo. Provide shrinkage reinforcement of 50 mm (2 inch) wire

- mesh (16 gage). Finish underbed to true, level surface, and prepare and condition it to receive terrazzo topping and ensure permanent bond.
- B. Monolithic Terrazzo: Shall consist of terrazzo topping placed integrally on prepared concrete slab. Broom clean concrete slabs to receive terrazzo. Before placing of terrazzo topping, saturate slabs with water until all absorption by concrete has stopped. Remove all excess water. Place terrazzo over prepared slab in one continuous operation.
  - C. Topping: Spread topping to provide finished thickness of 10 mm (3/8 inch) (after grinding) on vertical surfaces, and 16 mm (5/8 inch) on horizontal surfaces. Provide topping in uniform composition, and use same marble granules that appear on surface for its entire thickness. Trowel and pack base to proper form, and roll floor and thresholds with heavy roller so that terrazzo will be dense with even surface showing at least 70 percent marble granules. Lay terrazzo topping full above strips to permit grinding terrazzo down to finish floor level.

### 3.3 INSTALLING BASES

- A. Provide base to match existing height, and with 25 (one inch) radius cove at bottom. Make external corners of base conform to contour of wall finish above. Provide square toe or cove at corners of floor field.
- B. Round top of projecting base to 6 mm (1/4 inch) radius.
- C. At openings having metal door frames, return base on itself, with toe or cove in line with back edge of metal frame.

### 3.4 CURING

- A. Cure terrazzo topping at least six days before grinding and until it sets sufficiently hard to permit coarse stone grinding without dislodging surface aggregate. Curing time for terrazzo base may be reduced to four days, subject to approval of Resident Engineer. During curing period, cover terrazzo with either water proof paper, cotton mats, or one inch of clean wet sand. Lap and secure against displacement of joints in paper or mats. Keep sand (if used) wet by sprinkling with clean water at intervals of not more than eight hours. Do final grinding or rubbing of terrazzo before finish coat of plaster or other connecting wall finish is applied.

### 3.5 GRINDING

- A. After curing, wet-grind terrazzo to smooth even surface, then grout with neat white portland cement paste of creamy consistency, filling voids. Grout shall remain on surfaces not less than two days and be removed by final grinding. Grind terrazzo surfaces with electric grinding machines. Where impossible to use machines, hand rub surfaces. Dry grinding of terrazzo is prohibited.

- B. Final grinding or rubbing to terrazzo shall remove scratches, and produce true surface of uniform color and texture, without irregularities. When tested with steel straight edge, terrazzo base surfaces shall not show wave exceeding 1.6 mm (1/16 inch) between divider strips. When tested with steel straight edge 900 mm (three feet) long, floor surfaces shall not show wave exceeding 0.8 mm (1/32 inch). Protect adjacent walls, floors, and other connecting work from rubbing stones and from splashing, while grinding is in progress.

### 3.6 CLEANING

After final grinding, clean terrazzo and condition to counteract efflorescence. Apply mixture of not less than one part of liquid cleaner to three parts of water and allow it to soak uniformly into terrazzo from fifteen to thirty minutes, keeping surfaces wet.

### 3.7 SEALING

- A. After surfaces are dry, wash and rinse terrazzo and (except on terrazzo surfaces containing nonslip aggregate) apply coat of sealer. Buff terrazzo surfaces with a weighted polishing brush or electric buffing machine.
- B. After plastering work is completed and terrazzo cleaned, wash terrazzo work with soap and water and leave in finished, polished condition. Cover and protect terrazzo until completion of the work of all other trades.

### 3.8 ALTERATIONS

- A. In altered rooms and areas where terrazzo floors and base occurs, patch, repair and replace existing terrazzo, and provide new terrazzo to match existing similar work in composition, color, height, shape and finish. Use divider strips to match existing. Cure terrazzo at least six days before grinding. Then grout with neat portland cement to fill voids. After two days, remove grout by final grinding. Dry grinding is prohibited. After final grinding, clean terrazzo. After surfaces are dry, wash and rinse terrazzo, and apply coat of sealer. Buff terrazzo surfaces with electric buffing machine.

- - - E N D - - -