Proposal

[redacted]

Veterans Affairs
[redacted]

DATE: [redacted]

Modernfold Operable Partition

We propose to furnish and install one (1) Modernfold Acousti-Seal Encore for one (1) opening approximately 15'-8" x 8'-0".

[redacted]

Price Includes:

- Manually operated
- Single panels
- 54 STC
- 2" SureSet manual bottom seals
- SureSet automatic top seals
- Modernfold standard vinyl finish
- #17 track painted white

-Structural support, beam punching, wood blocking and sound baffle **NOT** by [redacted]
-All wiring to be by electrician (main power and low voltage).
-Hoisting to installation location (if required) **NOT** by [redacted]. Must fit in elevator or job on 1st Floor.

DELIVERY: Approximately 7-8 weeks.
Track in stock in our warehouse.
Shop drawings available in 1 week.

[redacted]