

NOTES:

1. TERMINATE CAT 6 CABLE WITH RJ-45 PLUG FOR DIRECT CONNECTION TO CAMERA.
2. PROVIDE WITH ENVIRONMENTAL ENCLOSURE AND MOUNT FOR ALL OUTDOOR APPLICATIONS.

VS-FDC-1	OPTICAL FIBER DISTRIBUTION CABINET, COMBINATION SHELF, 96 FIBER CAPACITY, DETACHABLE FRONT PANEL, LC CONNECTORS. REQUIRES (2) 1.75" MOUNTING SPACES. PROVIDE LC COUPLER PANELS AS REQUIRED FOR COMPLETE INSTALLATION.	HITACHI COMMSCOPE SYSTIMAX HD-ZU HUBBELL HITACHI AMS
VS-INJ-1	8 PORT 15.4W PER PORT MID SPAN INJECTOR, IEEE 802.3AF COMPLIANT POWER INJECTOR FOR STANDARD CAT 6	AMS

**ISSUED FOR
SOLICITATION
FULLY SPRINKLERED**