


### SEQUENCE OF OPERATIONS SUMP PUMP (SP-X)

**General Description**  
There are two (2) separate sump pumps. One sump pump lifts fluid out of the elevator pit during a leak and discharges to an oil water separator. The other lifts storm water from the foundation and discharges on grade.


POINTS LIST - SUMP PUMP												
POINT NAME	HARDWARE POINTS				SOFTWARE POINTS						SHOWN ON GRAPHIC	
	AI	AO	BI	BO	AV	BV	LOOP	SCHED	TREND	ALARM		
<b>PUMPS</b>												
SP-1												
SP-2												
<b>ALARMS</b>												
FAILURE										X		10 MIN.
IN HAND										X		10 MIN.
START										X		10 MIN.
<b>NOTES:</b> 1 SEE STANDARD TRENDRING POINTS LIST SCHEDULE ON SHEET M-701 FOR APPLICABLE TREND INTERVALS.												



### SEQUENCE OF OPERATIONS OIL WATER SEPARATOR (OWS)


**General Description**  
The oil water separator receives fluid from the elevator sump pump and discharges to the sanitary main.

POINTS LIST - OIL WATER SEPARATOR												
POINT NAME	HARDWARE POINTS				SOFTWARE POINTS						SHOWN ON GRAPHIC	
	AI	AO	BI	BO	AV	BV	LOOP	SCHED	TREND	ALARM		
<b>PUMPS</b>												
OWS												
<b>ALARMS</b>												
HIGH LEVEL										X		10 MIN.
<b>NOTES:</b> 1 SEE STANDARD TRENDRING POINTS LIST SCHEDULE ON SHEET M-701 FOR APPLICABLE TREND INTERVALS.												




### SEQUENCE OF OPERATIONS STEAM CONDENSATE PUMP (CP-X) TYPICAL CONTROL DIAGRAM

POINTS LIST SCHEDULE (CP-X)												
POINT NAME	HARDWARE POINTS				SOFTWARE POINTS						SHOWN ON GRAPHIC	
	AI	AO	BI	BO	AV	BV	LOOP	SCHED	TREND	ALARM		
<b>PUMPS</b>												
PUMP 1 START/STOP										X		X
PUMP 2 START/STOP										X		X
<b>RECEIVER</b>												
WATER LEVEL										X		X
<b>ALARMS</b>												
COMMON ALARM										X		10 MIN.
HIGH WATER LEVEL ALARM										X		5 MIN.
CONDENSATE PUMP START/STOP										X		10 MIN.
<b>NOTES:</b> 1 SEE STANDARD TRENDRING POINTS LIST SCHEDULE ON SHEET M-701 FOR APPLICABLE TREND INTERVALS.												



### SEQUENCE OF OPERATIONS DOMESTIC ELECTRIC WATER HEATER (WH-1) NOT TO SCALE

POINTS LIST - DOMESTIC STEAM TO WATER HEATER (WH-1)												
POINT NAME	HARDWARE POINTS				SOFTWARE POINTS						SHOWN ON GRAPHIC	
	AI	AO	BI	BO	SETPOINT	AV	BV	LOOP	SCHED	TREND		ALARM
<b>WATER SIDE</b>												
WH-1 HWS TEMPERATURE											X	X
<b>SETPOINTS</b>												
WH-1 HWS TEMPERATURE SETPOINT					140 F						X	X
<b>ALARMS</b>												
WH-1 HIGH HWS TEMPERATURE											X	10 MIN.
WH-1 LOW HWS TEMPERATURE											X	10 MIN.



### SEQUENCE OF OPERATIONS HOT/COLD WATER RECIRCULATION PUMPS (RP-X)

POINTS LIST SCHEDULE - RECIRCULATION PUMP (RP-X)												
POINT NAME	HARDWARE POINTS				SOFTWARE POINTS						SHOWN ON GRAPHIC	
	AI	AO	BI	BO	AV	BV	LOOP	SCHED	TREND	ALARM		
<b>PUMPS</b>												
CWR PUMP STATUS										X	X	X
HWR PUMP STATUS										X	X	X
CWR PUMP START/STOP										X		X
HWR PUMP START/STOP										X		X
CWR PUMP FLOW RATE										X	X	X
HWR PUMP FLOW RATE										X	X	X
CWR PUMP FLOW RATE										X	X	X
HWR PUMP FLOW RATE										X	X	X
HWR/CWR TEMPERATURE										X		X
<b>ALARMS</b>												
CWR PUMP FAILURE										X		10 MIN.
CWR PUMP IN HAND										X		10 MIN.
CWR PUMP RUNTIME EXCEEDED										X		10 MIN.
CWR PUMP HIGH/LOW FLOW RATE										X		10 MIN.
HWR PUMP FAILURE										X		10 MIN.
HWR PUMP IN HAND										X		10 MIN.
HWR PUMP RUNTIME EXCEEDED										X		10 MIN.
HWR PUMP HIGH/LOW FLOW RATE										X		5 MIN.
LOW HWR / CWR TEMPERATURE										X		5 MIN.

**1**  
**SHEET REVISED  
AND REISSUED.**

### SEQUENCE OF OPERATIONS STEAM CONDENSATE PUMP (CP-X) REPLACEMENT WAREHOUSE GENERAL DESCRIPTION

The duplex steam condensate pump with condensate storage tank and manufacturer provided control panel provides steam condensate removal from the steam supply system as shown on the drawings.


#### COMPONENT CONTROLS

##### PUMP 1

The pump shall be activated (subject to the unit manufacturer's standard unitary safeties and controls) upon receiving a water level status.

##### PUMP 2

Upon failure of Pump 1, Pump 2 shall be activated (subject to the unit manufacturer's standard safeties and controls) upon receiving a water level status.



### SEQUENCE OF OPERATIONS HEATING HOT WATER HEAT EXCHANGER CONTROL DIAGRAM

POINTS LIST - HEAT EXCHANGER (HX-X)												
POINT NAME	HARDWARE POINTS				SOFTWARE POINTS						SHOWN ON GRAPHIC	
	AI	AO	BI	BO	SETPOINT	AV	BV	LOOP	SCHED	TREND		ALARM
<b>STEAM SIDE</b>												
STEAM VALVE 1/3												X
STEAM VALVE 2/3												X
<b>WATER SIDE</b>												
HWS TEMPERATURE											X	X
HWR TEMPERATURE											X	X
<b>SETPOINTS</b>												
OUTSIDE AIR TEMPERATURE									SEE SEQ.			X
HWS TEMPERATURE SETPOINT									160 F			X
HWR TEMPERATURE SETPOINT									140 F			X
<b>ALARMS</b>												
HIGH HWS TEMPERATURE											X	10 MIN.
LOW HWS TEMPERATURE											X	10 MIN.
<b>NOTES:</b> 1 SEE STANDARD TRENDRING POINTS LIST SCHEDULE ON SHEET M-701 FOR APPLICABLE TREND INTERVALS.												

### SEQUENCE OF OPERATIONS HEATING HOT WATER PUMPS

**General Description**  
The inline pumps will operate as lead/standby to provide heating hot water to the AHU preheat coils and VAV reheat coils as shown on the drawings. 1 primary pump(s) will operate as lead, while the remaining pump will operate as standby and is to be activated upon shutdown or failure of the primary pump.

#### MODES OF OPERATION

##### NORMAL OPERATING MODE:

The pumps shall be in normal operating mode at all times unless overridden by the other modes outlined in this sequence.

##### STANDBY MODE:

Backup mode shall be activated upon failure of the lead pump. Backup mode shall be disabled by manual reset and the system will reset to normal operation.

#### COMPONENT CONTROLS

##### LEAD PUMP

##### NORMAL OPERATING MODE:

The controller shall modulate the pump to maintain the differential pressure setpoint as determined by final test and balance. The VFDs minimum speed shall not drop below 20%.

##### STANDBY MODE:

The pump shall be off.


##### STANDBY PUMP

##### NORMAL OPERATING MODE:

The pump shall be off.

##### STANDBY MODE:

The controller shall modulate the pump to maintain the differential pressure setpoint as determined by final test and balance. The VFDs minimum speed shall not drop below 20%.



### SEQUENCE OF OPERATIONS RECIRCULATING PUMP CONTROL DIAGRAM

POINTS LIST - HEATING HOT WATER PUMPS												
POINT NAME	HARDWARE POINTS				SOFTWARE POINTS						SHOWN ON GRAPHIC	
	AI	AO	BI	BO	AV	BV	LOOP	SCHED	TREND	ALARM		
<b>PUMPS</b>												
DIFFERENTIAL PRESSURE											X	X
PUMP 1 VFD SPEED											X	X
PUMP 2 VFD SPEED											X	X
PUMP 1 STATUS											X	X
PUMP 1 VFD FAULT											X	X
PUMP 2 STATUS											X	X
PUMP 2 VFD FAULT											X	X
PUMP 1 START/STOP											X	X
PUMP 2 START/STOP											X	X
DIFFERENTIAL PRESSURE SETPOINT											X	X
OUTSIDE AIR TEMP											X	X
<b>ALARMS</b>												
PUMP 1 FAILURE											X	10 MIN.
PUMP 1 IN HAND											X	10 MIN.
PUMP 1 RUNTIME EXCEEDED											X	10 MIN.
PUMP 2 FAILURE											X	10 MIN.
PUMP 2 IN HAND											X	10 MIN.
PUMP 2 RUNTIME EXCEEDED											X	10 MIN.
HIGH DIFFERENTIAL PRESSURE											X	5 MIN.
LOW DIFFERENTIAL PRESSURE											X	5 MIN.
<b>NOTES:</b> 1 SEE STANDARD TRENDRING POINTS LIST SCHEDULE ON SHEET M-701 FOR APPLICABLE TREND INTERVALS.												

### CONSULTANT INFORMATION

**STRUCTURAL / CIVIL ENGINEER**  
H2B, INC.  
1225 N. LOOP WEST, SUITE 800  
HOUSTON, TX 77008  
(713) 864-2900

**COMMISSIONING**  
GLNH ARCHITECTS & ENGINEERS, INC.  
2939 E. BROADWAY BLVD  
TUCSON, AZ 85716  
(520) 881-4546

**MECH. / ELEC. / PLUMB. / TECH ENGINEER**  
SPUR DESIGN  
11020 KING STREET, SUITE 350  
OVERLAND PARK, KS 66210  
(405) 842-6100

**FIRE PROTECTION ENGINEER**  
POOLE FIRE PROTECTION, INC.  
1910 W. 161ST STREET  
OLATHE, KS 66062  
(913) 824-8859

**LANDSCAPE ARCHITECT**  
ARC STUDIOS INC.  
3117 E. FLOWER STREET  
TUCSON, AZ 85716  
(520) 824-9555

### ARCHITECT

**SPUR DESIGN**

311 SW 25th Street  
Oklahoma City, OK 73109  
spur-design.com

10200 King Street, Suite 350  
Overland Park, KS 66210  
spur-design.com

### Office of Construction and Facilities Management

**VA** U.S. Department of Veteran Affairs

### SHEET TITLE MECHANICAL CONTROLS VI

APPROVED: PROJECT DIRECTOR

### PROJECT PHASE BID DOCUMENTS

FULLY SPRINKLERED

### PROJECT TITLE CONSTRUCT REPLACEMENT WAREHOUSE

PROJECT LOCATION  
500 AZ-89, PRESCOTT, AZ 86301

DATE  
04/23/2019

CHECKED BY  
JES

DRAWN BY  
JAD

VA PROJECT NUMBER  
649-414

BUILDING NUMBER  
165

DRAWING NUMBER  
165-M-706

Dwg. 116 OF 145