



SPECIFICATIONS	
Engine	TV35 G Kubota 49 HP 4-Cylinder TV35 D Kubota 44 HP 4-Cylinder
Configuration	Self-contained, 4-wheel configuration with front steering, two rear drive wheels and a rear mounted, high-lift, debris hopper with patented Recirculating Vacuum Air Technology
Construction	¼" and 7 gauge steel frame
Blower Fan	25" dia. abrasion resistant steel with replaceable machined UHMW, poly liner and 1.5" shaft with self-aligned bearings supporting both ends
Compaction	17.5 psi in front, 18.2 psi in rear
Sweeper	60" single sweeping head, follows all terrain with rear mounted roller on sweeper head (vertical float), rises to transport position, lowers to operating position by hydraulic cylinders
Hopper Capacity	3.5 cubic yards
Lift	Rises 6'4" above the ground to dump debris into vehicle or container
Lift Safety	5° Inclinometer Sensor with lift interlock that prevents hopper from lifting if the machine is on a slope greater than 5°
Gauges	Water temp., oil pressure, volt meter, fuel level and hour meter
Wheels/Tires	5-bolt wheels and front (2) 20-10x10 4-ply premium turf tires rear (2) 26-12x12 6-ply premium turf tires
Drive	Hydrostatic pump drives two high efficiency piston hydraulic wheel motors on rear wheels with two speed operation, traction control and torque transfer capability and foot operated pedal

Speed	Infinitely variable, 0-8 mph low (operation), 0-14 mph high (transport), 0-7 mph reverse (high reverse is locked out)
Braking	Dynamic braking through the hydrostatic drive system, mechanically applied and hydraulically released parking brake on rear
Seat	Adjustable ride suspension, high back and retractable seat belt
Steering	Hydraulic power steering with automotive type steering wheel with tilt function
Electrical	12 volt, electronic key start
Controls	Hydraulic: lift/lower of debris hopper, open/close of debris hopper door, raise/lower of rotor head assembly, rotor on/off and fan on/off
Liquid Capacities	15 gallon fuel tank; 32 gallon hydraulic fluid tank
Hydraulic Oil	Crown AW46; ISO 46 Hydraulic Oil
Safety Features	Includes Certified ROPS and seatbelt, fold away rear view side mirrors and a solid state max grade detection for dump circuit
Dimensions	144"L x 68"W x 91"H; 84" wheel base
Weight	5,220 lbs. (2,368 kg)
Options	Brush, rubber finger and verti-cut with rubber fingers rotors; turn signal/light kit, 8' x 12.5" remote hose attachment, curb brush, canopy, hopper dump extension and backup camera




### Hydraulic Operated Lift Dump

The hydraulic lift dump raises the hopper to a height of 76" to unload debris into a truck or dumpster.



### Turbo Charged Engine

4-cylinder (49 HP Gas or 44 HP Diesel)  
Kubota Engines boast plenty of power and gets the job done quickly and efficiently.



### Hydraulic Cooling System

The hydraulic power cooling fan can be reversed to blow debris off the screen for improved temperature control.