

1 L05323 - SonoSite M-Turbo

SonoSite M-Turbo high-resolution, all-digital, 7.5-pound (3.0 kg) ultrasound system with 10.4 in. digital display. Standard features include display module, 2D grayscale with SonoMB Multi Beam Technology and Auto Gain, with SonoADAPT Tissue Optimization Technology, M-mode, HIPAA compliance tool set, comprehensive application specific calculation packages, PC direct connectivity capability (through USB Memory Stick or via SiteLink - USB Cable ordered separately). Also includes battery, ultrasound gel, and user guides. You can select one of five (5) different exterior color plates to customize your system.

The M-Turbo combines the high performance of cart-based systems with the speed, flexibility and durability of hand-carried ultrasound. 8 GB of on-board Flash memory will retain enough data for over 40 standard exams (or 2,400 seconds of clips, 1,200 still frames and 40 report pages) even after power is turned off. The system supports USB media playback, and connectivity is accomplished through one of two USB slots on the system, which allow for direct sharing of images (JPEG) and Clips (MPEG4) to a PC or Mac. Additional connectivity is achieved via the optional H-Universal Stand or Mini-Dock, to meet your specific needs.

M-Turbo's reliability and durability are backed by a five-year standard warranty, which is included in the price of the system. Software upgrades to the main system and transducer databases are both accomplished through one of the two USB ports on the system.

Additional features available to add to our system include: SonoHD Imaging Technology image processing, ColorHD, Tissue Harmonic Imaging, PW Doppler, TDI PW, CW Doppler, DICOM Bundle, Credentialing Worksheets, ACO, MSK Worksheets and a full array of multi-frequency, broadband transducers. This product is designed with an intuitive interface with Chip Fusion Technology.

Included with the purchase of your SonoSite M-Turbo, you will receive four consecutive hours of installation provided by a SonoSite Clinical Specialist. The installation includes an overview of the product and accessories purchased, training on the features, functions, and user interface, and system care/maintenance. Available for US locations only. Additional days system installation can be purchased separately as needed.

**2 P07272 - M-Turbo Color Option - Glacier Sky
Glacier Sky, Blue****3 P12813 - Color Application Software Package M-Turbo**

This package provides the following capabilities for the transducers that support these features:

- Tissue Harmonic Imaging (THI), a capability in which the system transmits at one frequency and receives at a higher harmonic frequency to reduce noise and clutter and improve resolution.
- SonoHD Imaging Technology, technology which significantly reduces speckle noise while enhancing tissue margins, thereby dramatically improving contrast and structural resolution.
- Velocity color flow imaging provides the clinician with the color sensitivity to perform color Doppler examinations with all transducers during a clinical procedure.
- PW Doppler is available on all transducers.
- CW Doppler is a quantitative assessment of blood flow with Duplex imaging for higher flow velocities.

| | | |
|----|--|---|
| 4 | P12819 - DICOM Bundle (Print/Store/Worklist Mpps Sc) M-Turbo The DICOM complete package includes the capability to interface with your PACS network with the complete offering of DICOM Print, Store, Worklist, storage commit, and modality perform procedure step. | 1 |
| 5 | P13930 - SonoMBe, M-Turbo Proprietary software that enhances the systems ability to aid needle visualization. | 1 |
| 6 | P07682 - HFL38X / 13-6 MHZ Transducer Biopsy Compatible HFL38x / 13-6 MHz multi-frequency, broadband, 38 mm linear array transducer for small parts, breast, vascular, nerve, IMT, musculoskeletal, and venous. Supports 2D with SonoMB Multi Beam Technology and Auto Gain capabilities, SonoHD Imaging Technology, M-mode, Color Power Doppler, Velocity Color Flow Doppler and Pulsed Wave Doppler. Biopsy guide available. 1-meter drop-test durability. Maximum depth is 6 cm. | 1 |
| 7 | P07699 - SLAx / 13-6 MHZ Transducer SLAx / 13-6 MHz transducer is a 26-mm broadband linear array for vascular, venous, nerve, superficial and musculoskeletal exams. Supports 2D, M-Mode, SonoRES, Color Flow Doppler, and Pulsed Wave Doppler. Maximum depth is 6.0 cm. STERIS(R) SYSTEM 1 Compatible. | 1 |
| 8 | L12163 - H-Universal Stand (M-Turbo Only) Ergonomic stand and mobile work platform for the M-Turbo system and transducers. Complete with power supply and DVI mini-dock. Requires isolation transformer kit (P12882) when more than one OEM peripherals are ordered and installed on the H-Stand. OEM peripherals include: B/W or color printer, DVD and LCD display. Isolation transformer mounts under the stand base. | 1 |
| 9 | P06293 - Sony Up 897 Md Black & White Video Printer Medical grade, monochrome video printer with interface cables. Worldwide power (100V-240V, 50/60Hz) and video (NTSC/PAL). North American power cord supplied by manufacturer. | 1 |
| 10 | P07662 - User Guide M-Turbo M-Turbo Ultrasound System User Guide, English | 1 |
| 11 | P08144 - Service Manual M-Turbo M-Turbo Ultrasound Service Manual. | 1 |
| 12 | P08144 - Service Manual M-Turbo M-Turbo Ultrasound Service Manual. | 1 |
| 13 | 5-YR-WARRANTY - 60 MONTHS - STANDARD COVERAGE WARRANTY 60 MONTHS - STANDARD COVERAGE WARRANTY | 1 |
| 14 | 1-YR-WARRANTY - 12 MONTHS - STANDARD COVERAGE WARRANTY 12 MONTHS - STANDARD COVERAGE WARRANTY (For Designated Products) | 1 |