



NOTES

1. Vendor shall remove 2 existing booths; existing booth -1 occupies the entire recessed space.
2. Dispose of in VA provided dumpster or remove from site immediately.
3. After removal, there will be approximately 60 day delay to allow VA to prepare site to receive new booths.
4. Prior to fabrication, verify all existing conditions and dimensions in the field.
5. Prior to fabrication, submit shop drawings to VA for approval.
6. VA will tie in utilities after installation of new booths
7. All demolition shall be done after 4:30 pm, and other than normal working hours as coordinate with VA.
8. Any work creating noise to install new units shall accomplished after normal working hours.
9. Provide matching trim pieces to fit between booth and walls to provide smooth look as required.

HERSHEL WOODY WILLIAMS VA MEDICAL CENTER  
HUNTINGTON, WEST VIRGINIA