



SITE PLAN DEMOLITION AND NEW WORK
SCALE: 1"=50'-0"

1" = 50'
GRAPHIC SCALE

TECHNICON
ENGINEERS/ARCHITECTS
MACON & ATLANTA

- DEMOLITION NOTES:**
(THIS SHEET ONLY)
- CONTRACTOR SHALL REMOVE ALL GRADE LEVEL AND ABOVE GRADE LEVEL ITEMS ASSOCIATED WITH THE ABANDONED SYSTEM. REFER TO GENERAL NOTE 14 ON DRAWING SHEET X1.
 - CONTRACTOR SHALL SEAL ENDS OF PIPING/INVERTS AND ABANDON IN PLACE. REFER TO GENERAL NOTE 14 ON DRAWING SHEET X1 AND SPECIFICATION SECTION 33300 SANITARY SEWER, UTILITIES.
 - EXISTING TO BE ABANDONED IN PLACE.
- NEW WORK NOTES:**
(THIS SHEET ONLY)
- CONTRACTOR SHALL REABRIVATE EXISTING PIPE BY SLIP LINING METHOD BETWEEN MANHOLES. REFER TO SPECIFICATIONS SECTION 333020 SEWER MAIN AND LATERAL REABRICATION BY LINING.
 - CONTRACTOR SHALL INSTALL NEW SANITARY SEWER SYSTEM PIPING BY TRENCH METHOD AND EXCAVATION. REFER TO SPECIFICATIONS SECTION 33300 SANITARY SEWER, UTILITIES AND SPECIFICATION SECTIONS 33300 SANITARY SEWERAGE UTILITIES AND 312011 EARTH WORK.
 - CONTRACTOR SHALL INSTALL NEW MANHOLE, FRAME AND COVER AT THIS APPROXIMATE LOCATION. REFER TO DETAILS 2, 4 AND 6, ON SHEET X2 AND PROFILES ON SHEET X3.
 - CONTRACTOR SHALL CONNECT TO EXISTING SANITARY SEWER PIPING AT THIS APPROXIMATE LOCATION. INSTALL OUTSIDE TWO-WAY CLEAN AT AND ROUTE NEW SANITARY PIPING AS INDICATED. REFER TO DETAILS 2, 4 AND 6, ON SHEET X2 AND PROFILES ON SHEET X3.
 - CONTRACTOR SHALL SAW CUT, BREAKOUT AND REPAIR SIDEWALKS AND STREET PAVING AS REQUIRED. COORDINATE ALL PAVING CUTS WITH COTR. FLOWABLE FILL SHALL BE USED AS FILL AT STREET AND PARKING LOT CROSSINGS. REFER TO GENERAL NOTES ON SHEET X1, DETAILS 7, 8 AND 9 ON SHEET X2 AND SPECIFICATION SECTION 320523 CEMENT AND CONCRETE FOR EXTERIOR IMPROVEMENT, 312323.33 FLOWING FILL, 321218 ASPHALT PAVING, 321723 PAVEMENT MARKINGS AND 033000 CAST IN PLACE CONCRETE.
 - CONTRACTOR SHALL CONNECT TO EXISTING MANHOLE AT THIS LOCATION. GROUT INVERT AS REQUIRED.
 - CONTRACTOR SHALL INSTALL PASS THRU PIPING IN EXISTING MANHOLE TO BE ABANDONED. SEAL INVERTS TO BE ABANDONED AND OTHER OPENINGS TO PREVENT GROUND WATER INFILTRATION. REFER TO DETAIL 10 ON SHEET X2.
 - EXISTING PIPE AND ASSOCIATED CONNECTIONS, CLEAN OUTS, ETC. SHALL BE CLEANED AND REMAIN IN SERVICE.
 - CONTRACTOR SHALL REABRIVATE EXISTING MANHOLE. REFER TO SPECIFICATIONS SECTION 333010 SEWER MANHOLE REABRICATION.
 - CONTRACTOR SHALL REMOVE AND REINSTALL LAMP POST AND ALL OTHER FEATURES AS REQUIRED TO INSTALL SANITARY SEWER PIPING, MANHOLES, ETC..
 - TERMINATION OF NEW WORK.
 - CONTRACTOR SHALL SEAL END OF ABANDONED PIPING INVERT.
 - CONTRACTOR SHALL INSTALL PASS THRU PIPING IN EXISTING MANHOLE TO BE ABANDONED. SEAL INVERTS TO BE ABANDONED. REFER TO DETAIL 11 ON SHEET X2.
 - CHAIN LINK FENCE AROUND CHILLER COMPOUND MAY INTERFERE WITH ROUTING OF NEW PIPING. IF APPLICABLE, CONTRACTOR SHALL CONNECT TO EXISTING PIPING OUTSIDE OF FENCED AREA. EXISTING CLEANOUT IS TO BE REMOVED BELOW GRADE. REFER TO GENERAL NOTE 14 ON SHEET X1.
 - CLOSURE OF STREET OR DRIVE IS NOT PERMITTED. REFER TO GENERAL NOTE 2 ON SHEET X1.

Revisions	Date
1. REPLACE BUILDING SERVICE TO BUILDING 26	11 MAY 09

APPLIED ENGINEERING SOLUTIONS, INC.
440 Martin Luther King, Jr. Blvd, Suite 101A
Macon, Georgia 31201
(478) 314-1270
www.aes-pe.com

Drawing Title	Project Title	Date
SITE PLAN DEMOLITION AND NEW WORK	REPLACE SANITARY SEWER LINES PHASE IV	JULY 8, 2008
Approved Project Director	Building Number N/A	Project No. 557-08-101
Checked BP	Drawn PW	Drawing No. L1
CONSTRUCTION DOCUMENTS	Location CARL VINSON VA MEDICAL CENTER DUBLIN, GEORGIA	Drawn by + or +

Veterans Administration