

SECTION 01 58 16
TEMPORARY INTERIOR SIGNAGE

PART 1 GENERAL

DESCRIPTION

This section specifies temporary interior signs, including directional signage, job identification signage with project title and contractor name, precautionary signage (danger/risk/slip/trip/etc.) signage.

PART 2 PRODUCTS

2.1 TEMPORARY SIGNS

- A. Temporary interior signs as identified above are required in this project.
- B. For bid purposes include 24 square feet of signs, 5mm foam core with paper face lettering, a minimum of 2.5 inches tall. All lettering will be machine printed.
- C. Coordinate with COR for quantity, wording and location of signs.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Develop a temporary signage plan and submit/present it to the COR for comments and approval. Install temporary signs per the approved plan.

3.2 LOCATION

- A. Install where directed by COR.
- B. Replace missing, damaged, or illegible signs.

- - - E N D - - -