



**BLDG 3  
GROUND FLOOR PLAN**  
SCALE: 1/8" = 1'-0"  
NORTH

**CODED NOTES**

- ① INSTALL NEW LITHONIA LED EXIT SIGN ABOVE DOOR "EXR LED EL M6" OR EQUAL.
- ② WIRE BRUSH / CLEAN SURFACES TO EXIST. METAL HANDRAILS, STEPS & SUPPORTS. APPLY 2 COATS MIN. SHERWIN WILLIAMS B54-B2-11 INDUSTRIAL ENAMEL PAINT. HANDRAIL & SUPPORTS SHALL BE BLACK & STEPS SHALL BE SAFETY YELLOW.
- ③ SCRAPE & CLEAN EXIST. PAINTED CONCRETE FLOOR SURFACES. REMOVE ALL FLAKED/CHIPPED PAINT AS REQUIRED. APPLY 2 COATS MIN. SHERWIN WILLIAMS PORCH & FLOOR ENAMEL PAINT. COLOR SHALL BE SOFTWARE GRAY SW7074 TRAFFIC PATHWAY STRIPES SHALL BE SAFETY YELLOW.
- ④ CLEAN ALL EXIST. METAL WRAPPED STEAM PIPES THIS AREA. REMOVE DAMAGED STEAM PIPE INSULATION WRAPPING WHERE IT EXISTS & RE-WRAP WITH NEW INSULATION AND SHEET METAL COVERING. INSTALL SHEET METAL COVERINGS TO ALL STEAM PIPES NOT CURRENTLY WRAPPED WITH SHEET METAL. INSTALL NEW IDENTIFICATION STICKERS ON EVERY PIPING SYSTEM AND PROVIDE DIRECTION OF FLOW & SOURCE. GAS PIPES SHALL BE PAINTED YELLOW PER CODE REQUIREMENTS, EXHAUST PIPES PAINT SILVER AND IDENTIFY CONDENSATE PIPES BOILER FEED PIPES PER COLOR CODE REQUIREMENTS.
- ⑤ SCRAPE & CLEAN ALL EXIST. STRUCTURAL STEEL MEMBERS, WALLS AND CEILING SURFACES. APPLY 2 COATS MIN. SHERWIN WILLIAMS ENAMEL PAINT. COLOR HINTING BLUE SW6519.
- ⑥ AREA OVER TOILET & OFFICE SPACE SCRAPE & CLEAN ALL EXIST. STRUCTURAL STEEL MEMBERS, WALLS AND CEILING SURFACES. APPLY 2 COATS MIN. SHERWIN WILLIAMS ENAMEL PAINT. COLOR HINTING BLUE SW6519.
- ⑦ WIRE BRUSH / CLEAN METAL TRAYS & PIPING. APPLY 2 COATS MIN. SHERWIN WILLIAMS B54-B2-11 INDUSTRIAL ENAMEL PAINT. COLOR HINTING BLUE SW6519.
- ⑧ REMOVE ALL CEILING MOUNTED DOME LIGHTS, MOUNTING BRACKETS, HANGER, CONDUITS & ASSOCIATED HARDWARE. CONDUITS & WIRING SHALL BE TERMINATED AT THE JUNCTION BOX. APPLY 2 COATS MIN. SHERWIN WILLIAMS B54-B2-11 INDUSTRIAL ENAMEL PAINT. COLOR HINTING BLUE SW6519.
- ⑨ REMOVE CEILING MOUNTED HEAT UNIT, MOUNTING BRACKETS, HANGER, CONDUITS & ASSOCIATED HARDWARE. THE EXTERIOR MOUNTED DOME HOUSING ON THE ROOF SIDE SHALL REMAIN AND BE CONVERTED INTO AN EXHAUST FAN BY CONTRACTOR. INSTALL NEW VARIABLE SPEED FAN MOTOR, VARIABLE CONTROL SWITCH & WIRING AT EXISTING LOCATION OF FORMER UNIT CONTROLS. USE OF EXISTING CONDUITS IS ALLOWED. REMOVE HEAT UNIT HEAT PIPING FROM MAIN LINE TO HEAT UNIT ENTIRELY. CLEAN CEILING AND APPLY 2 COATS MIN. SHERWIN WILLIAMS B54-B2-11 INDUSTRIAL ENAMEL PAINT. COLOR HINTING BLUE SW6519.
- ⑩ REMOVE CEILING EXHAUST LOUVER & FAN UNIT. INSTALL NEW GREENHECK NYD-180-A5 EXHAUST FAN UNIT IN EXISTING OPENING. UNIT SHALL HAVE A NEW VARIABLE SPEED FAN MOTOR. INSTALL NEW VARIABLE CONTROL SWITCH & WIRING AT EXISTING LOCATION OF FORMER FAN CONTROLS. USE OF EXIST. CONDUITS IS ALLOWED.
- ⑪ REPAIR FLOOR DRAIN. PATCH CRACKED CONCRETE AREAS WITH GROUT TOP & BOTTOM SURFACES AND REPAINT PER NOTES 3 AND 5.
- ⑫ INSTALL NEW DEAD BOLT KEY LOCK & REMOVABLE CORE CYLINDER (BEST LOCK) TO MATCH VA LOCKS N EXISTING DOOR FRAME.

**UNITED STATES DEPARTMENT OF VETERANS AFFAIRS**  
VA MEDICAL CENTER - 1540 SPRING VALLEY DRIVE - HUNTINGTON WV 25704

DRAWING TITLE: <b>RENOVATION WORK GROUND FLOOR &amp; CEILING</b>		PROJECT TITLE: <b>REPLACE LIGHTS &amp; PAINT BOILER PLANT</b>	
APPROVED: CHRIS ECKLES ASS'T CHIEF, ENGINEERING	BUILDING: <b>3</b>	PROJECT NUMBER: <b>12-110</b>	DRAWING NUMBER: <b>A2</b>
APPROVED: JOHN KLIM CHIEF, ENGINEERING	DRAWN: STEVE ELROD	DATE: <b>OCT '12</b>	DWG.