

PURCHASE ORDER: 658-B90011

REQUESTING SERVICE: SURGERY

SHIP TO: 143-RECEIVING

V.A. Medical Center  
VA MEDICAL CENTER  
1970 ROANOKE BLVD  
SALEM, VA 24153

<b>Qty</b>	<b>Product Description</b>
1	OEC Elite™ CFD 31 cm Digital Mobile Ergo C-arm Basic Vascular (Basic Vascular Platform with up to 8 fps Cine)
1	Service, Training, 1 Week Excludes Accommodation, Technical Training, Elite
1	Sony UP-971AD Hybrid Graphic Printer
1	NuBoom ULTRA M2 High Definition All in One Equipment Management and Visualization System
1	NuBoom Substitute (2) 24" Monitors for (2) 26" High Bright Monitors
1	Spring Arm and Single-Color Size-3 LED Surgical Light for NuBoom S7001TA
1	IDI, 100UC Plus, A100-1517, Urology And Multipurpose Mobile Imaging Table With Motorized Elevation, Trendelenburg Tilt, Longitudinal And Transverse Tabletop Motion
1	IDI, Heavy Duty Boot-Style Stirrups, Pneumatic Assist, Pair, Includes 2 Side Rail Clamps C000-0656, # A 100-2247
1	IDI, Physician Elbow Supports, Pair, With Pads, # C000-0594
2	IDI, Side-Rail Clamp, Rotating, For Leg Holders C000-

---

<i>Part Number</i>	<i>Qty</i>	<i>Product Description</i>
		0745, # C000-0746

---

<b>Qty</b>	<b>Description</b>
1	<p data-bbox="443 934 1073 1035"><b>OEC Elite™ CFD 31 cm Digital Mobile Ergo C-arm Basic Vascular (Basic Vascular Platform with up to 8 fps Cine)</b></p> <p data-bbox="443 1041 1073 1283">OEC ELITE CFD: Basic Vascular Software Includes: Additional imaging profiles: Vascular; real-time digital subtraction (DSA); reference image hold; peak opacification; roadmapping; re-registration; variable landmarking; mask save/recall; 8 fps cine with recording/playback rates of 4 and 8 fps; and frame-by-frame review</p> <p data-bbox="443 1325 1073 1497">31 cm CMOS Flat Panel Detector (CFD): High image quality at low dose with a CMOS crystalline structure flat panel detector; tri-mode imaging capabilities at 31 cm, 21 cm, and 15 cm; easily removable grid; and integrated laser aimer</p> <p data-bbox="443 1539 1073 1885">Ergo C-arm: Ergonomic design to ease physical demands of positioning a C-arm: low-profile X-ray tube for large field of view; radial dial color coded brakes; full length handles along C-arm; manual adjustment of lateral rotation, cephalad/ caudal tilt, wig-wag, and horizontal motion; 152° orbital rotation (55° overscan and 97° underscan); SmartView 180°/180° flip-flop; lateral height: 39.0" (99 cm); 22,500 HU/min housing cooling rate; cable pushers; low resistance wheels; and motorized vertical lift</p> <p data-bbox="443 1927 1073 1957">OEC ELITE CFD STANDARD PACKAGE INCLUDES:</p>

<i>Part Number</i>	<i>Qty</i>	<i>Description</i>	<i>List Price</i>	<i>Net Price</i>
		<p>Imaging: Live Zoom up to 4x with no change in technique; Digital Pen; squircle image retains 100% shape when rotated; image annotation; measurement tools; SmartMetal; AutoTrak Automatic Brightness Stabilization (ABS); General-Purpose Dynamic Range Management (GDRM); Minimal Difference Spatiotemporal noise filter (MDST); noise filter with on-screen indicator; automatic and manual digital brightness and contrast control; negate mode; save/auto-save feature; swap/auto-swap feature; last image hold; 40,000 image storage; preset imaging profiles: General, General HD, Orthopedic, Spine and 9900; and multi-functional footswitch and handheld controls</p> <p>Image Viewing: Incredible detail displayed with 32" (81 cm) 4K UHD color display with anti-glare and touchscreen capabilities; Viewing versatility with articulating monitor display for optimal viewing with travel of 45" (114 cm) horizontal, 17" (43 cm) vertical, 27" (67 cm) forward, and 5° up/ 5° down tilt</p> <p>Workstation with Intuitive User Interface: SmartConnect start up; flat work surfaces and storage bins; ergonomically designed handles and low friction wheels; simple touchscreen operations; physical and virtual keyboard with image control keypad; multi-purpose image directory; integrated DICOM interface; radiation dose structured report (RDSR) and X-ray dose summary; room-in-use indicator interface; examination list and customized patient information</p> <p>Dose Management: Selectable modes can be used individually or in combination and include continuous fluoroscopy, pulse, low dose, HLF, and digital spot; on-screen PreView Collimator; and Smart Window</p> <p>X-ray Generator and Power Management: 15 kW power from standard wall outlet; patented generator battery buffer design; power monitoring with on-screen display; controlled shutdown process; accidental power loss protection with a 20 second battery back-up power to workstation and C-arm</p> <p>Connectivity: Multiple ports including: ethernet, room interface, video output, video input, USB</p> <p>Security: Password protection, blank screen</p>		

<i>Part Number</i>	<i>Qty</i>	<i>Description</i>	<i>List Price</i>	<i>Net Price</i>
		function, delete all patient information		
		Warranty: One-year warranty		
		OEC Clinical Excellence: Up to 2 days of in-service training by our ARRT certified Clinical Imaging Specialists (CIS) during warranty period; entails up to 8 hours of training per day on system function/operation, provided from 7am to 5pm, Monday through Friday, excluding holidays; post-training skills assessment; radiographers may be eligible for Continuing Education credits approved by the American Society of Radiologic Technologists (ASRT); includes all CIS travel expenses; additional on-line training materials will be provided for future reference		
	1	<b>Service, Training, 1 Week Excludes Accommodation, Technical Training, Elite</b>		
		Service, Training, 1 Week Excludes Accommodation, Technical Training, Elite		
	1	<b>Sony UP-971AD Hybrid Graphic Printer</b>		
		Sony UP-971AD, Sony Hybrid Graphic Printer		
	1	<b>NuBoom ULTRA M2 High Definition All in One Equipment Management and Visualization System</b>		
		Includes:		
		- Two (2) Overhead 24" HD Monitors		
		- 2 Single segment boom arms		
		- 7" Touch Screen Master Control		
		- DOCS Software		
		- Split-Screen compatibility on all monitors		
		- Universal Output		
		- 3 external shelves, movable, left or right side		
		- Pre-wired cabinet with 20 outlets		
		- Shelf mounted hanger		
		- Utility basket		
		- E-Cylinder basket		
		- Weekday Installation		
		10 Inputs:		
		- 2 'S' Video		
		- SOG Left and Right		
		- 1 HDSDI 1080i		
		- 1DVI-D 1080P		
		- 3 VGA/RGB		
		- 1 Composite		
		Installation Includes:		
		- Weekday - Dates to be inclusive of Monday –		

<i>Part Number</i>	<i>Qty</i>	<i>Description</i>	<i>List Price</i>	<i>Net Price</i>
		<p>Thursday; Includes In-Service.</p> <ul style="list-style-type: none"> <li>- Price estimate based on facility being located within 100-mile radius of top 50 airports and is subject to change based on additional accessories purchased and determinations from pre-installation consultation.</li> <li>- 2 Days In-Service.</li> </ul> <p>WARRANTY:</p> <ul style="list-style-type: none"> <li>- CompView Medical warrants the functionality of our products (NuBOOM and DOCS) for a duration of one year. Start date of warranty is the date of product installation or 60 days after shipment, whichever is earlier.</li> </ul>		
	1	<p><b>NuBoom Substitute (2) 24" Monitors for (2) 26" High Bright Monitors</b></p> <p>Substitute (2) 24" Monitors For (2) 26" HB Monitors, ACC-10029-00</p>		
	1	<p><b>Spring Arm and Single-Color Size-3 LED Surgical Light for NuBoom S7001TA</b></p> <p>Single Color or Light, Quantity 1, Size 3, LDM-20025-00</p>		
	1	<p><b>IDI, 100UC Plus, A100-1517, Urology And Multipurpose Mobile Imaging Table With Motorized Elevation, Trendelenburg Tilt, Longitudinal And Transverse Tabletop Motion</b></p> <p>Multi-Purpose Mobile Urological Imaging Table with motorized Elevation, Trendelenburg Tilt Longitudinal and Transverse Tabletop Motions</p> <ul style="list-style-type: none"> <li>- Carbon fiber tabletop with low x-ray attenuation</li> <li>- 2" (5cm thick tabletop &amp; tabletop extension pads with memory foam construction and waterproof cover</li> <li>- Tabletop dimensions: 28"W x 46"L ( 71 x 117 cm)</li> <li>- Radiolucent tabletop extension: 24"W x 34"L (61 x 86 cm)</li> <li>- Imaging area, main tabletop: 25"W x 20"L (63.5 x 50.8 cm)</li> <li>- Imaging area, tabletop extension: 24"W x 34"L (61 x 86 cm)</li> <li>- Motorized Tabletop motions with hand control and foot control: <ul style="list-style-type: none"> <li>- Elevation 31.3" – 41.1" (79.4 – 104.4 cm)</li> <li>- Trendelenburg Tilt ± 15°</li> <li>- Longitudinal tabletop travel = 10" (25.4cm)</li> <li>- Transverse tabletop travel = ± 3.5 (±8.9 cm, 17.8cm total)</li> </ul> </li> </ul>		

<i>Part Number</i>	<i>Qty</i>	<i>Description</i>	<i>List Price</i>	<i>Net Price</i>
		<ul style="list-style-type: none"> <li>- Built-in footswitch storage tray</li> <li>- Removable radiographic cassette tray, loads from either side of table</li> <li>- Standard US side-rails for accessory attachments on main tabletop</li> <li>- Patient weight capacity: <ul style="list-style-type: none"> <li>- With patient upper body on main tabletop: 525 lbs.(238 kg)</li> <li>- With patient upper body on extension: 400 lbs. (181 kg)</li> <li>- Load capacity on extension only: 250 lbs. (113.4 kg)</li> </ul> </li> <li>- Table weight: 575 lbs. (261 kg)</li> <li>- Locking swivel casters, 5" (12.7 cm), for easy transport</li> <li>- Electrical power required: 110 VAC, 60 Hz, or 230 VAC 50/60 Hz operation (must specify with order). 10 amp max. required at 110V.</li> <li>- Battery back-up operation</li> </ul> <p>Accessories included:</p> <ul style="list-style-type: none"> <li>- Tabletop Pad, 2" thick, waterproof</li> <li>- Tabletop Extension, with pad</li> <li>- Hand control pendant</li> <li>- Footswitch control</li> <li>- Drain Bag Support Hoop</li> <li>- Disposable drain bag and hose assembly, box of 20</li> <li>- Removable Radiation Shield Flap for perineal end of table</li> <li>- Patient Restraint Straps (2)</li> <li>- Armboard (1), rail mounted, with pad and strap</li> <li>- Disposable covers for footswitch, box of 50</li> </ul> <p>WARRANTY:</p> <ul style="list-style-type: none"> <li>- Image Diagnostics Inc. (IDI) products are warranted to be free from failures due to defects in materials or Workmanship for a period of 3 years for parts and 1 year for labor.</li> <li>- During this period any warranty claims should be addressed directly with the manufacturer:  Image Diagnostics, Inc.  310 Authority Drive  Fitchburg, MA 01420  ( 978 ) 829-0009, Fax ( 978 ) 829-0027</li> </ul>		
	1	<b>IDI, Heavy Duty Boot-Style Stirrups, Pneumatic Assist, Pair, Includes 2 Side Rail Clamps C000-0656, # A 100-2247</b>		

---

<b>Qty</b>	<b>Description</b>
	IDI, Heavy Duty Boot-Style Stirrups, Pneumatic Assist, Pair, Includes 2 Side Rail Clamps C000-0656, # A 100-2247
1	<b>IDI, Physician Elbow Supports, Pair, With Pads, # C000-0594</b>
	IDI, Physician Elbow Supports, Pair, With Pads, # C000-0594
2	<b>IDI, Side-Rail Clamp, Rotating, For Leg Holders C000-0745, # C000-0746</b>
	IDI, Side-Rail Clamp, Rotating, For Leg Holders C000-0745, # C000-0746

---