

Attachment B, Finishes List

LOCATION	Floor	Wall	Base	Other
Lobby/Reception	Luxury Vinyl Plank Flooring Mannington Natures Path 3 x 36or 48 Color TBD	Sherwin Williams zero VOC Color: TBD	Vinyl Base: Johnsonite 6" Color Beige	Reception station to be Modular Systems Furniture Feature wall with accent lighting
PACT Clinic Exam Room	Luxury Vinyl Plank Flooring Mannington Natures Path 3 x 36or 48 Color TBD	Sherwin Williams zero VOC Color: TBD Color: TBD 2 paint colors in room	Vinyl Base: Johnsonite 6" Color Beige	Casework to be Herman Miller Compass Modular Clinical Furniture Apx 6' wide with sink unit See Technical Specs
Mental Health Consult Rooms	Luxury Vinyl Plank Flooring Mannington Natures Path 3 x 36or 48 Color TBD	Sherwin Williams zero VOC Color: TBD Color: TBD 2 paint colors in room	Vinyl Base: Johnsonite 6" Color Beige	Dimmer switch for lighting
Team Work Areas (PACT Team workrooms)	Luxury Vinyl Plank Flooring Mannington Natures Path 3 x 36or 48 Color TBD	Sherwin Williams zero VOC Color: TBD Color: TBD 2 paint colors in room	Vinyl Base: Johnsonite 6" Color Beige	
Pathology and Lab	Armstrong Sheet Vinyl Rejuvenations Pattern and Color : TBD Heat Weld	Sherwin Williams zero VOC Color: TBD Color: TBD 2 paint colors in room	Rolled cove base 6"	Modular Clinical Lab Furniture Unicell or Herman Miller Co Struc
Toilet Rooms	Dal Tile Porcelain Tile Fabrique 12x24 Color Gris Linen	Dal Tile Fabrique Cream Linen 12x24 With 6" 2x2 Accent Gris Linen	Rolled cove base 6"	Sherwin Williams zero VOC Color: TBD Corian Counter tops
Storage Rooms	Armstrong Sheet Vinyl Rejuvenations Pattern and Color : TBD Heat Weld	Sherwin Williams zero VOC Color: TBD Color: TBD 2 paint colors in room	Rolled cove base 6"	
Staff Lounge	Luxury Vinyl Plank Flooring Mannington Natures Path 3 x 36or 48 Color TBD	Sherwin Williams zero VOC Color: TBD Color: TBD 2 paint colors in room	Vinyl Base: Johnsonite 6" Color Beige	Millwork with Corian top
Communications Room	Armstrong Rejuvenations Pattern and Color : TBD Heat Weld	Sherwin Williams zero VOC Color: TBD	Vinyl Base: Johnsonite 6" Color Beige	
Soiled Utility Room	Armstrong Rejuvenations Pattern and Color : TBD Heat Weld	Sherwin Williams zero VOC Color: TBD	Rolled cove base 6"	
Hallways	Luxury Vinyl Plank Flooring Mannington Natures Path 3 x 36or 48 Color TBD	Sherwin Williams zero VOC Color: TBD Color: TBD 2 paint colors in room	Vinyl Base: Johnsonite 6" Color Beige	Wall protection and handrails as needed Accent wall with Vinyl Type 2 wallcovering Pattern and Color TBD

LOCATION	Floor	Wall	Base	Other
Lighting				Recessed, indirect LED, lens-less, size 2x2 Recommend Lithonia Breez Series Part # 2BZL2 30L EZ1 LP840 N100 USPOM
				Exit Lights: Lithonia LED w/battery backup Part # LQMSW3R 120/277VAC ELN
Ceiling				Color White with White Grid 2x2 Flush Armstrong #824
		Sound masking required throughout the space		
Handrails				Acrovyn HR-6CN #372, Classic Maple Stainless steel brackets
Wall Protection				Wall: Acrovyn Wall Covering Crash Rails: Acrovyn SCR-40N, 4", surface mount Corner Guards: Acrovyn SM-20N, 3" Color for all: 997 Irish Cream