

PLUMBING FIXTURE SCHEDULE										
REFER TO SPECIFICATION SECTION 22 40 00 "PLUMBING FIXTURES" FOR FURTHER REQUIREMENTS										
		① WALL MOUNTED	④ SEMI-RECESSED	⑦ STAINLESS STEEL	⑩ PRE CAST TERRAZZO	⑬ CAST IRON	⑮ AS PER MFR. STANDARD			
		② FLOOR MOUNTED	⑤ COUNTERTOP	⑧ STEEL	⑪ MOLDED STONE	⑭ WHITE	⑯ AS INDICATED			
		③ FULLY RECESSED	⑥ VITREOUS CHINA	⑨ FIBERGLASS	⑫ BRASS	⑬ CHROME PLATED	⑰ PROVIDE PER SPECIFICATIONS			
TAG	DESCRIPTION	PIPE CONNECTIONS				MOUNTING MATERIAL	COLOR	CARRIER	REMARKS	
		SAN	VENT	DCW	DHW					
P-102	WATER CLOSET	4"	2"	1½"	-	2	6	14	SIPHON JET, WALL OUTLET, FLOOR MOUNTED, REAR DISCHARGE, ELONGATED BOWL, TOP OF RIM 18" ABOVE FINISHED FLOOR, SENSOR OPERATED FLUSH VALVE, BDPBAN WASHER W/GRAB BAR OFFSET.	
P-414	LAVATORY	1½"	1½"	½"	½"	2	6	14	FRONT OVERFLOW, OVAL-SHAPED BOWL, SELF DRAINING DECK AREA, 8" CENTERS FAUCET PUNCH, 34" ABOVE FINISHED FLOOR.	
P-505	SERVICE SINK	3"	1½"	½"	½"	1	8	-	20"x25" FLUSHING RIM, WALL HUNG, STEEL. (ASME/ANSI A1112 6.1M) SET 30" ABOVE FINISHED FLOOR.	
P-528	SINK	2"	1½"	½"	½"	5	7	-	SELF RIMMING 18 GAUGE TYPE 318 STAINLESS STEEL TOP MOUNT (ASME/ANSI A112.19.3M) DRAIN PUNCHED CENTERED, 3-HOLE PUNCHED FAUCET, FULLY COATED INSULATED UNDERSIDE, 12" DEPTH, 22" FRONT TO BACK, 25" WIDE	
P-530	SINK	2"	1½"	½"	½"	5	7	-	SELF RIMMING 18 GAUGE TYPE 304 STAINLESS STEEL TOP MOUNT (ASME/ANSI A112.19.3M) DRAIN PUNCHED CENTERED, 3-HOLE PUNCHED FAUCET, FULLY COATED INSULATED UNDERSIDE, 10-12" DEPTH, 19" FRONT TO BACK, 21" WIDE	
P-604	DRINKING FOUNTAIN	1½"	1½"	½"	-	1	8	-	ELECTRIC WATER COOLER, MECHANICALLY COOLED, WALL HUNG, SELF-CONTAINED, WHEEL CHAIR ACCESSIBLE, BUBBLER STYLE, 5mL/sec (5gpm), LEAD FREE, 19"x19", SET 38" ABOVE FINISHED FLOOR.	
P-602	HOSE BIB	-	-	½"	-	1	-	-	COMBINATION FAUCET, WALL MOUNTED, W/ VACUUM BREAKER	

MEDICAL GAS CONNECTION SCHEDULE						
TAG	DESCRIPTION	PIPING CONNECTIONS			ELEC	REMARKS
		OXYGEN	MED. AIR	VACUUM		
AP1	MAIN MEDICAL GAS ALARM PANEL	½"	½"	¾"	120/160 (EMERGENCY POWER)	FULLY ELECTRONIC MONITORING SYSTEM.
AP2 AP3 & AP4	MEDICAL GAS ALARM PANEL	-	-	-	120/160 (EMERGENCY POWER)	ACCOMMODATES FOUR ALARM MODULES.
VC1 VC2 & VC3	MEDICAL GAS VALVE CABINET	¾"	¾"	1½"	-	FULL PORT, DOUBLE SEAL, BALL TYPE SHUT-OFF VALVES AND 18 GAUGE STEEL W/WHITE EPOXY FINISH VALVE BOX ASSEMBLY.
GO1 & GO2	GAS OUTLET (GEOMETRIC QUICK-CONNECT KEY STYLE)	½"	½"	¾"	-	OXYGEN, VACUUM OUTLETS AND (1)SLIDE ASSEMBLY.
GO3	GAS OUTLET (GEOMETRIC QUICK-CONNECT KEY STYLE)	½"	-	-	-	OXYGEN OUTLET, COMPLETE WITH SECURITY COVER.
PS1	PRESSURE SWITCH	¾"	¾"	-	-	UL LISTED, SINGLE POLE, DOUBLE THROW, SNAP ACTION MICROSWITCH.
VS1	VACUUM SWITCH	-	-	¾"	-	UL LISTED, SINGLE POLE, DOUBLE THROW SWITCHING ELEMENTS.

[illegible]

CLEANOUT SCHEDULE		
REFER TO SPECIFICATION SECTION 22 13 00 "FACILITY SANITARY SEWERAGE" FOR FURTHER REQUIREMENTS		
ITEM	DESCRIPTION	ACCESSORIES
CO1	CLEANOUT TILE	ADJUSTABLE CAST IRON WITH THREADED BRONZE PLUG, NICKEL-BRONZE VANDAL-RESISTANT ROUND SCORIATED COVER, LINE SIZE
WCO	CLEANOUT WALL	COUNTERSUNK BRONZE PLUG AND VANDAL-RESISTANT POLISHED CHROME COVER

DRAIN SCHEDULE		
REFER TO SPECIFICATION SECTION 23 13 00 "FACILITY SANITARY SEWERAGE" FOR FURTHER REQUIREMENTS		
ITEM	DESCRIPTION	ACCESSORIES
FD1	FLOOR DRAIN CARPET OR BARE CONCRETE	CAST IRON BODY W/CLAMPING COLLAR, SEEPAGE OPENING 6" DIA. SATIN FINISH BRONZE STRAINER, 3" BOTTOM OUTLET, 1/2" TRAP PRIMER CONNECTION, VANDAL-RESISTANT SCREWS
	FLOOR DRAIN CERAMIC OR QUARRY TILE	CAST IRON BODY W/CLAMPING COLLAR, SEEPAGE OPENING 6" SQ. SATIN FINISH BRONZE STRAINER W/TILE FLANGE, 3" BOTTOM OUTLET, 1/2" TRAP PRIMER CONNECTION, VANDAL-RESISTANT SCREWS
FD2	FLOOR DRAIN	TWO-PIECE CAST IRON BODY W/CLAMPING COLLAR, SEE PAGE OPENINGS, 8-12" DIA SATIN NIKALOY COVER, 3" BOTTOM OUTLET, 1/2" TRAP PRIMER CONN., VANDAL-RESISTANT SCREWS

Office of
Construction
and Facilities
Management

 Department of
Veterans Affairs