



- GENERAL NOTES**
- REFER TO DRAWINGS AND SPECIFICATIONS OF OTHER CONSTRUCTION TRADES FOR ADDITIONAL ELECTRICAL WORK INCLUDED IN THE DIVISION 26 CONTRACT.
 - COORDINATE EXACT LOCATIONS OF EQUIPMENT WITH DIVISIONS 1-23 DRAWINGS. VERIFY EXACT WIRING AND CONNECTION REQUIREMENTS WITH SUBMITTAL DOCUMENTS BEFORE INSTALLATION. SPECIALTY OUTLET TYPES SHALL BE VERIFIED BEFORE ORDERING. ALL ELECTRICAL WORK SHOWN HERE MUST BE VERIFIED AND COORDINATED IN FIELD BEFORE INSTALLATION.
 - REFER TO ARCHITECTURAL ELEVATIONS FOR RECEPTACLE MOUNTING HEIGHTS. COORDINATE EXACT HEIGHTS IN FIELD.
 - ALL CONDUITS IN AREAS WITHOUT SUSPENDED CEILINGS SHALL BE RUN INCONSPICUOUSLY AS POSSIBLE. HIDDEN BEHIND BEAMS, CLOSE TO DECK, ETC. OBTAIN APPROVAL OF CONDUIT RUNS BELOW BEAMS WITH OWNERS REPRESENTATIVE.
 - REFER TO ARCHITECTURAL DOOR SCHEDULES, AND DOOR HARDWARE SPECIFICATION FOR ELECTRICAL DEVICES INSTALLED AT DOORS.
 - PROVIDE ALL FINAL POWER CONNECTIONS TO EQUIPMENT. PROVIDE ALL CONDUIT, DEVICE BOXES, AND CONTROL WIRING TO EQUIPMENT UNLESS NOTED OTHERWISE.
- CODED NOTES**
- JUNCTION BOX ABOVE CEILING FOR LIGHT BOOM WITH FLAT SCREEN. PROVIDE CRITICAL POWER CIRCUIT AND MAKE FINAL CONNECTION.
 - RECEPTACLE FOR ELECTRO-SURGICAL UNIT.
 - JUNCTION BOX ABOVE CEILING FOR ENDOSCOPY SYSTEM. PROVIDE CRITICAL POWER CIRCUIT AND MAKE FINAL CONNECTIONS.
 - RECEPTACLE FOR INFUSION PUMP. COORDINATE EXACT LOCATION.
 - RECEPTACLE FOR PHYSIOLOGICAL MONITOR. COORDINATE EXACT LOCATION IN FIELD.
 - JUNCTION BOX FOR WIRING TO MONITORING SYSTEM. EXTEND 1 1/4" CONDUIT TO CABLE TRAY SYSTEM.
 - COORDINATE EXACT LOCATION OF RECEPTACLE IN FIELD.
 - JUNCTION BOX ABOVE CEILING FOR NORMAL POWER CONNECTION TO UTILITY RAIL SYSTEM. MAKE FINAL CONNECTION.
 - JUNCTION BOX ABOVE CEILING FOR CRITICAL POWER CONNECTION TO UTILITY RAIL SYSTEM. MAKE FINAL CONNECTION.
 - PROVIDE (2) VOICE/DATA RECEPTACLES IN UTILITY RAIL SYSTEM. EXTEND 2-1" CONDUIT ABOVE CEILING.
 - COORDINATE EXACT LOCATION OF DUCT MOUNTED DETECTORS WITH MECHANICAL CONTRACTOR.
 - JUNCTION BOX ABOVE CEILING FOR POWER CONNECTION TO AUTOMATIC DOOR CONTROLLER. MAKE FINAL CONNECTION.
 - JUNCTION BOX FOR POWER CONNECTION TO WALL MOUNTED MONITOR. COORDINATE EXACT LOCATION. EXTEND 1" CONDUIT TO EXISTING CABLE TRAY SYSTEM.
 - RECEPTACLE FOR WALL MOUNTED MONITOR. COORDINATE EXACT LOCATION.
 - JUNCTION BOX ABOVE CEILING FOR POWER SUPPLY TO DOOR STRIKE. EXTEND 1/2" CONDUIT FROM ABOVE CEILING TO ELECTRIC STRIKE IN DOOR FRAME.
 - JUNCTION BOX MOUNTED IN WALL AT 48" FOR CARD READER. EXTEND 1" CONDUIT FROM ELECTRIC STRIKE TO ABOVE CEILING. EXTEND 1" CONDUIT FROM JUNCTION BOX TO ABOVE CEILING.

KEYPLAN

CONSTRUCTION DOCUMENTS

KORDA/NEMETH ENGINEERING, INC.
1650 WATERMARK DRIVE
COLUMBUS, OHIO 43215
DESIGNED BY
ERIC R. GORDON
DRAWN BY
Cory A. Cameron
CHECKED BY
R. Randy Lowe
JOB FILE 2011-0812

NO.	REVISIONS/SUBMISSIONS	DATE
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		

Consultant	KORDA KORDA/NEMETH ENGINEERING 1650 Watermark Drive, Suite 200 - Columbus, Ohio 43215-7010 614-487-1650 • FAX 614-487-8981 • WEB www.korda.com
Seal	
	FED/Matrix A Joint Venture 255 COUNTY ROAD 555 SOUTH, BARTOW, FLORIDA 33830 Telephone: (863) 665-6363 Fax: (863) 667-1773
Drawing Title	EIGHT EAST ENLARGED PLAN
Approved: Project Director	Project Director
Project Title	RENOVATE EIGHT EAST FOR ENDOSCOPY & CARDIOLOGY IC VAHCS
Location	IOWA CITY, IOWA
Date	07/27/2012
Checked	RRL
Drawn	ERC
Project Number	636A8-12-005
Building Number	1
Drawing Number	1-E3
39 of 42	

VA FORM 08-6231

