

1. All drawings are labeled with the words “Not for Construction”: This is an oversight and shall be disregarded. The documents are 100%.

2. Detail A7 on Dwg 1.AD102A indicates top of window frame at 8’-5”, with 8’-0” ceilings and no pocket detail: Please note this is on the demolition page, and most existing ceilings are at 9’-0 on south exterior wall, see response #3.

3. Detail A7 on Dwg 1.AE102A makes reference to sheet 1.ID602, but no sheet exists. Also references top of window at 8’-5” when finish schedule indicates 8’-0” ceilings: No pocket required where ceilings are lower than window. Run perimeter grid straight across opening or match existing heights where practical. Place a vertical section of AT and pin to prevent open view above ceiling. Coordinate with COR. No sheet 1.ID602 exists, disregard reference.

4. Demolition plan on 1.AD102A does not accurately reflect the existing wall locations in the Phase 2 area: Delete previous sheet 1.AD102A in entirety, replace with new sheet 1.AD102A attached.

5. Who is responsible for relocating existing furnishings: VA is responsible for moving existing modular furniture. Any items remaining will be minimal and become contractor property for disposal.

6. Provide clarification of work relating to Bid Item II Deductive Alternate regarding exam room casework. The drywall soffit is not deleted nor indicated as such. Install all cabinet support blocking behind drywall regardless of bid item. Tackable wall surface shall be deleted from Bid Item II. Delete under-cabinet task lighting from Bid Item II (since there will not be anything to attach it to).

7. Provide clarification of work relating to Bid Item II Deductive Alternate regarding VC and CC equipment items:

a. Where all VC items are indicated on plans, contractor shall receive new item at the job site, delivered by VA. It shall be uncrated and inspected by VA in the presence of contractor at the job site prior to installation in the work area. Generally, all work should be near completion at this time.

b. Clarification is provided as follows for VV, VC, and CC items.

Clarification for Sheets 1.QH102A Equipment Plan. Change Key Notes on the drawing for the following:

Change <CC01> X-Ray Illuminator to <VC01>

Change <CC02> Sphygmamometer to VC02>

Change <CC03> Otoscope/Ophthalmoscope to <VC03>

Change <CC04> Portable Exam Light to <VC04>

Change <CC05> Glove Dispenser to <VC05>

Change <CC06> Sharps Dispenser to <VC06>

Change <VC01> Exam Bed to <VV20>

Change <VC04> Refrigerator to <VV21>
Change <VC05> Centrifuge to <VV22>
Change <VC06> TV to <VV23>

Clarification for Sheets 1.QH102B Equipment Plan. Change Key Notes on the drawing for the following:

Change <CC01> X-Ray Illuminator to <VC01>
Change <CC02> Sphygmamometer to <VC02>
Change <CC03> Otoscope/Ophthalmoscope to <VC03>
Change <CC04> Portable Exam Light to <VC04>
Change <CC05> Glove Dispenser to <VC05>
Change <CC06> Sharps Dispenser to <VC06>
Change <VC01> Exam Bed to <VV20>
Change <VC04> Refrigerator to <VV21>
Change <VC05> Centrifuge to <VV22>
Change <VC06> TV to <VV23>

8. *The following specifications do not appear to be included:*

- a. 083313 Coiling Counter Doors (attached)
- B. 087113 Door Operators (attached)

9. *Provide contact information of current firm servicing the facility fire alarm system:*
Electronic Specialty Company, Dunbar WV 800-642-5500, Shane Higgins

10. *The double doors were not assigned hardware numbers, nor was it indicated in the schedule. Hardware set 4K was not included in the schedule. Double doors shall have hardware set HW-8B. Following is hardware set 4K:*

<u>Each door:</u>	<u>Non-Rated:</u>
<u>1 continuous hinge</u>	<u>Integral hinge guard channel , Adjusta screws</u>
<u>1 utility lock</u>	<u>Fo9</u>
<u>1 Armor Plae</u>	<u>J101x1.275 MM (.05 inch) thickness</u>
<u>1 edge guard (wood doors)</u>	<u>J208M/J211 (verify) cut, hardware</u>
<u>1 floor stop</u>	<u>L02121 x 3 fasteners</u>
<u>1 set self adhesive seals</u>	<u>ROY154</u>

11. *Is hardware set 2H11 to be Set 2H? Is there a hardware set for the bathroom doors 2C137 and 2C139? Yes, hardware set 2H11 shall be 2H. The hardware sets for bathrooms 2C137 and 2C139 shall be 2H.*