

KEYED NOTES :

- ① REMOVE EXISTING SPRINKLER HEAD.



LEGEND:

- SPK SPRINKLER LINE TO BE REMOVED
SPK SPRINKLER LINE
● EXPOSED PENDENT SPRINKLER HEAD.
○ UPRIGHT SPRINKLER HEAD.
◆ POINT OF DISCONNECT
● POINT OF CONNECTION

GENERAL NOTES :

- ALL PIPING SHOWN IS DIAGRAMMATIC ONLY, VERIFY EXACT LOCATION IN FIELD.
- REFER TO ARCHITECTURAL DRAWINGS FOR LATEST REFLECTED CEILING PLAN.
- FURNISH AND INSTALL ALL NECESSARY PIPING EQUIPMENT SUPPORTS AND ANY EQUIPMENT NOT SHOWN ON DRAWING NEEDED TO PROVIDE A COMPLETE AND WORKABLE SYSTEM.
- PROVIDE ACCESS TO ALL EQUIPMENT REQUIRING PERIODIC SERVICE AND MAINTENANCE.
- CONTRACTOR SHALL OBTAIN AND PAY FOR ALL PERMITS, FEES AND CHARGES IN CONNECTION WITH THIS WORK.
- ALL SPRINKLER PIPING SHALL BE IN ACCORDANCE WITH STATE AND LOCAL CODES AND NFPA-13.
- WORK SHALL BE COORDINATED WITH THE WORK OF ALL OTHER TRADES.
- PIPING SHALL RUN CONCEALED IN ALL AREAS WITH THE EXCEPTION OF MECHANICAL ROOMS OR WHERE NO CEILING EXISTS.
- INSTALL DIELECTRIC COUPLINGS BETWEEN DISSIMILAR MATERIALS.
- THIS CONTRACTOR IS RESPONSIBLE FOR ALL CUTTING AND PATCHING RELATED TO THE WORK OF THIS TRADE.
- OFFICE AREA, PATIENT ROOMS ETC. BASED ON LIGHT HAZARD OCCUPANCY, MAXIMUM COVERAGE OF 225 SQFT PER HEAD. DENSITY SHALL BE .10 GPM OVER 1500 SQFT.
- STORAGE AREAS BASED ON ORDINARY HAZARD GROUP 1 OCCUPANCY, MAXIMUM COVERAGE OF 130 SQFT PER HEAD. DENSITY SHALL BE .15 GPM OVER 1500 SQFT.
- IN AREAS WITH ACOUSTIC DROP CEILING TILES, SPRINKLER HEADS TO BE CENTERED IN CENTER OF TILE IN BOTH DIRECTIONS.
- SPRINKLERS SYSTEM MUST BE LEFT ACTIVE AND OPERATIONAL AT THE END OF EACH SHIFT. OUTAGES FOR THE RELOCATION OF SPRINKLER HEADS IS TO BE LIMITED TO A SINGLE SHIFT AND THE WORK MUST REMAIN UNDER CONSTANT SUPERVISION OF ONE OR MORE WORKERS AS A FIRE WATCH DURING SUCH OUTAGES.

1 SPRINKLER HEAD REMOVALS PLAN
FPR100 SCALE: 1/4" = 1'-0"



2 WORK KEY PLAN
FPR100 SCALE: N.T.S.



100% DESIGN SUBMISSION

		CONSULTANTS:		ARCHITECT/ENGINEERS:	Drawing Title		Project Title		Project Number		STRATTON VA MEDICAL CENTER
					FIRE PROTECTION REMOVALS PLAN		VISION CLINIC RENOVATIONS		528A8-08-830		
					Approved: Project Director		Location		Building Number		
							ALBANY, NEW YORK		1		
							Date		Drawing Number		
100% SUBMISSION	05/13/11			<div><div>SAGE ENGINEERING ASSOCIATES, LLP</div><div>1211 WESTERN AVENUE ALBANY, NY 12203</div><div>(518)453-6091 FAX(518)453-6092</div></div> <div></div> <div>SEA PROJECT NO. 2217</div>	MAY 13, 2011		Checked DPL	Drawn EJG	FPR100	 Department of Veterans Affairs	
95% SUBMISSION - REISSUED	06/04/10										
95% SUBMISSION	02/12/10										
60% SUBMISSION	07/17/09										
Revisions:	Date										