Barton & Loguidice, P.C.
Celebrating 50 years of service
Engineers • Environmental Scientists • Planners • Landscape Architects
Syracuse • Albany • Rochester • Ellenville • Newburgh • Camp Hill

December 7, 2011

Mr. Robert Seigart, AIA
Schopfer Architects
1111 James Street
Syracuse, New York 13203

Re: Department of Veterans Affairs Medical Center Bath, NY
Preliminary Pre-Renovation Asbestos Survey Report – Bldg. 34

File: 906.019.001

Dear Mr. Seigart:

This letter and attachments represent Barton & Loguidice, P.C.'s (B&L's) preliminary report for the above-referenced project. A final report will be issued after additional site inspections; this report was issued due to general project schedule requirements.

Introduction

B&L was retained to conduct a pre-renovation asbestos survey and removal design documents for the renovation project planned at Building 34 on the Veterans Medical Center in Bath, New York. The survey was conducted by David Morse and Tim Strzepek of B&L on November 30, 2011. Additional site visits are planned to finalize the survey work. Mr. Morse and Mr. Strzepek are New York State Department of Labor (DOL) certified asbestos inspectors. Copies of their NYS Department of Labor certifications and B&L's company license are provided in Appendix A.

Discussion and Results

The survey included all accessible areas of Building 34 including the basement, first, second and third floors, attic, and exterior. The cross-over corridors to other buildings were partially reviewed to facilitate installation of a new entrance. Representative suspect material sampling was conducted throughout the affected areas. Friable samples were collected in triplicate and submitted for analysis by polarized light microscopy (PLM) with dispersion staining. Friable samples were also analyzed utilizing serial analysis. Non-friable organically bound (NOB) materials were sampled in duplicate and were analyzed in accordance with New York State Department of Health (DOH) requirements. NOBs are first subjected to an ashing and acid washing procedure to properly break down the material. The sample is then analyzed by PLM

The experience to listen. The power to solve.
290 Elwood Davis Road • Box 3107 • Syracuse, New York 13220
Telephone: 315-457-5200 • Facsimile: 315-451-0052 • www.BartonandLoguidice.com

for asbestos content. If asbestos is found, the analysis is complete. However, a negative result must be confirmed by using Transmission Electron Microscopy (TEM). All samples were analyzed by AmeriSci New York, Inc. located in New York, New York.

The entire investigation included the collection of eight triplicate sets of friable material samples and eighteen NOB samples sets. Laboratory reports, sample chain-of-custody forms, and laboratory certifications are included in Appendix B. Material sample results are summarized in the table below by location.

Bldg 34 – Asbestos Sample Results

Sample Number	Material Description	Estimated Quantity	Lab Results (% Asbestos)	Condition / Friability	Material Location
CLSH-1-1,2,3	Sheetrock ceiling and associated joint compound	NA	NAD	NA	Basement
WLPL-2-1,2,3	Wall plaster divider at end of pipe tunnels entering basement	NA	NAD	NA	Basement
FIT-3-1,2,3	**Mud pipe fit insulation on fiberglass pipe insulation**	**10 EACH**	**2.0% Chrysotile**	**Fair / Friable**	**Basement**
Pl-4-1,2,3	Canvas covering on fiberglass pipe insulation	NA	NAD	NA	Basement
GROUT-5-1,2,3	Ceramic tile grout	NA	NAD	NA	Bathrooms throughout
FLVCS-6-1,2	Blue/grey pebble pattern floor sheeting	NA	NAD	NA	Throughout building
CLLI-7-1,2	2'x 2' White ceiling	NA	NAD	NA	Throughout building
BBD-8-1,2	Vinyl baseboard	NA	NAD	NA	Throughout building
BBDMAS-9-1,2	Vinyl baseboard mastic	NA	NAD	NA	Throughout building
WLPL-10-1,2,3	Wall plaster	NA	NAD	NA	Throughout building
WLSH-11-1,2,3	Wall and ceiling sheetrock and associated joint compound	NA	NAD	NA	Throughout building

Bldg 34 – Asbestos Sample Results					
Sample Number	**Material Description**	**Estimated Quantity**	**Lab Results (% Asbestos)**	**Condition / Friability**	**Material Location**
FLVCT-12-1,2	12"x 12" White streaked floor tile	NA	NAD	NA	Crossover corridors
FLMAS-13-1,2	Floor tile mastic under FLVCT-12	NA	NAD	NA	Crossover corridors
CLTL-14-1,2	1'x 1' White ceiling tiles	NA	NAD	NA	Crossover corridors
FLMAS-15-1,2	Floor sheeting mastic - tan	NA	NAD	NA	Throughout
FLVCS-16-1,2	Green floor sheeting around room perimeters	NA	NAD	NA	Throughout
FS-17-1,2	Red firestop compound	NA	NAD	NA	Throughout – above ceilings
FOIL-18-1,2	Tar foil paper in residual fiberglass attic insulation	NA	NAD	NA	Attic
TP-19-1,2	Tarpaper under roof shingles	NA	NAD	NA	Roof
FLMAS-20-1,2	Original black floor tile mastic	NA	Trace	NA	Stair tower floor
CAULK-21-1,2	Grey door caulk around stair tower entry	NA	NAD	NA	Exterior
CAULK-22-1,2	Newer white window caulk	NA	NAD	NA	Exterior
RFSH-23-1,2	Black roof shingles	NA	NAD	NA	Roof
CAULK-24-1,2	**Older, original grey door caulk**	**20 SF**	**2.0% Chrysotile**	**Fair / Non-friable**	**Exterior**
DOOR-25-1,2,3	**Interior wood doors cores**	**50 EACH**	**30.8% Chrysotile**	**Fair / Friable**	**Throughout**
WLMAS-26-1,2	Mastic under ceramic tiles	NA	NAD	NA	Bathrooms

NAD: No Asbestos Detected Trace: Less Than 1.0 % Asbestos (Non-ACM) N/A: Not Applicable

The survey identified asbestos containing fire doors, caulk, and minor pipe insulation in the basement area of the building. These ACMs will be incorporated into B&L's asbestos abatement design documents for the project. These abatement drawing and specifications will comply with state and federal regulations as they apply to asbestos abatement. In accordance with NYSDOL

Industrial Code Rule 56, all material determined to be asbestos containing must be removed by a NYS licensed asbestos abatement contractor prior any renovation impacting these materials.

B&L will also prepare a cleaning and decontamination specification for the bat/animal waste in the attic of the building.

If you have any questions, please call me at (315) 457-5200. It was a pleasure working with you on this project and I hope we can be of service in the future.

Very truly yours,

BARTON & LOGUIDICE, P.C.

David A. Morse
Senior Project Industrial Hygienist

John E. Rigge
Senior Associate

DAM/JER/akg

Attachments

Appendix A

NYSDOL Inspector Certifications and Company License

NEW YORK STATE - DEPARTMENT OF LABOR
DIVISION OF SAFETY AND HEALTH
LICENSE AND CERTIFICATE UNIT
STATE CAMPUS BUILDING 12
ALBANY, NY 12240

ASBESTOS HANDLING LICENSE

Barton & Loguidice, P.C.

P.O. Box 3107

Syracuse, NY 13220

FILE NUMBER: 99-0130
LICENSE NUMBER: 29267
LICENSE CLASS: RESTRICTED
DATE OF ISSUE: 02/09/2011
EXPIRATION DATE: 02/28/2012

Duly Authorized Representative – Scott D Nostrand:

This license has been issued in accordance with applicable provisions of Article 30 of the Labor Law of New York State and of the New York State Codes, Rules and Regulations (12 NYCRR Part 56). It is subject to suspension or revocation for a (1) serious violation of state, federal or local laws with regard to the conduct of an asbestos project, or (2) demonstrated lack of responsibility in the conduct of any job involving asbestos or asbestos material.

This license is valid only for the contractor named above and this license or a photocopy must be prominently displayed at the asbestos project worksite. This license verifies that all persons employed by the licensee on an asbestos project in New York State have been issued an Asbestos Certificate, appropriate for the type of work they perform, by the New York State Department of Labor.

Maureen A. Cox

Maureen A. Cox, Director
FOR THE COMMISSIONER OF LABOR

SH 432 (4-07)

STATE OF NEW YORK - DEPARTMENT OF LABOR

ASBESTOS CERTIFICATE

DAVID A MORSE
CLASS(EXPIRES)
C ATEC(12/11) D INSP(12/11)
H PM (12/11)

CERT# 94-16657
DMV#

MUST BE CARRIED ON ASBESTOS PROJECTS

EYES GRN
HAIR BRO
HGT 5' 11"

IF FOUND RETURN TO:
NYSDOL - L&C UNIT
ROOM 161A BUILDING 12
STATE OFFICE CAMPUS
ALBANY NY 12240

STATE OF NEW YORK - DEPARTMENT OF LABOR

ASBESTOS CERTIFICATE

TIMOTHY J STRZEPEK
CLASS(EXPIRES)
C ATEC(07/12) D INSP(07/12)
H PM (07/12)

CERT# 90-03209
DMV# 685146125

MUST BE CARRIED ON ASBESTOS PROJECTS

EYES BRO
HAIR BRO
HGT 5' 10"

IF FOUND RETURN TO:
NYSDOL - L&C UNIT
ROOM 161A BUILDING 12
STATE OFFICE CAMPUS
ALBANY NY 12240

Appendix B

Asbestos Laboratory Reports, Laboratory Certifications, and Sample Chain-of-Custody Forms

Please Reply To:

AmeriSci New York
117 EAST 30TH ST.
NEW YORK, NY 10016
TEL: (212) 679-8600 • FAX: (212) 679-3114

FACSIMILE TELECOPY TRANSMISSION

To: John E. Rigge
Barton & Loguidice, P.C.
Fax #: (315) 451-0052

Email: jrigge@bartonandloguidice.com

From: Ella Babayeva
AmeriSci Job #: 211121216
Subject: ELAP-PLM/TEM 3 day Results
Client Project: 906.019.001; Schopfer Architects, LLP; VA Medical Center Bldg. 34, Bath, NY

Date: Monday, December 05, 2011
Time: 10:28:08
Comments:

Number of Pages: 6
(including cover sheet)

CONFIDENTIALITY NOTICE: Unless otherwise indicated, the information contained in this communication is confidential information intended for use of the individual named above. If the reader of this communication is not the intended recipient, you are hereby notified that any dissemination, distribution or copying of this communication is prohibited. If you have received this communication in error, please immediately notify the sender by telephone and return the original message to the above address via the US Postal Service at our expense. Preliminary data reported here will be verified before final report is issued. Samples are disposed of in 60 days or unless otherwise instructed by the protocol or special instructions in writing. Thank you.

AmeriSci New York
117 EAST 30TH ST.
NEW YORK, NY 10016
TEL: (212) 679-8600 • FAX: (212) 679-3114

PLM Bulk Asbestos Report

Barton & Loguidice, P.C.
Attn: John E. Rigge
PO Box 3107
290 Elwood Davis Road
Syracuse, NY 13220

Date Received 12/02/11 **AmeriSci Job #** 211121216
Date Examined 12/04/11 **P.O. #**
ELAP # 11480 **Page** 1 **of** 11
RE: 906.019.001; Schopfer Architects, LLP; VA Medical Center Bldg. 34, Bath, NY

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
CLSH-1-1 1 **Location:** Bulk Material	211121216-01	*No*	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
Analyst Description: White/Tan, Homogeneous, Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Cellulose 20 %, Non-fibrous 80 %			
CLSH-1-2 1 **Location:** Bulk Material	211121216-02	*No*	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
Analyst Description: OffWhite/Tan, Homogeneous, Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Cellulose 10 %, Non-fibrous 90 %			
CLSH-1-3 1 **Location:** Bulk Material	211121216-03	*No*	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
Analyst Description: OffWhite/Tan, Homogeneous, Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Cellulose 15 %, Non-fibrous 85 %			
WLPL-2-1 2 **Location:** Bulk Material	211121216-04	*No*	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
Analyst Description: Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 100 %			
WLPL-2-2 2 **Location:** Bulk Material	211121216-05	*No*	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
Analyst Description: Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 100 %			

See Reporting notes on last page

PLM Bulk Asbestos Report

906.019.001; Schopfer Architects, LLP; VA Medical Center
Bldg. 34, Bath, NY

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
WLPL-2-3 2 **Location:** Bulk Material **Analyst Description:** Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 100 %	211121216-06	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
FIT-3-1 3 **Location:** Bulk Material **Analyst Description:** Grey, Homogeneous, Fibrous, Bulk Material **Asbestos Types:** Chrysotile 2.0 % **Other Material:** Fibrous glass 45 %, Mineral Wool 3 %, Non-fibrous 50 %	211121216-07	***Yes***	2 % (ELAP 198.1; 400pc) by Ella Babayeva on 12/04/11
FIT-3-2 3 **Location:** Bulk Material **Analyst Description:** Bulk Material **Asbestos Types:** **Other Material:**	211121216-08		NA/PS
FIT-3-3 3 **Location:** Bulk Material **Analyst Description:** Bulk Material **Asbestos Types:** **Other Material:**	211121216-09		NA/PS
PI-4-1 4 **Location:** Bulk Material **Analyst Description:** White, Homogeneous, Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Cellulose 95 %, Non-fibrous 5 %	211121216-10	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
PI-4-2 4 **Location:** Bulk Material **Analyst Description:** White, Homogeneous, Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Cellulose 90 %, Non-fibrous 10 %	211121216-11	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11

See Reporting notes on last page

PLM Bulk Asbestos Report

906.019.001; Schopfer Architects, LLP; VA Medical Center
Bldg. 34, Bath, NY

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
PI-4-3 4 **Location:** Bulk Material **Analyst Description:** White, Homogeneous, Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Cellulose 95 %, Non-fibrous 5 %	211121216-12	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
GROUT-5-1 5 **Location:** Bulk Material **Analyst Description:** White, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 100 %	211121216-13	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
GROUT-5-2 5 **Location:** Bulk Material **Analyst Description:** White, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 100 %	211121216-14	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
GROUT-5-3 5 **Location:** Bulk Material **Analyst Description:** White, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 100 %	211121216-15	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
WLPL-10-1 10 **Location:** Bulk Material **Analyst Description:** Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 100 %	211121216-16	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
WLPL-10-2 10 **Location:** Bulk Material **Analyst Description:** Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 100 %	211121216-17	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11

See Reporting notes on last page

PLM Bulk Asbestos Report

906.019.001; Schopfer Architects, LLP; VA Medical Center
Bldg. 34, Bath, NY

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
WLPL-10-3 10 **Location:** Bulk Material	211121216-18	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
Analyst Description: Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 100 %			
WLSH-11-1 11 **Location:** Bulk Material	211121216-19	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
Analyst Description: White/Off-White, Heterogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 100 %			
WLSH-11-2 11 **Location:** Bulk Material	211121216-20	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
Analyst Description: White/Off-White, Heterogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 100 %			
WLSH-11-3 11 **Location:** Bulk Material	211121216-21	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
Analyst Description: OffWhite, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Cellulose Trace, Non-fibrous 100 %			
DOOR-25-1 25 **Location:** Bulk Material	211121216-22	***No***	NAD (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
Analyst Description: OffWhite, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Cellulose Trace, Fibrous glass Trace, Non-fibrous 100 %			
DOOR-25-2 25 **Location:** Bulk Material	211121216-23	***Yes***	30.8 % (by NYS ELAP 198.1) by Ella Babayeva on 12/04/11
Analyst Description: White, Homogeneous, Fibrous, Bulk Material **Asbestos Types:** Chrysotile 30.8 % **Other Material:** Non-fibrous 69.2 %			

See Reporting notes on last page

PLM Bulk Asbestos Report

906.019.001; Schopfer Architects, LLP; VA Medical Center
Bldg. 34, Bath, NY

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
DOOR-25-3 25 **Location:** Bulk Material **Analyst Description:** Bulk Material **Asbestos Types:** **Other Material:**	211121216-24		NA/PS
FLVCS-6-1 6 **Location:** Bulk Material **Analyst Description:** OffWhite/Blue, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 3.5 %	211121216-25	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
FLVCS-6-2 6 **Location:** Bulk Material **Analyst Description:** OffWhite/Blue, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 4.6 %	211121216-26	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
CLLI-7-1 7 **Location:** Bulk Material **Analyst Description:** Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 36.6 %	211121216-27	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
CLLI-7-2 7 **Location:** Bulk Material **Analyst Description:** Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 44.6 %	211121216-28	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
BBD-8-1 8 **Location:** Bulk Material **Analyst Description:** Green, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 40.4 %	211121216-29	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11

See Reporting notes on last page

PLM Bulk Asbestos Report

906.019.001; Schopfer Architects, LLP; VA Medical Center
Bldg. 34, Bath, NY

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
BBD-8-2 8 **Location:** Bulk Material	211121216-30	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Green, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 39.8 %			
BBDMAS-9-1 9 **Location:** Bulk Material	211121216-31	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Beige, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 38.8 %			
BBDMAS-9-2 9 **Location:** Bulk Material	211121216-32	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Beige, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 45.2 %			
FLVCT-12-1 12 **Location:** Bulk Material	211121216-33	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Tan, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 8 %			
FLVCT-12-2 12 **Location:** Bulk Material	211121216-34	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Tan, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 12.1 %			
FLMAS-13-1 13 **Location:** Bulk Material	211121216-35	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Black, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 10.7 %			

See Reporting notes on last page

PLM Bulk Asbestos Report

906.019.001; Schopfer Architects, LLP; VA Medical Center
Bldg. 34, Bath, NY

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
FLMAS-13-2 13 **Location:** Bulk Material **Analyst Description:** Black, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 13.7 %	211121216-36	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
CLTL-14-1 14 **Location:** Bulk Material **Analyst Description:** Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 46.1 %	211121216-37	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
CLTL-14-2 14 **Location:** Bulk Material **Analyst Description:** Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 48.4 %	211121216-38	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
FLMAS-15-1 15 **Location:** Bulk Material **Analyst Description:** Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 12.5 %	211121216-39	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
FLMAS-15-2 15 **Location:** Bulk Material **Analyst Description:** Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 9.8 %	211121216-40	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
FLVCS-16-1 16 **Location:** Bulk Material **Analyst Description:** Green, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 6.2 %	211121216-41	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11

See Reporting notes on last page

PLM Bulk Asbestos Report

906.019.001; Schopfer Architects, LLP; VA Medical Center
Bldg. 34, Bath, NY

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
FLVCS-16-2 16 **Location:** Bulk Material	211121216-42	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Green, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 29.1 %			
FS-17-1 17 **Location:** Bulk Material	211121216-43	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Red, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 26.5 %			
FS-17-2 17 **Location:** Bulk Material	211121216-44	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Red, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 19.7 %			
FOIL-18-1 18 **Location:** Bulk Material	211121216-45	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Silver/Black/Tan, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 23.2 %			
FOIL-18-2 18 **Location:** Bulk Material	211121216-46	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Silver/Black/Tan, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 1.8 %			
TP-19-1 19 **Location:** Bulk Material	211121216-47	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Black, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 1.9 %			

See Reporting notes on last page

PLM Bulk Asbestos Report

906.019.001; Schopfer Architects, LLP; VA Medical Center
Bldg. 34, Bath, NY

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
TP-19-2 19 **Location:** Bulk Material	211121216-48	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Black, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 9.1 %			
FLMAS-20-1 20 **Location:** Bulk Material	211121216-49	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Black, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 6.3 %			
FLMAS-20-2 20 **Location:** Bulk Material	211121216-50	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Black, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 7 %			
CAULK-21-1 21 **Location:** Bulk Material	211121216-51	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 8.3 %			
CAULK-21-2 21 **Location:** Bulk Material	211121216-52	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 7.3 %			
CAULK-22-1 22 **Location:** Bulk Material	211121216-53	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: White, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 11.9 %			

See Reporting notes on last page

PLM Bulk Asbestos Report

906.019.001; Schopfer Architects, LLP; VA Medical Center
Bldg. 34, Bath, NY

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
CAULK-22-2 22 **Location:** Bulk Material	211121216-54	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: White, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 8.1 %			
RFSH-23-1 23 **Location:** Bulk Material	211121216-55	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Green/Black, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Fibrous glass 5 %, Non-fibrous 20.9 %			
RFSH-23-2 23 **Location:** Bulk Material	211121216-56	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Green/Black, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Fibrous glass 9 %, Non-fibrous 20.4 %			
CAULK-24-1 24 **Location:** Bulk Material	211121216-57	***Yes***	Trace (<0.25 % pc) (ELAP 198.6; 400pc) by Ella Babayeva on 12/04/11
Analyst Description: Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** Chrysotile <0.25 % pc **Other Material:** Non-fibrous 44 %			
CAULK-24-2 24 **Location:** Bulk Material	211121216-58	***Yes***	2 % (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: Grey, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** Chrysotile 2.0 % **Other Material:** Non-fibrous 10.8 %			
WLMAS-26-1 26 **Location:** Bulk Material	211121216-59	***No***	NAD (by NYS ELAP 198.6) by Ella Babayeva on 12/04/11
Analyst Description: White, Homogeneous, Non-Fibrous, Bulk Material **Asbestos Types:** **Other Material:** Non-fibrous 1.9 %			

See Reporting notes on last page

PLM Bulk Asbestos Report

906.019.001; Schopfer Architects, LLP; VA Medical Center
Bldg. 34, Bath, NY

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
WLMAS-26-2	211121216-60	***No***	NAD
26 **Location:** Bulk Material			(by NYS ELAP 198.6) by Ella Babayeva on 12/04/11

Analyst Description: White, Homogeneous, Non-Fibrous, Bulk Material
Asbestos Types:
Other Material: Non-fibrous 22.4 %

Reporting Notes:
Analyzed by: Ella Babayeva

*NAD/NSD =no asbestos detected; NA =not analyzed; NA/PS=not analyzed/positive stop; PLM Bulk Asbestos Analysis by EPA 600/M4-82-020 per 40 CFR 763 (NVLAP Lab Code 200546-0), ELAP PLM Method 198.1 for NY friable samples or 198.6 for NOB samples (NY ELAP Lab ID11480); Note:PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. NAD or Trace results by PLM are inconclusive, TEM is currently the only method that can be used to determine if this material can be considered or treated as non asbestos-containing in NY State (also see EPA Advisory for floor tile, FR 59,146,38970,8/1/94) National Institute of Standards and Technology Accreditation requirements mandate that this report must not be reproduced except in full without the approval of the lab.This PLM report relates ONLY to the items tested. AIHA Lab # 102843, RI Cert#AAL-094, CT Cert#PH-0186, Mass Cert#AA000054.

Reviewed By:_____ _____END OF REPORT_____

AmeriSci Job #: **211121216**

Client Name: Barton & Loguidice, P.C.

Table I
Summary of Bulk Asbestos Analysis Results

906.019.001; Schopfer Architects, LLP; VA Medical Center Bldg. 34, Bath, NY

AmeriSci Sample #	Client Sample#	HG Area	Sample Weight (gram)	Heat Sensitive Organic %	Acid Soluble Inorganic %	Insoluble Non-Asbestos Inorganic %	** Asbestos % by PLM/DS	** Asbestos % by TEM
01	CLSH-1-1	1	----	----	----	----	NAD	NA
Location: Bulk Material								
02	CLSH-1-2	1	----	----	----	----	NAD	NA
Location: Bulk Material								
03	CLSH-1-3	1	----	----	----	----	NAD	NA
Location: Bulk Material								
04	WLPL-2-1	2	----	----	----	----	NAD	NA
Location: Bulk Material								
05	WLPL-2-2	2	----	----	----	----	NAD	NA
Location: Bulk Material								
06	WLPL-2-3	2	----	----	----	----	NAD	NA
Location: Bulk Material								
07	FIT-3-1	3	----	----	----	----	Chrysotile 2.0	NA
Location: Bulk Material								
08	FIT-3-2	3	----	----	----	----	NA/PS	NA
Location: Bulk Material								
09	FIT-3-3	3	----	----	----	----	NA/PS	NA
Location: Bulk Material								
10	PI-4-1	4	----	----	----	----	NAD	NA
Location: Bulk Material								
11	PI-4-2	4	----	----	----	----	NAD	NA
Location: Bulk Material								
12	PI-4-3	4	----	----	----	----	NAD	NA
Location: Bulk Material								
13	GROUT-5-1	5	----	----	----	----	NAD	NA
Location: Bulk Material								
14	GROUT-5-2	5	----	----	----	----	NAD	NA
Location: Bulk Material								
15	GROUT-5-3	5	----	----	----	----	NAD	NA
Location: Bulk Material								
16	WLPL-10-1	10	----	----	----	----	NAD	NA
Location: Bulk Material								

See Reporting notes on last page

Table I
Summary of Bulk Asbestos Analysis Results
906.019.001; Schopfer Architects, LLP; VA Medical Center Bldg. 34, Bath, NY

AmeriSci Sample #	Client Sample#	HG Area	Sample Weight (gram)	Heat Sensitive Organic %	Acid Soluble Inorganic %	Insoluble Non-Asbestos Inorganic %	** Asbestos % by PLM/DS	** Asbestos % by TEM
17	WLPL-10-2	10	---	---	---	---	NAD	NA
Location: Bulk Material								
18	WLPL-10-3	10	---	---	---	---	NAD	NA
Location: Bulk Material								
19	WLSH-11-1	11	---	---	---	---	NAD	NA
Location: Bulk Material								
20	WLSH-11-2	11	---	---	---	---	NAD	NA
Location: Bulk Material								
21	WLSH-11-3	11	---	---	---	---	NAD	NA
Location: Bulk Material								
22	DOOR-25-1	25	---	---	---	---	NAD	NA
Location: Bulk Material								
23	DOOR-25-2	25	---	---	---	---	Chrysotile 30.8	NA
Location: Bulk Material								
24	DOOR-25-3	25	---	---	---	---	NA/PS	NA
Location: Bulk Material								
25	FLVCS-6-1	6	0.288	58.7	37.8	3.5	NAD	NAD
Location: Bulk Material								
26	FLVCS-6-2	6	0.261	58.6	36.8	4.6	NAD	NAD
Location: Bulk Material								
27	CLLI-7-1	7	0.268	28.7	34.7	36.6	NAD	NAD
Location: Bulk Material								
28	CLLI-7-2	7	0.242	28.9	26.4	44.6	NAD	NAD
Location: Bulk Material								
29	BBD-8-1	8	0.371	36.9	22.6	40.4	NAD	NAD
Location: Bulk Material								
30	BBD-8-2	8	0.420	40.2	20.0	39.8	NAD	NAD
Location: Bulk Material								
31	BBDMAS-9-1	9	0.520	42.1	19.0	38.8	NAD	NAD
Location: Bulk Material								
32	BBDMAS-9-2	9	0.250	39.6	15.2	45.2	NAD	NAD
Location: Bulk Material								

See Reporting notes on last page

Table I
Summary of Bulk Asbestos Analysis Results
906.019.001; Schopfer Architects, LLP; VA Medical Center Bldg. 34, Bath, NY

AmeriSci Sample #	Client Sample#	HG Area	Sample Weight (gram)	Heat Sensitive Organic %	Acid Soluble Inorganic %	Insoluble Non-Asbestos Inorganic %	** Asbestos % by PLM/DS	** Asbestos % by TEM
33	FLVCT-12-1	12	0.314	22.6	69.4	8.0	NAD	NAD
Location: Bulk Material								
34	FLVCT-12-2	12	0.406	22.9	65.0	12.1	NAD	NAD
Location: Bulk Material								
35	FLMAS-13-1	13	0.234	58.1	31.2	10.7	NAD	NAD
Location: Bulk Material								
36	FLMAS-13-2	13	0.351	49.0	37.3	13.7	NAD	NAD
Location: Bulk Material								
37	CLTL-14-1	14	0.165	23.0	30.9	46.1	NAD	NAD
Location: Bulk Material								
38	CLTL-14-2	14	0.122	22.1	29.5	48.4	NAD	NAD
Location: Bulk Material								
39	FLMAS-15-1	15	0.361	29.4	58.2	12.5	NAD	NAD
Location: Bulk Material								
40	FLMAS-15-2	15	0.369	27.4	62.9	9.8	NAD	NAD
Location: Bulk Material								
41	FLVCS-16-1	16	0.292	56.8	37.0	6.2	NAD	NAD
Location: Bulk Material								
42	FLVCS-16-2	16	0.326	52.1	18.7	29.1	NAD	NAD
Location: Bulk Material								
43	FS-17-1	17	0.162	54.3	19.1	26.5	NAD	NAD
Location: Bulk Material								
44	FS-17-2	17	0.305	78.0	2.3	19.7	NAD	NAD
Location: Bulk Material								
45	FOIL-18-1	18	0.272	76.5	0.4	23.2	NAD	NAD
Location: Bulk Material								
46	FOIL-18-2	18	0.553	97.1	1.1	1.8	NAD	NAD
Location: Bulk Material								
47	TP-19-1	19	0.259	97.3	0.8	1.9	NAD	NAD
Location: Bulk Material								
48	TP-19-2	19	0.276	83.3	7.6	9.1	NAD	NAD
Location: Bulk Material								

See Reporting notes on last page

Table I
Summary of Bulk Asbestos Analysis Results
906.019.001; Schopfer Architects, LLP; VA Medical Center Bldg. 34, Bath, NY

AmeriSci Sample #	Client Sample#	HG Area	Sample Weight (gram)	Heat Sensitive Organic %	Acid Soluble Inorganic %	Insoluble Non-Asbestos Inorganic %	** Asbestos % by PLM/DS	** Asbestos % by TEM
49	FLMAS-20-1	20	0.205	87.8	5.9	6.3	NAD	NAD
Location:	Bulk Material							
50	FLMAS-20-2	20	0.330	50.6	42.4	6.8	NAD	Chrysotile <1.0
Location:	Bulk Material							
51	CAULK-21-1	21	0.384	51.0	40.6	8.3	NAD	NAD
Location:	Bulk Material							
52	CAULK-21-2	21	0.110	14.5	78.2	7.3	NAD	NAD
Location:	Bulk Material							
53	CAULK-22-1	22	0.243	71.6	16.5	11.9	NAD	NAD
Location:	Bulk Material							
54	CAULK-22-2	22	0.185	70.8	21.1	8.1	NAD	NAD
Location:	Bulk Material							
55	RFSH-23-1	23	0.490	24.5	49.6	25.9	NAD	NAD
Location:	Bulk Material							
56	RFSH-23-2	23	0.913	25.6	45.0	29.4	NAD	NAD
Location:	Bulk Material							
57	CAULK-24-1	24	0.343	13.1	42.9	44.0	Chrysotile <0.25	NA
Location:	Bulk Material							
58	CAULK-24-2	24	0.297	26.3	60.9	10.8	Chrysotile 2.0	NA
Location:	Bulk Material							
59	WLMAS-26-1	26	0.104	30.8	67.3	1.9	NAD	NAD
Location:	Bulk Material							
60	WLMAS-26-2	26	0.134	23.1	54.5	22.4	NAD	NAD
Location:	Bulk Material							

See Reporting notes on last page

AmeriSci Job #: **211121216**

Client Name: Barton & Loguidice, P.C.

Table I
Summary of Bulk Asbestos Analysis Results

906.019.001; Schopfer Architects, LLP; VA Medical Center Bldg. 34; Bath, NY

AmeriSci Sample #	Client Sample#	HG Area	Sample Weight (gram)	Heat Sensitive Organic %	Acid Soluble Inorganic %	Insoluble Non-Asbestos Inorganic %	** Asbestos % by PLM/DS	** Asbestos % by TEM

Analyzed by. Marik Peysakhov_____; Date Analyzed 12/5/2011

**Quantitative Analysis (Semi/Full); Bulk Asbestos Analysis - PLM by EPA 600/M4-82-020 per 40 CFR or ELAP 198.1 for New York friable samples or ELAP 198.6 for New York NOB samples; TEM (Semi/Full) by EPA 600/R-93/116 (not covered by NVLAP Bulk accreditation) or ELAP 198.4; for New York samples; NAD = no asbestos detected during a quantitative analysis; NA = not analyzed; Trace = <1%; Quantitation for beginning weights of <0.1 grams should be considered as qualitative only; Qualitative Analysis: Asbestos analysis results of "Present" or "NVA = No Visible Asbestos" represents results for Qualitative PLM or TEM Analysis only (no accreditation coverage available from any regulatory agency for qualitative analyses); AIHA Lab # 102843, NVLAP Lab Code 200546-0, NYSDOH ELAP Lab ID#11480.

Warning Note: PLM limitation, only TEM will resolve fibers <0.25 micrometers in diameter. TEM bulk analysis is representative of the fine grained matrix material and may not be representative of non-uniformly dispersed debris for which PLM evaluation is recommended (i.e. soils and other heterogenous materials).

Reviewed By:_____

211121216

Barton & Loguidice, P.C.

Engineers • Environmental Scientists • Planners • Landscape Designers

Asbestos Bulk Sample Chain-of-Custody

290 Elwood Davis Road/Box 3107
Syracuse, New York 13220
(315) 457-5200 Fax: (315) 451-0052

Project: **Schopfer Architects, LLP**
VA Medical Center Bldg. 34
Bath, NY

Project No.: **906.019.001**
Date Sampled: **11/30/2011**
Sampled by: **DAM**

Sample Identification	Date Sampled	Sample Medium	Analysis Required	Method Reference
CLSH - 1 - 1,2,3	**11/30/2011**	BULK	% Asbestos	PLM
WLPL - 2 - 1,2,3	**11/30/2011**	BULK	% Asbestos	PLM
FIT - 3 - 1,2,3	**11/30/2011**	BULK	% Asbestos	PLM
PI - 4 - 1,2,3	**11/30/2011**	BULK	% Asbestos	PLM
GROUT - 5 - 1,2,3	**11/30/2011**	BULK	% Asbestos	PLM
WLPL - 10 - 1,2,3	**11/30/2011**	BULK	% Asbestos	PLM
WLSH - 11 - 1,2,3	**11/30/2011**	BULK	% Asbestos	PLM
DOOR - 25 - 1,2,3	**11/30/2011**	BULK	% Asbestos	PLM
		BULK	% Asbestos	PLM
		BULK	% Asbestos	PLM
		BULK	% Asbestos	PLM
		BULK	% Asbestos	PLM
		BULK	% Asbestos	PLM
		BULK	% Asbestos	PLM

Comments: **Stop at first positive (> than 1% asbestos) in each triplicate sample series.**
Prices as per agreement.

Report Results to:

E-mail: **TAT: 72 HOURS**
Fax: **Dave Morse** **(315) 451-0052**
Written: Dave Morse 10 calendar days
Invoice: Dave Morse 10 calendar days

Chain-of-Custody:	Signature	Date
Relinquished by:		12/1/11
Received by Lab.:		12/2/11 1124
Received by Analyst:		

211121216

Barton & Loguidice, P.C.

Engineers • Environmental Scientists • Planners • Landscape Designers

Asbestos Bulk Sample Chain-of-Custody

290 Elwood Davis Road/Box 3107
Syracuse, New York 13220
(315) 457-5200 Fax: (315) 451-0052

Project: Schopfer Architects, LLP
VA Medical Center Bldg. 34
Bath, NY

Project No.: 906.019.001
Date Sampled: 11/30/2011
Sampled by: DAM

Sample Identification	Date Sampled	Sample Medium	Analysis Required	Method Reference
FLVCS - 6 - 1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM
CLLI - 7 - 1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM
BBD - 8 - 1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM
BBDMAS - 9 - 1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM
FLVCT - 12 -1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM
FLMAS - 13 - 1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM
CLTL - 14 - 1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM
FLMAS - 15 - 1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM
FLVCS - 16 - 1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM
FS - 17 - 1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM
FOIL - 18 - 1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM
TP - 19 - 1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM
FLMAS - 20 - 1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM
CAULK - 21 - 1,2	11/30/2011	BULK (NOB)	% Asbestos	PLM grav. / TEM

Comments: **Advance to TEM if PLM result is 1% asbestos or less.**
Stop at first positive in each sample set.

Report Results to:

E-mail:
TAT: 72 HOURS

Fax:	Dave Morse	(315) 451-0052
Written:	Dave Morse	10 calendar days
Invoice:	Dave Morse	10 calendar days

Chain-of-Custody:	Signature	Date
Relinquished by:		12/1/11
Received by Lab.:		12/2/11 1124
Received by Analyst:		

211121216

Barton & Loguidice, P.C.

Engineers • Environmental Scientists • Planners • Landscape Designers

Asbestos Bulk Sample Chain-of-Custody

290 Elwood Davis Road/Box 3107
Syracuse, New York 13220
(315) 457-5200 Fax: (315) 451-0052

Project: **Schopfer Architects, LLP**
VA Medical Center Bldg. 34
Bath, NY

Project No.: **906.019.001**
Date Sampled: **11/30/2011**
Sampled by: **DAM**

Sample Identification	Date Sampled	Sample Medium	Analysis Required	Method Reference
CAULK - 22 - 1,2	**11/30/2011**	BULK (NOB)	% Asbestos	PLM grav. / TEM
RFSII - 23 - 1,2	**11/30/2011**	BULK (NOB)	% Asbestos	PLM grav. / TEM
CAULK - 24 - 1,2	**11/30/2011**	BULK (NOB)	% Asbestos	PLM grav. / TEM
WLMAS - 26 - 1,2	**11/30/2011**	BULK (NOB)	% Asbestos	PLM grav. / TEM
		BULK (NOB)	% Asbestos	PLM grav. / TEM
		BULK (NOB)	% Asbestos	PLM grav. / TEM
		BULK (NOB)	% Asbestos	PLM grav. / TEM
		BULK (NOB)	% Asbestos	PLM grav. / TEM
		BULK (NOB)	% Asbestos	PLM grav. / TEM
		BULK (NOB)	% Asbestos	PLM grav. / TEM
		BULK (NOB)	% Asbestos	PLM grav. / TEM
		BULK (NOB)	% Asbestos	PLM grav. / TEM
		BULK (NOB)	% Asbestos	PLM grav. / TEM
		BULK (NOB)	% Asbestos	PLM grav. / TEM

Comments: **Advance to TEM if PLM result is 1% asbestos or less.**
Stop at first positive in each sample set.

Report Results to:

E-mail:
Fax: **Dave Morse** **(315) 451-0052**
Written: Dave Morse 10 calendar days
Invoice: Dave Morse 10 calendar days

TAT: 72 HOURS

Chain-of-Custody:	Signature	Date
Relinquished by:		12/1/11
Received by Lab.:		12/2/11 1124
Received by Analyst:		