



- SUPPLY NOTES:**
1. WATER SUPPLY LINES TO BE CPVC, SUPPORTED 4' O.C. MAX.
 2. WATER TEMPERATURE FACTORY SET AT A MAXIMUM OF 110°F.
 3. SHUT OFF VALVES ARE TO BE PROVIDED AT EACH FIXTURE IN ACCORDANCE WITH SCHEMATICS ABOVE.
 4. WATER HAMMER ARRESTORS PROVIDED, OR IF AIR CHAMBERS, TO BE MINIMUM 15" LONG AND NOT LESS THAN THE DIAMETER OF PIPE SERVED.
 5. DIELECTRIC UNIONS TO BE USED AT CONNECTIONS OF WATER LINES TO WATER HEATER.
 6. COLD WATER INLET TO BE PROVIDED WITH A SHUT OFF VALVE ABOVE FLOOR AT THE COLD WATER SUPPLY PER SCHEMATIC.
 7. FULL SIZED SHUT OFF VALVE TO BE PROVIDED BETWEEN BUILDING AND WATER MAIN/METER BY OTHERS ON SITE.
- WASTE NOTES:**
1. DMV MATERIAL TO BE CONCEALED SCHEDULE 40 PVC.
 2. ALL PIPES TO BE SECURED MAXIMUM 4' O.C.
 3. ALL CLEAN OUTS SHALL BE ACCESSIBLE, PROVIDED AT THE BASE OF ALL WASTE/SOIL STACKS, AND SO THAT ALL HORIZONTAL PIPING MAY BE REACHED WITHOUT PASSING THROUGH MORE THAN 45° OF TURNS.
 4. 1/4" PER. FT SLOPE PROVIDED ON ALL HORIZONTAL BRANCHES.
 5. VENT PIPE SHALL END 12" ABOVE FINISHED ROOF AND NOT BE LOCATED WITHIN 10' OF OTHER VENT OPENINGS.
 6. ALL VERTICAL TO HORIZONTAL OR HORIZONTAL TO HORIZONTAL CHANGES IN DIRECTION SHALL BE THROUGH LONG TURN T.Y. OR COMBINATION WYE FITTINGS WITH 1/8" BEND.
 7. ALL HORIZONTAL TO VERTICAL CHANGES IN DIRECTION SHALL BE THROUGH SANITARY TEE, OR IF AT THE SAME LEVEL ON THE STACK THEN THROUGH AN APPROVED DOUBLE FIXTURE FITTING.

MOBILE MODULAR
EXPRESS INC.
P.O. BOX 1099
EDGEWOOD, MD 21040
1-410-676-3700
WWW.MOBILEMODULAR.COM

Mobile/Modular
EXPRESS LLC.
64 HESS ROAD
LEOLA, PA 17450
PHONE: (717) 656-2081
FAX: (717) 656-4349

BUSINESS OFFICE
MODULAR UNIT
FO6064

PLUMBING
SCHEMATICS

DWG. NO.:	P1	DATE	12-4-08				
DESIGNED:		REVISIONS					
10/2/08							
PRINTED:							
6/18/12 12:01PM							
SERIAL NO.:		NTA REVISION					
08102363-67							
SCALE:							
NTS							