



- LEGEND:
- SV1: SHEET VINYL
MFG.: TEKNOFLOR
PATTERN: NATURAL
COLOR: #5203 BEECH NUT
WIDTH: 6'-7" W.
 - SV2: SHEET VINYL
MFG.: TEKNOFLOR
PATTERN: OAK COLLECTION
COLOR: #73804 DARK OAK
WIDTH: 6'-7" W.
 - SV3: SHEET VINYL COVERED UP WALL 6"
TO MATCH ADJACENT SHEET VINYL

- GENERAL NOTES:
- CONTRACTOR TO PROVIDE FLOORING AND WELDING ROD SAMPLES TO BE APPROVED BY VA INTERIOR DESIGNER
 - ALL WORK SHOULD BE DONE IN ACCORDANCE WITH NFPA, VA, AND STATE OF IDAHO REQUIREMENTS AND ALL OTHER APPLICABLE CODES
 - WORK TO BE COMPLETED OFF HOURS FROM 12:00AM-8:00AM AND TO BE COORDINATED WITH EMERGENCY DEPARTMENT
 - REMOVE AND INSTALL TRANSITION STRIPS AS NECESSARY AND OTHER ITEMS AS NECESSARY TO COMPLETE WORK
 - SITE MEASUREMENT REQUIRED TO VERIFY ALL DIMENSIONS
 - REMOVE EXISTING FLOORING AND BASE, PROVIDE AND INSTALL ARDEX MC RAPID MOISTURE BARRIER, PREPARE FLOOR TO ACCEPT NEW FLOORING, AND PROVIDE AND INSTALL NEW FLOORING, WALL BASE, AND WELDING RODS AT SEAMS.



BUILDING 85 - FIRST FLOOR - ER

SCALE: 1/8" = 1'-0"

