

Project Name:

Building 200

Survey Segment:

A: Building 200

Address:

4150 Clement, San Francisco, CA 94121

<u>Homog. Area #</u>	<u>Asbestos Results</u>	<u>Material Description</u>	<u>Quantity</u>	<u>Location / *(Quantity)*</u>	<u>Condition</u>	<u>Damage Type</u>	<u>Friability</u>	<u>Exposure Pot.</u>
176	ND None Detected	Skim Coat Smooth on Wallboard (MtI #175) 2nd Floor	330 Sq.Ft.	Throughout Space: S Walls *330*□	Good	None	Friable	Low
176B	ND None Detected	Skim Coat Smooth on Wallboard (MtI #175) 2nd Floor (Split Layer: Drywall-Pink)	330 Sq.Ft.	Throughout Space: S Walls *330*□	Good	None	Friable	Low
176C	ND None Detected	Skim Coat Smooth on Wallboard (MtI #175) 2nd Floor (Split Layer: Mastic-Off-White)	330 Sq.Ft.	Throughout Space: S Walls *330*□	Good	None	Friable	Low
2: 2A-101B Fire Closet								
113	NEG	Plaster Smooth White Over Coarse Gray [Old MtI #317]	42 Sq.Ft.	Throughout Space: *42*□	Good	None	Non-Friable	Low
142	NEG	Baseboard Black w/ Brown Adhesive (Old MtI #322)	5 Lin.Ft.	Throughout Space: *5*□	Good	None	Non-Friable	Low
153	1-5% Chrysotile	Floor Tile 9x9 Gray & Lt Gray Marble Pattern w/ Black Mastic	3 Sq.Ft.	Throughout Space: *3*□	Good	None	Non-Friable	Low
153B	1-5% Chrysotile	Floor Tile 9x9 Gray & Lt Gray Marble Pattern w/ Black Mastic (Split Layer: Mastic-Black)	3 Sq.Ft.	Throughout Space: *3*□	Good	None	Non-Friable	Low

Length: 3 ft. Width: 1 ft. Height: 7 ft. Area: 3 sq.ft
Floor: Floor Tile Wall: Plaster Ceiling: Plaster
Asb Debris: No Notes:

Project Name:

Building 200

Survey Segment:

A: Building 200

Address:

4150 Clement, San Francisco, CA 94121

Homog. Area #	Asbestos Results	Material Description	Quantity	Location / *(Quantity)*	Condition	DamageType	Friability	ExposurePot.
---------------	------------------	----------------------	----------	-------------------------	-----------	------------	------------	--------------

2: 2A-102 Entry to Restroom

Length: 7 ft. Width: 4 ft. Height: 10 ft. Area: 28 sqft
Floor: Floor Tile Wall: Plaster Ceiling: Ceiling Tile
Asb Debris: No Notes:

101	NEG	Ceiling Tile, Laid-In 2' x 2' w/ Pinholes & Light Texture [Old Mtl #301]	28 Sq.Ft.	Throughout Space: *28*□	Good	None	Friable	Low
106	POS	Vinyl Floor Tile 12x12 Beige w/ Blue and White Streaks & Black Mastic [Old Mtl #304] 1-5% Chrysotile in black mastic	28 Sq.Ft.	Throughout Space: *28*□	Good	None	Non-Friable	Low
113	NEG	Plaster Smooth White Over Coarse Gray [Old Mtl #317]	186 Sq.Ft.	Throughout Space: *186*□	Good	None	Non-Friable	Low
114	NEG	Baseboard Beige w/ Beige/White Adhesive [Old Mtl #308]	16 Lin.Ft.	Throughout Space: *16*□	Good	None	Non-Friable	Low

Project Name:
Building 200

Survey Segment:
A: Building 200

Address:
4150 Clement, San Francisco, CA 94121

Homog. Area #	Asbestos Results	Material Description	Quantity	Location / *(Quantity)*	Condition	Damage Type	Friability	Exposure Pot.
---------------	------------------	----------------------	----------	-------------------------	-----------	-------------	------------	---------------

2: 2A-102A Restroom

Length: 12 ft. Width: 10 ft. Height: 10 ft. Area: 120 sq.ft
Floor: Ceramic Tile Wall: Plaster Ceiling: Ceiling Tile
Ash Debris: No Notes:

101	NEG	Ceiling Tile, Laid-In 2' x 2' w/ Pinholes & Light Texture [Old Mtl #301]	108 Sq.Ft.	Throughout Space: *108*□	Good	None	Friable	Low
110	ND	Ceiling Tile, Laid-In None Detected 2' x 2' w/ Parallel Fissures & Random Pinholes	12 Sq.Ft.	Throughout Space: Various Locations *12*□	Good	None	Friable	Low
113	NEG	Plaster Smooth White Over Coarse Gray [Old Mtl #317]	440 Sq.Ft.	Throughout Space: *440*□	Good	None	Non-Friable	Low
121	POS	Adhesive Mirror	5 Sq.Ft.	Throughout Space: 2 Mirrors on E Wall at SE Corner *5*□	Good	None	Non-Friable	Low
130	POS	Ceramic Wall Tile Adhesive and Grout 4" Off-white (Old Mtl #318)	176 Sq.Ft.	Throughout Space: *176*□	Good	None	Non-Friable	Low
138	ND	Ceramic Floor Tile Adhesive and Grout None Detected 1" Tan w/ Brown Specks	120 Sq.Ft.	Throughout Space: *120*□	Good	None	Non-Friable	Low
138B	ND	Ceramic Floor Tile Adhesive and Grout None Detected 1" Tan w/ Brown Specks (Split Layer: Grout-White)	120 Sq.Ft.	Throughout Space: *120*□	Good	None	Non-Friable	Low
138C	ND	Ceramic Floor Tile Adhesive and Grout None Detected 1" Tan w/ Brown Specks (Split Layer: Plaster-Off-White)	120 Sq.Ft.	Throughout Space: *120*□	Good	None	Non-Friable	Low

<u>Project Name:</u> Building 200		<u>Survey Segment:</u> A: Building 200		<u>Address:</u> 4150 Clement, San Francisco, CA 94121	
<u>Homog. Asbestos Area #</u>	<u>Results</u>	<u>Material Description</u>	<u>Quantity</u>	<u>Location / *(Quantity)*</u>	<u>Condition</u> <u>Damage Type</u> <u>Friability</u> <u>Exposure Pot.</u>
2: 2A-103 Reception					
101	NEG	Ceiling Tile, Laid-In 2' x 2' w/ Pinholes & Light Texture [Old Mtl #301]	352 Sq.Ft.	Throughout Space: *352* <input type="checkbox"/>	Length: 22 ft. Width: 16 ft. Height: 10 ft. Area: 352 sqft Floor: Carpet Wall: Wallboard Ceiling: Ceiling Tile Asb Debris: No Notes: Good None Friable Low
104	ND None Detected	Wallpaper Adhesive Clear Yellow	220 Sq.Ft.	Throughout Space: E Wall *220* <input type="checkbox"/>	Good None Non-Friable Low
105	NEG	Baseboard Gray w/ Beige/White Adhesive (Old Mtl #303)	76 Lin.Ft.	Throughout Space: *76* <input type="checkbox"/>	Good None Non-Friable Low
115	ND None Detected	Carpet Adhesive Tan	352 Sq.Ft.	Throughout Space: *352* <input type="checkbox"/>	Good None Non-Friable Low
177	ND None Detected	Gypsum Wallboard System No Skim 2nd Floor	675 Sq.Ft.	Throughout Space: *675* <input type="checkbox"/>	Good None Friable Low
177B	ND None Detected	Gypsum Wallboard System No Skim 2nd Floor (Split Layer: Texture-Off-White)	675 Sq.Ft.	Throughout Space: *675* <input type="checkbox"/>	Good None Friable Low
Suspected ACM In Each Surveyed Space/Room					
5/13/2010 9:57:14 AM					IHI Environmental Project No. 200

Project Name:
Building 200

Survey Segment:
A: Building 200


Address:
4150 Clement, San Francisco, CA 94121

<u>Homog. Area #</u>	<u>Asbestos Results</u>	<u>Material Description</u>	<u>Quantity</u>	<u>Location / *(Quantity)*</u>	<u>Condition</u>	<u>Damage Type</u>	<u>Friability</u>	<u>Exposure Pot.</u>
----------------------	-------------------------	-----------------------------	-----------------	--------------------------------	------------------	--------------------	-------------------	----------------------

2: 2A-171A Restroom								
Length: 7 ft. Width: 3 ft. Height: 10 ft. Area: 21 sqft								
Floor: Ceramic Tile Wall: Plaster Ceiling: Plaster								
Asb Debris: No Notes:								

113	NEG	Plaster Smooth White Over Coarse Gray [Old Mtl #317]	204 Sq.Ft.	Throughout Space: *204* [†]	Good	None	Non-Friable	Low
121	POS	Adhesive Mirror	2	Sq.Ft. Throughout Space: S Wall, Center *2* [†]	Good	None	Non-Friable	Low
130	POS	Ceramic Wall Tile Adhesive and Grout 4" Off-white (Old Mtl #318)	43	Sq.Ft. Throughout Space: *43* [†]	Good	None	Non-Friable	Low
138	ND None Detected	Ceramic Floor Tile Adhesive and Grout 1" Tan w/ Brown Specks	21	Sq.Ft. Throughout Space: *21* [†]	Good	None	Non-Friable	Low
138B	ND None Detected	Ceramic Floor Tile Adhesive and Grout 1" Tan w/ Brown Specks (Split Layer: Grout-White)	21	Sq.Ft. Throughout Space: *21* [†]	Good	None	Non-Friable	Low
138C	ND None Detected	Ceramic Floor Tile Adhesive and Grout 1" Tan w/ Brown Specks (Split Layer: Plaster-Off-White)	21	Sq.Ft. Throughout Space: *21* [†]	Good	None	Non-Friable	Low

SF VA Medical Center
Building : 200
Second Floor
Asbestos Material Location



PROJECT No: 09B-2173
 SHEET: Bldg200FP02 ML
 DRAWN BY: S. Rahman
 DATE: 12-14-09
 REVISED BY:
 DATE:
 REVISED BY:
 DATE:

- Explanation:**
- ACM Floor Tile Mastic
 - ACM Vinyl Floor Tile
 - ACM Vinyl Sheet Flooring (Assumed)
 - ACM Ceramic Floor Tile Adhesive And Grout (Assumed)
 - ACM Vinyl Sheet Flooring Mastic
 - ACM Terrazzo Flooring (Assumed)
 - ACM Exterior Wall Stucco
 - ACM Ceramic Wall Tile And Adhesive And Grout
 - ACM Skim Coat on Concrete
 - ACM Skim Coat on Wallboard
 - ACM Stair Tread (Assumed)
 - ACM Mirror Adhesive
 - ACM Window Frame Caulking
 - ACM Black Sink Undercoating

