



1. DISCONNECT AND REMOVE ALL EXISTING PNEUMATIC CONTROL VALVES CONNECTED TO THE REMOVED VALV TERNAL UNITS. DISCONNECT AND REMOVE THE EXISTING PNEUMATIC TUBING/PIPING CONNECTED TO EACH CONTROL VALVE BACK TO THE PNEUMATIC PIPING MAIN AS REQUIRED.
2. DISCONNECT AND REMOVE EACH EXISTING WALL MOUNTED THERMOSTAT SHOWN INCLUDING ITS ASSOCIATED PNEUMATIC TUBING/PIPING BACK TO THE PNEUMATIC PIPING MAIN AS REQUIRED.


KEYED NOTES:

- ① DISCONNECT AND REMOVE THE EXISTING HORIZONTAL RUN, HEATING WATER SUPPLY AND RETURN PIPING DOWNSTREAM OF THE EXISTING 2" HWS&R SHUT-OFF VALVE AS SHOWN INCLUDING ALL CONNECTIONS TO REMOVED VAV TERMINAL UNITS.
- ② DISCONNECT AND REMOVE THE EXISTING HORIZONTAL RUN, HEATING WATER SUPPLY AND RETURN PIPING BEING ROUTED TO THE EXISTING FIN TUBE RADIATION. CAP THE HWS&R PIPING AT THE POINT THE PIPING IS ROUTED VERTICALLY DOWN TO THE EXISTING FIN TUBE RADIATION AS REQUIRED AND RECONNECT AS SHOWN ON THE INSTALLATION PLANS.
- ③ DISCONNECT AND REMOVE THE EXISTING 2-WAY PNEUMATIC CONTROL VALVE SERVING THE FIN TUBE RADIATION LOCATED BEHIND THE EXISTING FIN TUBE ENCLOSURE AND REMOVE THE EXISTING PNEUMATIC TUBING/PIPING CONNECTED TO THE CONTROL VALVE BACK TO THE PNEUMATIC PIPING MAIN AS REQUIRED. RECONNECT THE EXISTING HEATING WATER PIPING ON EITHER SIDE OF THE REMOVED CONTROL VALVE AS REQUIRED. TEMPORARILY REMOVE THE EXISTING FIN TUBE ENCLOSURE AS REQUIRED FOR THE REMOVAL WORK AND REINSTALL FOLLOWING THE REMOVAL WORK.



100% DESIGN SUBMISSION

| | | | | | | | | | | |
|---------------------------|----------|--------------|--|----------------------|---|----------------------------|---------------------------|---------|-----------------|----------------------------------|
| | | CONSULTANTS: | | ARCHITECT/ENGINEERS: | <div><div><div><div>SAGE ENGINEERING ASSOCIATES, LLP</div><div>1211 WESTERN AVENUE ALBANY, NY 12203</div><div>(518)453-6091 FAX(518)453-6092</div></div><div>SEA PROJECT NO. 2217</div></div></div> | Drawing Title | Project Title | | Project Number | STRATTON VA MEDICAL CENTER |
| | | | | | | HVAC PIPING REMOVALS PLAN | VISION CLINIC RENOVATIONS | | 528A8-08-830 | |
| | | | | | | Approved: Project Director | Location | | Building Number | |
| | | | | | | | ALBANY, NEW YORK | | 1 | |
| | | | | | | | Date | Checked | Drawn | |
| | | | | | | | MAY 13, 2011 | LM | JWP | |
| | | | | | | | | | Drawing Number | |
| 100% SUBMISSION | 05/13/11 | | | | | | | | | |
| 95% SUBMISSION - REISSUED | 06/04/10 | | | | | | | | | |
| 95% SUBMISSION | 02/12/10 | | | | | | | | | |
| 60% SUBMISSION | 07/17/09 | | | | | | | | | |
| Revisions: | Date | | | | | | | | | |

 Department of Veterans Affairs