

Glazing to remain

Remove glazing

Existing wall to remain

Demo wall

Existing exit sign to remain, typ.

Ceiling grid to remain as indicated, replace ceiling tiles, typ.

Remove ceiling grid and acoustical ceiling tiles, typ.

Existing return diffuser, see MEP drawings

Existing supply diffuser, see MEP drawings

Existing exhaust register, see MEP drawings

1

Exit sign to remain, typ.

2

Relocate sign above new canopy, see exterior elevation, typ.

3

Existing canopy to remain, typ.

4

Existing canopy to remain. Replace existing lighting with T8 outdoor fixtures. See electrical, typ.

5

Remove soffit and light fixtures, see electrical, typ.

6

Soffit to remain, typ., light fixtures to be replaced.

7

Remove wall mounted HVAC equipment, see mechanical.

8

Upgrade all light fixtures from T12 to T8's, typ.

9

Salvage indicated exit signs for relocation.

10

Remove all ceiling tiles. Suspended grid to remain undamaged, typ.

See mechanical, electrical, and plumbing sheets for additional scope of demolition work, typ.

1

D-2.1

Reflected Ceiling Plan - Demolition

scale: 1/8" = 1'-0"

| Revisions | | |
|-----------|------|---------|
| No. | Date | Remarks |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Hernandez Consulting
ALBERT ARCHITECTURE

Allen&Hoshall
engineering since 1915

| Approved: | |
|-----------|-----------|
| Title | Signature |
| | |
| | |
| | |
| | |
| | |

| Drawing Title | |
|------------------------------------|--|
| Demolition- Reflected Ceiling Plan | |
| Approved: Service Engineer | |
| Approved: Service Director | |

| Project Title | |
|--|--------------------------------------|
| Southeast VA Health Care System (SLVHCS) A&E Design Urgent Care | |
| Building Number | |
| Location | 1601 Perdido Street, New Orleans, LA |

| | |
|--------------|------------------|
| Date | January 18, 2013 |
| Project No. | VA256-C-0231 |
| DRAWING NO. | D-2.1 |
| Drawn | S. Gonzalez |
| Checked | |
| Dwg. 3 OF 12 | |

Department of Veterans Affairs