



GENERAL NOTES:

1. ALL FIXTURES ARE TYPE "A1", UOI.
2. RE-INSTALL ALL EXISTING DEVICES, PA SPEAKERS, NURSE CALL DEVICES, ETC IN CEILINGS WHICH ARE BEING REPLACED.
3. ALL NEW OCCUPANCY SENSOR SWITCHES SHALL MATCH EXISTING IN SPACE.
4. ALL FIXTURES WITHIN THE CONSTRUCTION SPACE ARE TO BE REPLACED WITH NEW AS INDICATED.

REFERENCED NOTES:

1. EXISTING FIXTURES IN THIS ROOM/SPACE BEING REPLACED. CONNECT TO EXISTING CIRCUIT AND SWITCHING, UOI.
2. RECONNECT ALL EGRESS EMERGENCY LIGHTING TO EXISTING CIRCUIT FED FROM LIFE SAFETY PANEL "EL". FIXTURES ARE TO BE REPLACED AS INDICATED.
3. PROVIDE NEW RELAY AND CONNECT TO EXISTING TIME CLOCK.

FIXTURE MOUNTING		FIXTURE TYPE		LENS	FINISH
R-RECESSED	C-CASEWORK	F-FLUORESCENT	A-ACRYLIC	WH-WHITE	
RL-RECESSED LAY-IN	CH-CHAIN	I-INCANDESCENT	A12-ACRYLIC	BK-BLACK	
RF-RECESSED FLANGED	PL-POLE	Q-QUARTZ	#12 PATTERN	DB-DARK BRONZE	
S-SURFACE	W-WALL	MV-MERCURY VAPOR	PC-POLYCARBONATE	SBA-SELECTED BY	
P-PENDENT	B-BRACKET	MH-METAL HALIDE		ARCHITECT	
	U-UNIVERSAL	HPS-HIGH PRESSURE SODIUM		MS-MANUFACTURER'S STANDARD	

TYPE NO.	MANUF'R	CATALOG NO.	FIX. MTG.	FIX. TYPE	LENS	FIN.	LAMP NO. WATTS	VOLTS	COMMENTS
A1	LITHONIA	2RT5 14T5 MVOLT	R	F	A	MS	2 14	120/277	
A2	LITHONIA	2RT5 24T5HO MVOLT	R	F	A	MS	2 24	120/277	
B	LITHONIA	2SP8 4 32 MVOLT	R	F	A12	WH	2 32	120/277	
C	LITHONIA	VRI 132 PCL MVOLT	S	F	PC	MS	2 32	120/277	
D	LITHONIA	C 2 32 MVOLT	S	F	-	MS	2 32	120/277	
E1	LITHONIA	LQC 1R	U	LED	-	MS	- 1	120/277	
E2	LITHONIA	LQC 2R	U	LED	-	MS	- 1	120/277	
F	LITHONIA	REAL6C D6MW ESL 1500L 35K 277 LP6LN	U	LED	-	WH	- 18.8	277	

2 FIXTURE SCHEDULE
SCALE: N/A

1 LIGHTING
SCALE: 1/8" = 1'

Revisions

No.	Date	Remarks

Hernandez Consulting

ALBERT ARCHITECTURE

JBHM

ARCHITECTS, P.A.

Allen&Hoshall

engineering since 1915

Approved

Title

Signature

Building Title

ELECTRICAL - LIGHTING

Approved Service Engineer

Approved Service Director

Project Title

Southeast VA Health Care System (SLVHCS) A&E Design Urgent Care

Building Number

Checked MEB

Drawn

Location

1601 Perdido Street, New Orleans, LA

Date

JANUARY 18, 2013

Project No.

VA256-C-0231

Drawn

EL101

Imp. 1 OF 1

OFFICE OF FACILITIES

Department of Veterans Affairs