



GENERAL NOTES:

1) REFER TO SHEET E0.1 FOR GENERAL NOTES.

2) REFER TO SPECIFICATIONS.

3) PRIMARY ELECTRICAL SERVICE AS FOLLOWS:

A. CONTRACTOR

1. EXCAVATING, TRENCHING AND BACKFILLING FOR THE INSTALLATION OF CONDUIT.

2. TRANSFORMER PAD INSTALLED.

B. FP&L

1. PROVIDE PULL AND MAKE-UP CABLE INSTALLATION THROUGH UNDERGROUND SERVICE DUCT BANK.

2. PROVIDE TRANSFORMER.

HEX NOTES:

1) CONTRACTOR SHALL PROVIDE JUNCTION BOXES PRIOR TO ENTERING THE CONTACTOR 'LC-2' FOR TRANSITION OF LARGE HOME RUN CONDUCTORS TO #12 WIRING.

2) LIGHTING WIND SOCK PROVIDED BY ANOTHER DIV. OF WORK. PROVIDE 120V POWER AS REQUIRED. VERIFY EXACT LOCATION PRIOR TO ROUGH-IN.

Baker

Baker/Mellon Stuart Const. , Inc.
111 North Orange Avenue
Suite 625
Orlando, Florida 32801

KBJ

ARCHITECTS

KBJ Architects, Inc.
AAC00001
510 North Julia Street
Jacksonville, Florida 32202

Drawing Title SITE PLAN - ELECTRICAL		Project Title VA OUTPATIENT CLINIC BREVARD COUNTY	
Graphic Scale 0 12' 25' 50' 100' 150' SCALE: 1" = 50'-0"		Location BREVARD COUNTY, FLORIDA	
Approved: Area Project Manager		Drawn: MJR	Checked: CW/HP
Seal		Date 7-30-98	
Notes:			
Revisions			



Office of
Facilities
Management

Department of
Veterans Affairs

FINAL SUBMITTAL