


- KEYED NOTES:**
- ① HOT WATER FILTER, COORDINATE EXACT LOCATION WITH OWNER. FSI MODEL FSN 250.3 OR EQUIV. SEE DETAIL 1 ON M-103
- GENERAL NOTES:**
- 1. SCHEDULE 40 STEEL PIPING.
 - 2. GROOVED FITTINGS FOR PIPING 2-1/2" OR LARGER.
 - 3. FOAM INSULATE ON FILTER BODY 1" THICK. PIPING INSULATION AS PER SPECIFICATION.
 - 4. WILCOX VALVE FOR 500PSI FLOWMATE THROUGH FILTER ASSEMBLY.
- FILTER SPECIFICATIONS:**
- HOUSING: FSI MODEL FSN 250.3
- SYMBOLS**
- V— VALVE, SEE SPECIFICATIONS
- ABBREVIATIONS**
- POC POINT OF CONTACT

10TH FLOOR MECHANICAL ROOM PIPING PLAN

SCALE: 1/4" = 1'-0" (WHEN PLOTTED ON 30" X 42" PAPER)



CONSULTANTS:

ARCHITECT/ENGINEERS:

Revisions:	Date

Drawing Title	Project Title	Project Number
HEATING HOT WATER FILTER, 10TH FLOOR PLAN	INSTALL HEATING AND CHILLED WATER FILTRATION	528A-13-7-16
Approved Project Director	Location	Building Number
	VAMC SYRACUSE, N.Y.	1
Date	Checked	Drawn
11/9/2012	MA	DHA
DWG 3 of 5	MP-101	

