Create Campus Walking Path St. Cloud VA Health Care System Main Campus, St. Cloud, Minnesota CONTRACTOR PARKING AND MATERIAL STORAGE

GENERAL NOTES

All dimensions on drawings are approximate; Drawings are not to be scaled. It is the responsibility of the contractor to verify all field conditions and physical dimensions that influence the construction area.

It is recommended that contractors visit the proposed construction site prior to submitting their bids and they are encouraged to do so.

Contractor shall adhere strictly to State and Federal Occupational Safety and Health Administration (DSHA) Standards.

Contractor shall park only in the designated parking areas and are not to park on the lawn areas; the only exception is to load or unload supplies or equipment.

Contractor is responsible for the safeguarding of their tools and equipment. All tools and equipment are not to be left unattended and are to be secured at all times when the contractor is not present, or the construction site is not supervised by the contractor.

All VA property is to be safeguarded from damage. Any damaged VA property is to be restored to original condition prior to damage or replaced completely. This includes installation, labor, and procurement expenses.

Offsite disposal of the demolished items is the responsibility of the contractor.

All demolished material becomes the property and the responsibility of the contractor with the exception of specified items designated either in the plans or verbally requested by the COR to be retained by the VA.

Contractor must control demolition and construction dust from facility by erecting a dust barrier and ventilation with hepa filters. If venting to outside, the contractor will insure negative air pressure is maintained in encapsulated work area. When transporting debris, wet down sufficiently to prevent dust spreading.

If scaffolding is used, it must be used in accordance with (OSHA) regulations and is to be enclosed for the first eight feet above ground at end of each working day, until dismantled. Ladders must be removed and locked up at the end of each working day to prevent unauthorized persons from having access.

Clean all debris from construction site to the satisfaction of the CDR.

Contractor is responsible for erecting a barrier around work site to prevent patients, staff and visitors from entering construction site. This fence may be a plastic snow fence at open trench areas. All other areas require a metal chain-link fence be erected. Fencing to be 8' high, with top and bottom rail.

Provide vehicle/equipment swinging gate (lockable).

Provide swinging mandoor gate with emergency egress capabilities. Coordinate construction materials and location of fence with CDR.

Contractor is responsible for repairing and replacing any damaged lawn. The restoration will be performed by a landscape contractor that regularly does sodding as part of their business. All damaged lawn will be overcut by 6" or more to accomodate full width rolls of sod. Top soil to be tilled and graded to a smooth matching grade of undamaged lawn. Sod to be thoroughly saturated with water upon placement. The contractor is responsible for watering new sod until acceptance of established lawn restoration by the CDR.

Access to all buildings and parking areas must be maintained throughout the project.

Contractors are to coordinate all work with the Contracting Officers Representative.

SHEET INDEX

GENERAL: G1.0 COVER SHEET

C0.0 EXISTING SITE CONDITIONS

C1.0 OVERALL SITE LAYOUT PLAN AND SHEET INDEX

C2.0 PLAN AND PROFILE

C2.1 PLAN AND PROFILE

C2.2 PLAN AND PROFILE

C2.3 PLAN AND PROFILE C2.4 PLAN AND PROFILE

C2.5 PLAN AND PROFILE

C2.6 PLAN AND PROFILE

C2.7 PLAN AND PROFILE

C3.0 EROSION CONTROL PLAN

C3.1 EROSION CONTROL PLAN C3.2 EROSION CONTROL/SWPPP DETAILS

C4.0 DETAILS

C4.1 DETAILS

LANDSCAPE:

LA100 OVERALL LANDSCAPE PLAN LA101 LANDSCAPE PLAN DETAILS

LA102 LANDSCAPE PLAN DETAILS

LA103 LANDSCAPE DETAILS

LA104 LANDSCAPE DETAILS

ELECTRICAL:

E1.0 DRAWING INDEX, ABBREVIATIONS, SYMBOLS, NOTES AND DETAILS

E2.0 ELECTRICAL SITE PLAN

E3.0 POWER RISER DIAGRAM, DETAILS AND SCHEDULES

100% CD'S - FOR CONSTRUCTION



Date

VA FORM 08-6231

WALKING PATH

ALIGNMENT

(TYPICAL)



5

STAMP/SEAL:	
I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.	A
GINA M. DULLINGER REG. NO.	

Drawing Title COVER SHEET	Project Title CREA PATH
Approved: Project Director	Location VA MEDIO
	Date

Project Title CREATE CA	Project Number 02212002		
PATH	Building Number		
Location VA MEDICAL CENT	Drawing Number		
Date	Checked	Drawn	G1.0
10/16/2012	DJF	GMD	Dwg.1 of 24







