

FHCC PROJECT: 556-11-119

ROOM FINISH SCHEDULE										PLUNKETT RAYSICH ARCHITECTS, LLP
Project: AE SCIP for Building 6- James Lovell FHCC										Project No. 556-11-119
Room #	Room Name	Floor	Base	North	East	South	West	Ceiling	Type	Notes
007C	ELECTRICAL ROOM	CONC-1	-	-	-	-	-	-	-	-
100	STORAGE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
100A	STORAGE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
100B	STORAGE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
101	STORAGE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
101A	MALE LOCKER/RESTROOM	PT-5	PT-3	PT-1,2,4,6/PA-1	PT-1,2,4,6/PA-1	PT-1,2,4,6/PA-1	PT-1,2,4,6/PA-1	SUSP/GYP	AC- 2/PA-9	1,2,3,4
101B	FEMALE LOCKER/RESTROOM	PT-5	PT-3	PT-1,2,4,6/PA-1	PT-1,2,4,6/PA-1	PT-1,2,4,6/PA-1	PT-1,2,4,6/PA-1	SUSP/GYP	AC- 2/PA-9	1,2,3,4
102	DISH WASH	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
103	DISH STORAGE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
104	OFFICE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
105	MALE TOILET	PT-6	PT-3	PT-1,4/GT-1/PA-8	PT-1,4/GT-1/PA-8	PT-1,4/GT-1/PA-8	PT-1,4/GT-1/PA-8	SUSP	AC- 2	2
106	FEMALE TOILET	PT-6	PT-3	PT-1,4/GT-1/PA-8	PT-1,4/GT-1/PA-8	PT-1,4/GT-1/PA-8	PT-1,4/GT-1/PA-8	SUSP	AC- 2	2
107	DINING ROOM	PT-5,6,7,8,9/C-1	TRM-2	PA-5	PA-6,8/ST-1	PA-5/TRP-2	PA-5	SUSP/GYP	AC-3,4,5,6/LMC-1/PA-5	6,7,8,9,10,11,12,13,16,17,18
107A	COOK LINE	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 2	-
107B	SERVING LINE	QT-1	QT-2	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 2	5
108	J/C	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
109	STAIR	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	-
110	OFFICE SPACE	SV-1	RB-1	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
110A	PRODUCTION OFFICE	SV-1	RB-1	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
110B	TOILET	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
110C	COOK SUPERVISOR OFFICE	SV-1	RB-1	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
110D	STORAGE	SV-1	RB-1	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
111	J/C	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
112	KITCHEN	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
112A	UTENSIL WASH	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
112B	NEW COOK'S FREEZER	-	-	-	-	-	-	EXP	PA-3	-
112C	COOLER/FREEZER	-	-	-	-	-	-	EXP	PA-3	-
112D	NEW COOK'S FREEZER	-	-	-	-	-	-	EXP	PA-3	-
112E	INGREDIENT CONTROL	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
112F	COOLER	-	-	-	-	-	-	EXP	PA-3	-
114	POTENTIAL OFFICE SPACE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
114A	DAY DRY GOODS ROOM	QT-1	QT-2	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 2	-
114B	DRY STORAGE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
114C	STORAGE	QT-1	QT-2	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 2	-
115	SUPPLY/STORAGE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
116	HAC	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	-
117	STAIR	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	-
118	SUPERVISOR	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
119	SUPERVISOR	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
120	TELECOM	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	6
121	CALL CENTER	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	6
122	OFFICE	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
123	OFFICE	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-

FHCC PROJECT: 556-11-119

ROOM FINISH SCHEDULE										PLUNKETT RAYSICH ARCHITECTS, LLP
Project: AE SCIP for Building 6- James Lovell FHCC										Project No. 556-11-119
Room #	Room Name	Floor	Base	North	East	South	West	Ceiling	Type	Notes
124	OFFICE	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
126	OFFICE	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
127	OFFICE	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
128	OFFICE	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
129	OFFICE	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
131	TOILET	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
132	TOILET	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
133	BREAK ROOM	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
134	STORAGE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
135	CLOSET	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	-
136	CLOSET	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	-
137	CONFERENCE	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
137A	CLOSET	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	-
137B	CLOSET	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	-
138	CONFERENCE	EXTG	EXTG	PA-1	PA-1	PA-1	PA-1	SUSP	AC- 1	-
138A	CLOSET	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	-
138B	CLOSET	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	-
139	COPY	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
140	CONFERENCE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
141	BREAK ROOM	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
142	PASSAGE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
143	PASSAGE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
144	PASSAGE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 1	-
C100	CORRIDOR	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
C101	CORRIDOR	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
C102	CORRIDOR	PT-6,7,8	TRM-2	PA-5/TRP-2/MLAM-1	PA-5	PA-5/ST-1/MLAM-1	PA-5	SUSP/GYP	LMC-1/PA-8/WP-1	7,8,9,10,11,14,15,18
C103	CORRIDOR	EXTG/SV	EXTG/CT	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	6
C113	CART WASH	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-
C113A	CART STORAGE	EXTG	EXTG	EXTG	EXTG	EXTG	EXTG	SUSP	AC- 2	-

GENERAL NOTES:

- * ALL STEEL DOORS, HOLLOW METAL DOOR, WINDOW, AND SIDELITE FRAMES SHALL BE PAINTED PA-2, UNLESS OTHERWISE NOTED.
- * WOOD INTERIOR DOORS AT 107 DINING ROOM AND C102 CORRIDOR TO BE STAINED STN-2. ALL OTHER DOORS TO BE STAINED STN-1 TO MATCH EXISTING.
- * ALL LOUVERS, VENTS, AND GRILLES TO BE PAINTED TO MATCH ADJACENT WALL/CEILING COLOR.
- * ALL NEW AND EXISTING UNIT HEATER CABINETS WITHIN LIMITS OF CONSTRUCTION TO BE PAINTED TO MATCH ADJACENT WALL COLOR.
- * ALL CORNER GUARDS TO BE CG-1. REFER TO SHEET AS-201N AND AS-201S FOR LOCATIONS.
- * PROVIDE HORIZONTAL WINDOW BLINDS BL-1 AT ALL EXTERIOR WINDOWS WITHIN LIMITS OF CONSTRUCTION, UNLESS OTHERWISE NOTED.
- * ALL BULKHEADS AND SOFFITS TO BE PAINTED TO MATCH ADJACENT WALL COLOR, UNLESS OTHERWISE NOTED.
- * PROVIDE SLD-2 AT NEW WINDOW STOOL LOCATIONS.

FHCC PROJECT: 556-11-119

ROOM FINISH SCHEDULE							PLUNKETT RAYSICH ARCHITECTS, LLP			
Project: AE SCIP for Building 6- James Lovell FHCC							Project No. 556-11-119			
Room #	Room Name	Floor	Base	North	East	South	West	Ceiling	Type	Notes
<div>ROOM FINISH NOTES:</div> <div><div>1) PROVIDE TOILET PARTITIONS TP-1. REFER TO PLANS AND ELEVATIONS FOR LOCATIONS.</div><div>2) REFER TO ELEVATIONS ON SHEET AS-801 FOR TOILET ROOM WAINSCOT.</div><div>3) PROVIDE LOCKER LKR-1. REFER TO FLOOR PLANS AND ELEVATIONS FOR LOCATION.</div><div>4) PROVIDE SOLID SURFACE SLD-1 PANELS AT SHOWER STALL.</div><div>5) PROVIDE NEW CABINETRY TO MATCH EXISTING. CABINETS TO BE STAINED TO MATCH EXISTING SERVING LINE. COUNTERTOPS TO BE GRANITE ST-1 TO MATCH SERVING LINE. CONTRACTOR TO FIELD VERIFY EXISTING FINISHES AND SUBMIT SAMPLES TO FHCC FOR APPROVAL.</div><div>6) PATCH TO MATCH EXISTING, FLOOR, WALL, AND CEILING FINISHES AS NECESSARY, UNLESS OTHERWISE NOTED. VERIFY EXISTING FINSHES ON SITE AND SUBMIT SAMPLES TO INTERIOR DESIGNER/FHCC FOR APPROVAL.</div><div>7) REFER TO REFLECTED CEILING PLAN ON SHEET AS-301N FOR ACOUSTICAL CEILING LOCATIONS AND HEIGHTS.</div><div>8) REFER TO SHEET AS-201FP FOR FLOOR PATTTERN PLAN.</div><div>9) PROVIDE STONE VENEER ST-1 AT MONITOR INSET/FIREPLACE. RETURN ST-1 TO INTERIOR CORNERS AT MONITOR INSET AND FIREPLACE BUMP OUT WALLS.</div><div>10) PROVIDE WALL PROTECTION WP-1 AT COLUMN BASES WITH TRM-1 VERTICAL TRIM. PROVIDE MLAM-1 PANELS WITH TRM-1 VERTICAL TRIM ABOVE CHAIR RAIL. PROVIE TRM-2 AT BASE, CHAIRRAIL, AND TOP CAP.</div><div>11) PROVIDE TRANSLUCENT RESIN PANELS TRP-2 AT BORROWED AND DOOR LITES BETWEEN DINING ROOM 107 AND CORRIDOR C102. REFER TO SHEET AS-802 FOR ELEVATIONS. WOOD TRIM AND STOPS TO BE STAINED STN-2.</div><div>12) PROVIDE PT-9/GT-1 AT SOUTH FACE OF HALF HEIGHT PARTITION. PROVIDE PA-5 AT FACES OF HALF HIEIGHT PARTITIONS TO RECEIVE BOOTHS. PROVIDE TRP-1 PANELS ABOVE. WOOD TOP CAP AND STOPS TO BE STAINED STN-2. REFER TO SHEET AS-802 FOR ELEVATIONS.</div><div>13) FACE AND UNDERSIDE OF BULKHEAD TO BE PAINTED PA-5.</div><div>14) PROVIDE WP-1 FACE ON NEW DOORS FROM TRAM TO CORRIDOR C102. PROVIDE WP-1 AT CORIDOR FACING SIDE ONLY.</div><div>15) FACE AND UNDERSIDE OF CURVED SOFFIT TO BE PAINTED PA-8. PROVIDE WP-1 WRAP AT BULKHEADS.</div><div>16) PROVIDE WALL PROTECTION WP-1 AT FACE, SIDES, AND EXPOSED EDGES OF BANQUETTE SEATING. PROVIDE FABRIC F-1 AT SEAT AND FABRIC F-2 AT BACKREST CUSHIONS.</div><div>17) PROVIDE ACOUSTICAL CEILING TRIM AC-6 BETWEEN CEILINGS OF VARYING HEIGHTS. TRIM TO PAINTED TO MATCH ADJACENT CEILING TILE AC-3,4,OR 5.</div><div>18) HOLLOW METAL DOOR AND SIDELITE FRAMES TO BE PAINTED PA-11. FOR FRAMES IN CORRIDOR C102 PAINT CORRIDOR SIDE OF FRAME ONLY.</div></div>										