

## CONSULTANTS:

## ARCHITECT/ENGINEERS:



PAULI ENGINEERING, INC.  
2501 N. SHAW AVE., #121, FRESNO, CA 93711  
PH: (559)237-4408 - FAX: (559)237-4404  
E-MAIL: pauliengineering@abcglobal.net  
www.pauliengineering.com

# TREE REMOVAL AND DEMOLITION PLAN

## SITE IRRIGATION AND LANDSCAPE IMPROVEMENTS

**Location**  
2615 E. Clinton Ave, Fresno

Date	Checked	Drawn
1/3/2013		

Check EC

**Drawn**


Project Number  
570-12-200

CAMPUS

CD100  
of —  
Dwa

of —  
Dwa

**Office of  
Construction  
and Facilities  
Management**



## EXISTING TREES

- |                       |     |                  |     |                   |     |              |     |               |     |
|-----------------------|-----|------------------|-----|-------------------|-----|--------------|-----|---------------|-----|
| A = SYCAMORE          | (A) | D = EUCALYPTUS   | (D) | G = BRADFORD PEAR | (G) | J = ZELKOVA  | (J) | M = XYLOSMIA  | (M) |
| B = CHINESE ELM       | (B) | E = LOCUST TREE  | (E) | H = CAROB TREE    | (H) | K = MAGNOLIA | (K) | N = ALERPO    | (N) |
| C = CHINESE PISTACHIO | (C) | F = CREPE MYRTAL | (F) | I = REDWOOD       | (I) | L = DEODORA  | (L) | P = (E) TREES | (P) |

(E) TREE TO BE REMOVED

NOTE: REMOVE AND DISPOSE TREE, INC. LARGER THAN 2" DIAMETER, BACK SPACE LEFT BY THE TREE WITH AND RECOMPACT AT 90% OF MAX. ASTM D1557

NOTE:  
REMOVE AND DISPOSE TREE, INCLUDING STUMP AND ROOTS  
LARGER THAN 2" DIAMETER. BACKFILL AND LEVEL TO GRADE  
SPACE LEFT BY THE TREE WITH ACCEPTABLE FILL MATERIAL  
AND RECOMPACT AT 90% OF MAXIMUM COMPACTION AS PER  
ASTM D1557

## REFERENCES

- PROJECT #570-12-571, AREA UNDER DESIGN BY OTHERS

