



GENERAL NOTES:

1. DIMENSION IS SHOWN AS FOR USE IN PRICING CRASH RAIL INSTALLED ON THE CONNECTING CORRIDOR WALL.
2. INSTALL CRASH RAIL ON BOTH SIDES OF THE CORRIDOR, SPACED 6 INCHES FROM ANY DOOR FRAME OR CORNER CONDITION.
3. REFER TO SCOPE OF WORK AND PROJECT SPECIFICATIONS FOR ADDITIONAL INFORMATION.
4. ALL HATCHED AREAS SHALL REQUIRE ABATEMENT OF ASBESTOS TILE AND INSTALLATION OF NEW EPOXY FLOOR SYSTEM.
5. THE RED LINE INDICATES SECTION OF CORRIDOR THAT WILL RECEIVE NEW CRASH RAIL. USE SCOPE OF WORK, PROJECT SPECIFICATIONS AND, DRAWINGS WP-1 THROUGH WP-10 FOR ALL INFORMATION RELATED TO CRASH RAILS.

DRAWING NOTES

- | DRAWING NOTES | | |
|---------------|--|--------|
| 1. | REPLACE MOTION ACTIVATED DOUBLE DOOR, 96"W x 91"H PER SPECIFICATIONS AND SCOPE OF WORK. AND REPLACE SEPARATE STEEL DOOR FRAME. | REMOVE |
| 2. | REPLACE MOTION ACTIVATED DOUBLE DOOR, 96"W x 91"H PER SPECIFICATIONS AND SCOPE OF WORK. AND REPLACE SEPARATE STEEL DOOR FRAME. | REMOVE |
| 3. | REPLACE 3'8"W x 6'8"H WOOD DOOR PER SPECIFICATIONS AND SCOPE OF WORK. | |
| 4. | REPLACE MOTION ACTIVATED DOUBLE DOOR, 96"W x 91"H PER SPECIFICATIONS AND SCOPE OF WORK | |
| 5. | REPLACE MOTION ACTIVATED DOUBLE DOOR, 96"W x 91"H PER SPECIFICATIONS AND SCOPE OF WORK | |

[illegible][illegible]

--	--

Drawing Scale:	1:100
Drawing Start Date:	
Drawing Finish Date:	
Drawing Approved:	

	Approved: Chief, Facilities and Engineering:
	Approved: Associate Chief for Maintenance And Operations, Perry Point:

<p>Drawing Title:</p> <p>CONNECTING CORRIDOR WORK ITEMS</p>
<p>Approved: Associate Director for Operations:</p>
<p>Approved: Director, Medical Center:</p>

Project Title: HALLS AND WALLS FY-13		
Building No:	Checked: MOH	Drawn: MOH
Location: VAMHCS Perry Point MD		

Date: 1/5/2013

Project No: 512A5-13-305

DRAWING NO:

A — 1

Dwg. 2 Of 2