

SCOPE OF WORK

RELOCATE FLAMMABLES STORAGE BUILDING FORT CUSTER NATIONAL CEMETERY, AUGUSTA, MICHIGAN 49012

- A. The Contractor: Shall furnish all labor, material, tools, equipment, and supervision required to demolish the existing pavement and CMU walls of the materials storage areas to proper depth. The contractor shall also install a new concrete slab, concrete footings and walls, prepare sub-base, place reinforcing steel, place and finish new concrete pavement and bulk storage bin walls as described herein.
- B. The Contractor: Shall also furnish all labor, materials, tools, equipment and supervision required to relocate the existing Flammable Storage Building and install new electrical service to the relocated Flammables storage building in accordance with all current and applicable NEC codes and regulations and per applicable local state and federal regulations.
- B. The Work: The Work shall include, but shall not be limited to the following (not necessarily in the order indicated):
 - 1. Contractor shall procure and install all necessary materials to provide new concrete bulk storage bin and concrete pavement in the maintenance yard as indicated on the project drawings and specifications. The installation shall include excavation for new concrete footings and subgrade preparation, placement of forms and steel reinforcing, and placement and finishing 4000 psi concrete for new concrete pavement and bulk storage bin per accompanying drawings and specifications.
 - 2. Relocate the existing flammable storage building. Coordinate exact placement location with the COR.
 - 3. Procure and install all required electrical conduits, fittings, breakers, wire, and other miscellaneous items as required to provide a new electrical service to the relocated flammables storage building in accordance with all current and applicable NEC codes and regulations and per applicable local state and federal regulations.
 - 4. Haul away & dump debris and waste to an approved disposal site.
 - 5. Thoroughly clean up the work area at the end of each day's work, and at completion of the project. Leave premises clean and free of waste, scrap, used equipment, or other material intentionally or incidentally delivered to the site by Contractor or Contractor's personnel.
- C. Time of Completion: The project shall be completed within 30 calendar days after notice to proceed.
- D. Contractor Quality Control: The Job Site Superintendent will: a) review and approve submittals, b) inspect the quality of work performed, and c) certify the completed work for payment and other purposes.
- F. Availability/Constraints of Site: See attachments: Specification Sections 01 00 00 General Requirements, 01 33 23 Shop Drawings, Product Data and Samples, 01 45 29 Testing Laboratory Services, 31 20 11 Earth Moving, 03 30 53 Cast-in-place Concrete, 32 05 23, Cement & Concrete for Exterior Improvements and *"Fort Custer National Cemetery - Additional Information and Requirements."*
- G. Submittals After Award: Submit samples and shop drawings per specifications.
- H. Plans/details: Cover Sheet, X-1; Site Plans, L-1; and Details, L-2, and Electrical Plan, E-1.
- I. POC: The Contracting Officer's Representative (COR) for this project is: Kenneth Haines.
- J. Project completion: The project site shall be protected and/or restored to a condition equal to that existing prior to the commencement of work.

END OF SCOPE OF WORK