Department Of Veterans Affairs

FORT SILL NATIONAL CEMETERY

ELGIN, OKLAHOMA

REPLACE IRRIGATION CONTROLLERS

PROJECT 920-13-102

GENERAL NOTES:

1. ALL CONSTRUCTION WITHIN THE NATIONAL CEMETERY SHALL BE CONDUCTED WITH THE EMPHASIS ON PROPER CEMETERY ETIQUETTE AS THIS IS AN ACTIVE CEMETERY. NO DISRESPECTFUL ACTIVITY WILL BE TOLERATED.
2. COORDINATE ALL CONSTRUCTION ACTIVITIES WITH THE CEMETERY DIRECTOR TO AVOID CONFLICTS AND DISRUPTIONS OF SCHEDULED CEREMONIES AND DAILY CEMETERY OPERATIONS. SEQUENCE WORK AS NECESSARY TO ENSURE DAILY CEMETERY OPERATIONS REMAIN UNINTERRUPTED DURING CONSTRUCTION OPERATIONS.
3. CONTRACTOR SHALL PROVIDE AND MAINTAIN PROPER SIGNS, BARRICADES, CONES, AND FENCES TO PROPERLY PROTECT THE PUBLIC AND CEMETERY STAFF FROM INJURY. WORK AREAS SHALL BE BARRICADED OFF DURING NON-WORKING HOURS AND WHEN THERE IS NO ACTIVE CONSTRUCTION AT THE SITE.
4. THE CONTRACTOR SHALL PROVIDE CONSTRUCTION SIGNAGE AND CONES AT THE LIMITS OF ALL PAVEMENT AND SIDEWALK WORK AREAS SHOWING 'DETOUR' AND POINTING VISITOR TRAFFIC AROUND THE CONSTRUCTION ZONE(S). ONE LANE OF TRAFFIC SHALL BE MAINTAINED AT ALL TIMES.
5. ANY DAMAGE INCURRED TO EXISTING UTILITIES, IRRIGATION SYSTEM COMPONENTS, INSIDE AND OUTSIDE THE LIMITS OF WORK DUE TO CONTRACT OPERATIONS INCLUDING DAMAGE TO PAVEMENT, CURB AND GUTTER, SIDEWALKS AND OTHER STRUCTURES BY THE CONTRACTOR SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE GOVERNMENT. IF ANY EXISTING UTILITIES, UTILITY STRUCTURES, OR IRRIGATION SYSTEM COMPONENTS ARE UNCOVERED OR ENCOUNTERED DURING CONSTRUCTION, THEY SHALL BE SAFEGUARDED, PROTECTED FROM DAMAGE, AND SUPPORTED AS NECESSARY.
6. ALL AREAS ADJACENT TO THE SITE SHALL BE MAINTAINED IN A CLEAN CONDITION, MUD AND DUST FREE AT ALL TIMES. CONSTRUCTION OPERATIONS SHALL BE CONDUCTED IN SUCH A WAY AS TO PREVENT TRACKING OF MUD OR SOIL ONTO PUBLIC THOROUGHFARES. AT THE END OF EACH DAY THE CONTRACTOR SHALL CLEAN UP ALL MUD OR SOIL WHICH HAS BEEN TRACKED ON TO CEMETERY AND PUBLIC STREETS.
7. AREAS OUTSIDE OF THE CONSTRUCTION LIMITS IMPACTED BY OPERATIONS OF THE CONTRACTOR SHALL BE RETURNED TO THE STATE IT WAS FOUND PRIOR TO NEW CONSTRUCTION, EXCEPT WHERE NEW WORK IS SHOWN.
8. ALL TREES SHALL BE PROTECTED FROM DAMAGE TO TRUNKS, BRANCHES AND ROOTS.
9. ALL DEBRIS, EXCESS SOIL, CONCRETE, ASPHALT, ETC. SHALL BE REMOVED OFF CEMETERY PROPERTY AND PROPERLY DISPOSED OF AT AN APPROVED WASTE DISPOSAL SITE.
10. THOROUGHLY CLEAN UP THE WORK AREA AT THE END OF EACH DAY'S WORK, AND AT COMPLETION OF THE PROJECT. LEAVE PREMISES CLEAN AND FREE OF WASTE, SCRAP, USED EQUIPMENT, OR OTHER MATERIAL INTENTIONALLY OR INCIDENTALLY DELIVERED TO THE SITE BY CONTRACTOR OR CONTRACTOR'S PERSONNEL.
11. PROVIDE SMOOTH VERTICAL CURVES THROUGH HIGH AND LOW POINTS. PROVIDE UNIFORM SLOPES BETWEEN NEW AND EXISTING GRADES. AVOID RIDGES AND DEPRESSIONS.

NOTE: IT IS THE CONTRACTORS RESPONSIBILITY TO MAKE A SITE VISIT TO DEVELOP A FULL AND COMPLETE UNDERSTANDING OF THE CONTRACT SCOPE OF WORK; TO OBTAIN ALL MEASUREMENTS TO DETERMINE QUANTITIES OF THE EXISTING ASPHALT SIDEWALK TO BE DEMOLISHED AND EXISTING SUB-BASE AND OVERBURDEN TO BE EXCAVATED AND PROPERLY DISPOSED OF FROM THE CEMETERY; TO OBTAIN ALL MEASUREMENTS AND DETERMINE QUANTITIES OF MATERIALS, LABOR AND EQUIPMENT REQUIRED TO INSTALL A NEW CONCRETE SIDEWALK PER PROJECT DRAWINGS AND SPECIFICATIONS.

SHEET INDEX:

X - 1	COVER SHEET
D - 1	DEMOLITION SITE PLAN
L - 1	IRRIGATION CONTROLLERS SITE PLAN



PROJECT LOCATION

Revisions	Date

NATIONAL CEMETERY ADMINISTRATION

Drawing Title: **COVER SHEET & SHEET INDEX**	Project Title: **REPLACE IRRIGATION CONTROLLERS**		Date: **8/3/12**
Approved: Division Chief	Building Number: **-----**	Checked	Drawn: **CFC**
Approved: Service Director	Location: **FORT SILL NATIONAL CEMETERY**		Project No.: **920-13-102**
			DRAWING NO.: **X-1** Dwg. **1** Of **3**