

SHEET NOTES

EXPOSE EXISTING UTILITIES

Where potential grade and alignment conflicts might occur with existing utilities, the Contractor shall expose utilities or structures sufficiently in advance of laying pipe for the design engineer to verify the vertical and horizontal effect on the new construction. Any discrepancy with the plans shall be coordinated with the Dayton V.A. to ensure that there are no construction or conflict issues associate with said discrepancy. The cost of this work shall be included in the unit price bid for the various improvement items if a specific item is not provided in the estimate of quantities.


CAUTION

O.S.H.A. Clearance requirements to be maintained during construction between equipment and overhead utility lines.

PLAN LEGEND

See "Plan Legend" on Sheet GS0-03 denoting symbols and linetypes for Existing Conditions, New Work, Sediment & Erosion Control, and Abbreviations.


GRAPHIC SCALE



1 inch = 60 feet

PROJECT No. 4
ALONG OHIO AVE. FROM PENNSYLVANIA AVE. TO DELAWARE AVE.

GRAPHIC SCALE



1 inch = 60 feet

PROJECT No. 4
WEST OF OHIO AVE. FROM DELAWARE AVE. TO IOWA AVE.

DESIGNER/ENGINEER DPD
CAD OPERATOR DCH
QA/QC/CHECKER RMA

100% CD Submittal

01/29/2013

EMH&T
Evans, Mechwart, Hambleton & Tilton, Inc.
Engineers • Surveyors • Planners • Scientists
5500 New Albany Road, Columbus, OH 43054
Phone: 614.775.4500 Toll Free: 888.775.3648

Dynamis Engineering Ltd.
emht.com



Ryan M. Andrews
Professional Seal

Revised By:

Drawing Title

PROJECT No. 4:
OHIO AVE. - NEW JERSEY AVE. -
PENNSYLVANIA AVE. AREA IMPROVEMENT

Project Title

SANITARY SEWER REHABILITATION

Date

01/29/2013

Project No.

552-13-309

Drawing No.

GS1-05

Approved: Project Manager

Chris Moorhead

Approved: Service Chief

Mark Permelia

Building Number

N/A

Checked


RMA

Drawn

DCH

Location 4100 WEST THIRD STREET

DAYTON, OH 45428

Department of
Veterans Affairs



V/A

SHEET NOTES

EXPOSE EXISTING UTILITIES
Where potential grade and alignment conflicts might occur with existing utilities, the Contractor shall expose utilities or structures sufficiently in advance of laying pipe for the design engineer to verify the vertical and horizontal effect on the new construction. Any discrepancy with the plans shall be coordinated with the Dayton V.A. to ensure that there are no construction or conflict issues associate with said discrepancy. The cost of this work shall be included in the unit price bid for the various improvement items if a specific item is not provided in the estimate of quantities.

CAUTION
O.S.H.A. Clearance requirements to be maintained during construction between equipment and overhead utility lines.

PLAN LEGEND
See "Plan Legend" on Sheet GS0-03 denoting symbols and linetypes for Existing Conditions, New Work, Sediment & Erosion Control, and Abbreviations.



DESIGNER/ENGINEER DPD
CAD OPERATOR DCH
QA/QC/CHECKER RMA

100% CD Submittal

01/29/2013



Evans, Mechwart, Hambleton & Tilton, Inc.
Engineers • Surveyors • Planners • Scientists
5500 New Albany Road, Columbus, OH 43054
Phone: 614.775.4500 Toll Free: 888.775.3648

emht.com
Dynamy Engineering Ltd.



Professional Seal

Revised By:

Drawing Title
PROJECT No. 6:
PENN. AVE. - WISCONSIN AVE. AREA IMPROVEMENT
PROJECT No. 7:
BLDG. 410 - BLDG. 412 AREA IMPROVEMENT

Approved: Project Manager
Chris Moorhead

Approved: Service Chief
Mark Permelia

Project Title
SANITARY SEWER REHABILITATION

Building Number
N/A

Checked
RMA

Drawn
DCH


Location 4100 WEST THIRD STREET
DAYTON, OH 45428

Date
01/29/2013

Project No.
552-13-309

Drawing No.

GS1-06



Department of
Veterans Affairs
VA


SHEET NOTES

1. EXISTING STRUCTURE TO BE ABANDONED (TBA)
Remove structure to a minimum of one foot below finished grade, seal existing pipes with concrete stoppers or masonry, backfill with topsoil, seed and mulch.


EXPOSE EXISTING UTILITIES
Where potential grade and alignment conflicts might occur with existing utilities, the Contractor shall expose utilities or structures sufficiently in advance of laying pipe for the design engineer to verify the vertical and horizontal effect on the new construction. Any discrepancy with the plans shall be coordinated with the Dayton V.A. to ensure that there are no construction or conflict issues associate with said discrepancy. The cost of this work shall be included in the unit price bid for the various improvement items if a specific item is not provided in the estimate of quantities.

CAUTION
O.S.H.A. Clearance requirements to be maintained during construction between equipment and overhead utility lines.

PLAN LEGEND
See "Plan Legend" on Sheet GS0-03 denoting symbols and linetypes for Existing Conditions, New Work, Sediment & Erosion Control, and Abbreviations.



PROJECT No. 8
BLDG. 220 - BLDG. 305 AREA IMPROVEMENT



PROJECT No. 9
HOSPITAL AREA IMPROVEMENT

DESIGNER/ENGINEER	DPD
CAD OPERATOR	DCH
QA/QC/CHECKER	RMA

100% CD Submittal

01/29/2013



Evans, Mechwart, Hambleton & Tilton, Inc.
Engineers • Surveyors • Planners • Scientists
5500 New Albany Road, Columbus, OH 43054
Phone: 614.775.4500 Toll Free: 888.775.3648

emht.com

Dynamix Engineering Ltd.



Professional Seal

Revised By:

Drawing Title
PROJECT No. 8:
BLDG. 220 & BLDG. 305 AREA IMPROVEMENT
PROJECT No. 9:
HOSPITAL AREA IMPROVEMENT

Approved: Project Manager
Chris Moorhead

Approved: Service Chief
Mark Permelia

Project Title
SANITARY SEWER REHABILITATION

Building Number
N/A

Checked
RMA

Drawn
DCH


Location 4100 WEST THIRD STREET
DAYTON, OH 45428

Date
01/29/2013

Project No.
552-13-309










Drawing No.

GS1-07



Department of
Veterans Affairs

VA



* Item numbers refer to ODOT 2010 Construction and Material Specifications.

DESIGNER/ENGINEER DPD
CAD OPERATOR DCH
QA/QC CHECKER RMA

100% CD Submittal 01/29/2013

EMH&T
Evans, Mechwart, Hambleton & Tilton, Inc.
Engineers • Surveyors • Planners • Scientists
5500 New Albany Road, Columbus, OH 43054
Phone: 614.775.4500 Toll Free: 888.775.3648

emht.com
Dynamac Engineering Ltd.

STATE OF OHIO
RYAN M. ANDREWS
70263
REGISTERED PROFESSIONAL ENGINEER

Professional Seal

Revised By:

Drawing Title
PROJECT DETAILS

Approved: Project Manager
Chris Moorhead

Approved: Service Chief
Mark Permelia

Project Title
SANITARY SEWER REHABILITATION

Building Number
N/A

Checked
RMA

Drawn
DCH

Location 4100 WEST THIRD STREET
DAYTON, OH 45428


Date
01/29/2013

Project No.
552-13-309

Drawing No.
GS2-01

VAMC, DAYTON

Department of
Veterans Affairs



DETAIL NOTES

GENERAL
With normal soil and site conditions, this standard precast manhole may be used for any required manhole depth. Cast and assemble sections of the precast manhole with either all tongue or all groove ends up. Lift holes may be provided in each section for handling. Leave handling device for the flat slab in place.

TOP
Provide a flat slab for this section unless an eccentric cone is specified.

TRANSITION (OR REDUCER)
This section can be either eccentric cone or flat slab.

BASE
Manhole No. 3 is shown with a monolithic floor and riser which may be cast in one or two operations. A permissible alternate is to cast and ship the floor and barrel separately. Provide openings for inlet and outlet pipes, either when the unit is cast or later, to meet project requirements. Bottom channels may be formed of concrete, precast in the base or field constructed.

RISER SECTIONS
Openings for 18" and smaller inlet pipes may be either prefabricated or cut in the field provided the sides of the pipe at the springline do not project into the manhole.

CONNECTIONS
Connections between precast manhole sections and pipes on sanitary sewers may be sealed with resilient connectors conforming to ASTM C 923.

JOINT SEAL
Furnish resilient seal between precast manhole sections on sanitary sewers and flexible gasket joints per ODOT CMS 706.11.



OPENINGS
The maximum pipe opening is the O.D. of the pipe being supplied plus 2" when fabricated or field cut. Fill any voids per ODOT CMS 601.

MATERIALS
Provide materials for bases and other precast sections, including reinforcement not specified here, that meet the requirements of CMS 706.13.

TOP SLAB REBAR
Use epoxy coated reinforcing steel within the top slab.

LEGEND

1 Reconstruction to grade only. Approved materials are kept on file by the Office of Materials Management.



U:\20120980\Drawings\04\Sheets\20120980_ProjectDetails.dwg Last Saved By: dhill, 1/29/2013 9:38 AM Last Printed By: Hill, Dan, 1/29/2013 10:21 AM
1 Ref: 20120980-03-TTL-N.dwg

DESIGNER/ENGINEER	DPD
CAD OPERATOR	DCH
QA/QC/CHECKER	RMA
100% CD Submittal	01/29/2013
Revisions	Date

EMH&T
Evans, Mechwart, Hambleton & Tilton, Inc.
Engineers • Surveyors • Planners • Scientists
5500 New Albany Road, Columbus, OH 43054
Phone: 614.775.4500 Toll Free: 888.775.3648
emht.com
DynamicEngineering Ltd.

STATE OF OHIO
RYAN M. ANDREWS
70263
REGISTERED PROFESSIONAL ENGINEER

Ryan M. Andrews
Professional Seal

Revised By:	---



Drawing Title	PROJECT DETAILS
Approved: Project Manager	Chris Moorhead
Approved: Service Chief	Mark Permelia

Project Title	SANITARY SEWER REHABILITATION
Building Number	N/A
Location	4100 WEST THIRD STREET DAYTON, OH 45428

Date	01/29/2013
Project No.	552-13-309
Drawing No.	GS2-02

VAMC, DAYTON

Department of Veterans Affairs



LEGEND			
EXISTING			
STM	STM	STM	Storm Sewer
SAN	SAN	SAN	Sanitary Sewer
WM	WM	WM	Water Main
UGL	UGL	UGL	Underground Lighting
			Light Pole
			Manhole
			Catch Basin
			Curb
NEW WORK			
UD	UD	UD	Storm Sewer Underdrain
			Sanitary Sewer
			Spring Drain
			Catch Basin
			Curb

GENERAL NOTES

1. Spring drain location shown for bidding purposes. Actual location to be confirmed in the field prior to construction.
2. Verify location and elevation of all nearby utilities prior to construction. Verify elevation of existing catch basin and storm sewer pipes at connection point. Report all information to the Engineer prior to submitting shop drawings.
3. All utilities shown are based on information gathered from Dayton VA utility maps and field observations. Contact COTR and OUPS to located all utilities prior to beginning work.
4. Protect all existing utilities to remain. Maintain flow and service in all utilities throughout the duration of construction.
5. If a utility shut-down is required, notify COTR in writing 2 weeks prior to beginning work. Shut down must be approved by COTR prior to performing work.
6. Protect all site features to remain. Repair any damage at no additional cost to COTR.
7. Remove concrete curb to nearest joint beyond the limits of demolition. Sawcut curbs full depth in neat straight lines.
8. Protect survey control during construction. Provide additional control as necessary to perform construction operation.
9. Maintain at least one lane of traffic on New York Avenue during construction. Maintain traffic to access drive at all times during construction.
10. Where potential grade conflicts might occur with existing utilities and locations noted thus, **EXPOSE** uncover existing utilities sufficiently in advance of ordering materials and laying pipe or duct and provide the Engineer the location and elevation of said utility so the Engineer can determine if adjustments are necessary.
11. Elevations shown are based upon Montgomery County Auditor's aerial topography and are approximate. Contractor to verify all elevations prior to ordering materials and provide elevation information to Engineer for plan adjustments, if necessary.

CODED NOTES

- ① Remove curb as required for connection to existing storm catch basin. Replace curb per detail B, sheet GS2-04. Provide 1/2" preformed expansion joint filler where new curb abuts existing. Provide dowel connection to existing curb per detail D, sheet GS2-04.
- ② Limits of disturbance. Strip topsoil, reshape area to drain to new catch basin structure (max. 6H:1V slope). Replace topsoil and seed and mulch all disturbed areas. Provide class 1 lawn mixture per ODOT item 659. Refer to Detail A, sheet GS2-04.
- ③ Provide spring drains with 6" underdrain per Detail A, sheet GS2-04.
- ④ Protect existing light pole during construction. Expose light circuit prior to construction of storm sewer and underdrains. Relocated lighting circuit as necessary to facilitate construction of catch basin.
- ⑤ Install Dandy Bag (or equal) per detail C, sheet GS2-04, on catch basin.
- ⑥ Install silt fence behind back of curb in area of disturbance per Detail E, sheet GS2-04.



DESIGNER/ENGINEER	DPD
CAD OPERATOR	DCH
QA/QC/CHECKER	RMA

100% CD Submittal	01/29/2013
Revisions	Date

EMH&T
Evans, Mechwart, Hambleton & Tilton, Inc.
Engineers • Surveyors • Planners • Scientists
5500 New Albany Road, Columbus, OH 43054
Phone: 614.775.4500 Toll Free: 888.775.3648
emht.com
Dynamix Engineering Ltd.


STATE OF OHIO
RYAN M. ANDREWS
70263
REGISTERED PROFESSIONAL ENGINEER
Ryan M. Andrews
Professional Seal

Revised By:	




Drawing Title DRAINAGE IMPROVEMENT PLAN
Approved: Project Manager Chris Moorhead
Approved: Service Chief Mark Permelia

Project Title		
SANITARY SEWER REHABILITATION		
Building Number	Checked	Drawn
N/A	RMA	DCH
Location		
4100 WEST THIRD STREET DAYTON, OH 45428		

Date 01/29/2013
Project No. 552-13-309
Drawing No. GS2-03



VA Department of Veterans Affairs




- NOTES**
1. All exposed surfaces of Concrete Curb shall have a broom finish, unless placed by a curb machine.
 2. For replacement work, the curb shall be removed at an existing joint or no closer than 5' from and existing joint.
 3. Curb radius to match existing curb radius.
 4. Curb elevations to match roadway elevation, vary height if necessary to match existing curbs at connection.
 5. If existing underdrain encountered, protect during construction. Maintain drainage within underdrain during construction.

(B) DETAIL STRAIGHT 18" CURB (NO SCALE)

- NOTES**
1. Provide one ODOT 2-2B CB per ODOT Item 604.
 2. Elevations shown are based upon Montgomery County Auditor's aerial topography and are approximate. Contractor to verify all elevations prior to ordering materials and provide elevation information to Engineer for plan adjustments, if necessary, prior to ordering materials.

(A) DETAIL SPRING DRAIN PER ODOT STANDARD DRAWING DM 1.1 (MODIFIED) (NO SCALE)



(D) DETAIL CURB REPLACEMENT (NO SCALE)

Installation


1. Stand grate on end.
2. Place dandy bag over grate.
3. Roll grate over so that open end is up.
4. Pull up slack.
5. Tuck flap in.
6. Be sure end of grate is completely covered by flap or dandy bag will not fit properly.
7. Holding handles, carefully place dandy bag with grate inserted into catch basin frame so that red dot on the top of the dandy bag is visible.

Maintenance


1. With a stiff bristle broom or square point shovel remove silt & other debris off surface after each event.

Note

1. Frye Flow Systems Inlet Sedimentation Assembly May be Used as an Alternate.



(C) DETAIL DANDY/SEDIMENT FILTER BAG (NO SCALE)



(E) DETAIL SILT FENCE (NO SCALE)

1. The Height of A Silt Fence shall not Exceed 36 Inches (Higher Fences May Impound Volumes of Water Sufficient to Cause Failure of the Structure).
2. The Filter Fabric shall be Purchased in a Continuous Roll Cut to the Length of the Barrier to Avoid the Use of Joints. When Joints are Necessary, Filter Cloth shall be Spliced Together Only at a Support Post, with a Minimum of a 6-inch Overlap, and Securely Sealed.
3. Posts shall be Spaced a Maximum of 10 Feet apart at the Barrier Location and Driven Securely Into the Ground (Minimum Of 12 Inches).
4. A Trench shall be Excavated Approximately 6 Inches Wide and 6 Inches Deep Along the Line of Posts and Upslope from the Barrier.
5. The Filter Fabric shall be Stapled or Wired to the Fence, And 8-inches of the Fabric shall be Extended into the Trench. The Fabric shall not Extend More than 36 Inches above the Original Ground Surface. Filter Fabric shall not be Stapled to Existing Trees.
6. The Trench shall be Backfilled and Soil Compacted Over the Filter Fabric.
7. Silt Fences shall be Removed when they have Served their Useful Purpose, but not Before the Upslope Area has been Permanently Stabilized.

Maintenance:

Silt Fences and Filter Barriers shall be Inspected Immediately After Each Rainfall and at Least Daily During Prolonged Rainfall. Any Required Repairs shall be Made Immediately.

Should the Fabric on a Silt Fence or Filter Barrier Decompose or Become Ineffective Prior to the End of the Expected Usable Life and the Barrier is Still Necessary, the Fabric Shall be Replaced Promptly.

Sediment Deposits Should be Removed After Each Storm Event. They must be Removed when Deposits Reach Approximately One-half the Height of the Barrier.

Any Sediment Deposits Remaining in Place After the Silt Fence or Filter Barrier is no Longer Required shall be Dressed to Conform with the Existing Grade, Prepared and Seeded.

DESIGNER/ENGINEER _OPD
CAD OPERATOR _DCH
QA/QC/CHECKER _RWA

100% CD Submittal

01/29/2013

EMH&T

Evans, Mechwart, Hambleton & Tilton, Inc.
Engineers • Surveyors • Planners • Scientists
5500 New Albany Road, Columbus, OH 43054
Phone: 614.775.4500 Toll Free: 888.775.3648

emht.com
Dynamy Engineering Ltd.

STATE OF OHIO
RYAN M. ANDREWS
70263
REGISTERED
PROFESSIONAL ENGINEER

Ryan Andrews
Professional Seal

Revised By:

Drawing Title
DRAINAGE IMPROVEMENT PLAN
DETAILS

Approved: Project Manager
Chris Moorhead

Approved: Service Chief
Mark Permelia

Project Title
SANITARY SEWER REHABILITATION

Building Number
N/A

Checked
RMA


Drawn
DCH

Location 4100 WEST THIRD STREET
DAYTON, OH 45428

Date
01/29/2013

Project No.
552-13-309

Drawing No.
GS2-04



Department of
Veterans Affairs

V/A