

1 PARTIAL MECHANICAL FIRST FLOOR PLAN
SCALE: 1/8" = 1'-0"

KENOTES

- 23100 FIELD LOCATE EXISTING FAN POWERED BOX AND 1-5-20" AIRPORT PRELIMINARY CONTROL VALVE AND PNEUMATIC CONTROLS WITH TWO WAY ELECTRONIC VALVE AND THE INTO DDC.
- 23101 FIELD LOCATE EXISTING VAV BOX AND THERMOSTAT, RETROFIT PNEUMATIC CONTROLS AND THERMOSTAT VAV/ DDC. THROUGH WALL ROW AS COMPENSER. PATCH OPENING EITHER 22 QUOTE SHEET WITH APPLIED WOOD WALL COVERING TO MATCH DEMOUNTABLE PARTITION WALL COVERING, WARPING WALL COVERING AT ALL EDGES OF STEEL SHEET. OR: 0-0-0-0 PRE-FINISHED PAINTED ALUMINUM SHEET WITH ALL EDGES HEAVILY, PROVIDE SHEETS ON BOTH SIDES OF DEMOUNTABLE PARTITION, OVERSIZED 2" AT EACH EDGE OF OPENING AND FASTENED 4 POST MOUNTED WOOD BOLT INSULATION TO COMPLETELY FILL PARTITION CAVITY BETWEEN METAL SHEETS WITHOUT CAUSING SHEETS TO BULGE OR DISTORT.
- 23109 PROVIDE REMOTE WEBS FOR ROOF MOUNTED PUMPS, PFD-1 AND PFD-2, SERVING FLUID COOLERS, FC-1 AND FC-2, FOR COMPUTER ROOM ARE CONDITIONING UNITS.
- 23111 REMOVE STAINLESS STEEL UNIT HEATER AND ASSOCIATED BRASS PIPING.
- 23103 FABRIC DUCTWORK, REMOVE ON DUCTWORK AND CAP AT WALL LOWER. PROVIDE INSULATED BLANK OFF PANELS ON WALL LOWER.
- 23108 PROVIDE DUCT MOUNTED REPEAT COIL FOR EXISTING VAV BOXES AS SCHEDULED.


GENERAL NOTES

1. REFER TO DRAWING 0001 FOR PROJECT GENERAL NOTES.
2. REFER TO DRAWINGS W110 AND W130 FOR BUILDING REFERENCE PLANS.
3. THE FIRST FIGURE OF DUCT SIZE INDICATES DIMENSION OF FACE SHOWN OR INDICATED DUCT SIZES ARE NET INSIDE DIMENSION.
4. TOTAL STATIC PRESSURE NOTED IN SCHEDULES INCLUDES DUCT SYSTEM, TERMINAL UNITS, FILTERS, COILS, ETC.
5. FIELD VERIFY ALL EXISTING LIGHTS, PIPING AND SPRINKLER HEADS, COORDINATE EXACT DUCTWORK AND FABRIC DIFFUSERS WITH FIELD LOCATIONS.
6. KENOTES TYPICALLY ARE NOT DUPLICATED WITHIN A DRAWING. AN UNKNOTED ITEM IS THE SAME AS THE KENOTED ITEM ON THE DRAWING.

KEY PLAN

L	H	D
K	G	C
J	F	B
I	E	A

BUILDING 37



BOX CONSTRUCTION DOCUMENTS FOR BID	08-21-12
601 DESIGN SUBMITTAL	08-09-12
Revisions	Date

CONSULTANTS:

ARCHITECT/ENGINEERS:

Klüber, Inc.
10 S. Springway Ave.
Barrington, Illinois 60010
Tel: 630.406.1213
Fax: 630.406.9472
www.kluberinc.com

Klüber
Architects + Engineers

Drawing Title
BUILDING 37 - PARTIAL MECHANICAL FLOOR PLAN - AREA B

Project Title
HINES BUILDING 37 REPLACE/UPGRADE HVAC UNITS PHASES 1, 2, AND 3

Location
HINES BUILDING AND DEMONITION CENTER

Date
12-06-12

Checked
JKK

Drawn
JKK

Dwg. Number
37 - M312

Dwg. 22 of 58



Office of Construction and Facilities Management