



- A. REFER TO ROOF FINISH AND MATERIAL SCHEDULES FOR PLASTIC LAMINATE SELECTIONS.
- B. PROVIDE BASE, AS LISTED IN ROOF FINISH SCHEDULE, AT ALL CASEWORK.
- C. PROVIDE GROMMETS IN CASEWORK; COUNTERTOPS WHEREVER ELECTRICAL OR COMMUNICATIONS OUTLETS ARE INDICATED IN KNEE SPACE BLOCK. VERIFY LOCATION IN FIELD.
- D. ROUND ALL OUTSIDE CORNERS OF COUNTERTOPS WITH MINIMUM 1/4" RADIUS UNLESS NOTED OTHERWISE.
- E. PROVIDE 1/4" MINIMUM FILLERS AT PERPENDICULAR JUNCTION OF ALL CABINETS AND AT ALL CORNER JOINTS. PROVIDE SUFFICIENT MOUNTING, UNLESS NOTED OTHERWISE. SCORE ALL EDGES AND APPLY SEALANT TO JOINTS.
- F. PROVIDE SEALANT BETWEEN BACKSPLASH / SIDESPLASH OR COUNTERTOP AND WALL.
- G. ALL SHELVING IN CASEWORK TO BE ADJUSTABLE UNLESS NOTED OTHERWISE.
- H. SEE KEY FOR ABBREVIATIONS FOR ADDITIONAL CASEWORK AND EQUIPMENT ABBREVIATIONS.